



LEGEND

	PROPERTY LINE
	6" X 12" CURB AND NAILER
	SYNTHETIC TURF SURFACING
	4' HT. BLACK COATED CHAIN-LINK FENCE
	8' HT. BLACK COATED CHAIN-LINK FENCE
	LIGHT POLE (BY OTHERS)
	GAS
	EXISTING METHANE EXTRACTION LINE
	FUTURE BUILDING
	ELECTRICAL CONDUIT (BY OTHERS)

- KEYNOTES**
1. SYNTHETIC TURF. REFER TO DETAILS AND SPECIFICATIONS.
 2. 8' HEIGHT BLACK COATED CHAIN-LINK FENCE. REFER TO DETAILS AND SPECIFICATIONS.
 3. 4' HEIGHT BLACK COATED CHAIN-LINK FENCE. REFER TO DETAILS AND SPECIFICATIONS.
 4. 10' WIDE FENCE GATE. GATE SHALL EXTEND TO FULL HEIGHT OF FENCE. REFER TO SPECIFICATIONS.
 5. 4' WIDE FENCE GATE. GATE SHALL EXTEND TO FULL HEIGHT OF FENCE. REFER TO SPECIFICATIONS.
 6. FIELD LIGHTING. BY OTHERS.
 7. 6" X 12" CONCRETE CURB AND NAILER. REFER TO DETAIL.
 8. FREE-STANDING, 20' HEIGHT BACKSTOP NETTING. REFER TO PRODUCT LIST.
 9. CONCRETE SIDEWALK. SEE DETAIL.
 10. SOCCER GOALS. REFER TO PRODUCT LIST.
 11. ADJUST POST SPACING AS SUCH THAT NO POSTS ARE DRIVEN WITHIN 4' ON EITHER SIDE OF EXISTING METHANE EXTRACTION LINE.
 12. CORNER FLAGS. INSTALL IN TURF PER MANUFACTURER'S RECOMMENDATIONS.
 13. COMBOX. OFFSET 1' FROM CONCRETE CURB, CENTERED ON THE FIELD. CONTRACTOR TO PROVIDE 3 CONDUIT STUBS FROM COMBOX TO 3 FEET OUTSIDE OF CONCRETE CURB. CONDUIT SHALL BE STEEL RIGID METAL AND INSTALLED AS A MINIMUM STUB-UP IN THE BOX TO ALLOW FOR SEAL-OFF'S TO BE INSTALLED AT A LATER TIME. INSTALL RIGID COUPLING'S WITH METAL PLUGS TO PREVENT CONDUITS FROM FILLING WITH DEBRIS. DUCT TAPE IS NOT ACCEPTABLE.
 14. 20' WIDE GATE. GATE SHALL EXTEND TO FULL HEIGHT OF FENCE. REFER TO SPECIFICATIONS.
 15. PRESERVE, PROTECT, AND MAINTAIN EXISTING LANDFILL GAS INFRASTRUCTURE.

PRODUCT LIST

CONTRACTOR IS RESPONSIBLE FOR THE PURCHASE AND INSTALLATION OF ALL PRODUCTS. SUBMIT PRODUCT INFORMATION INCLUDING COLORS AND FINISHES TO OWNER'S REPRESENTATIVE PRIOR TO PURCHASE AND INSTALLATION.

ITEM	ITEM/MODEL	MANUFACTURER	QUANTITY	COMMENTS
BACKSTOP SYSTEM	CUSTOM	KEEPER GOALS	2	20'H X 90'L FREESTANDING BACKSTOP NETTING. INSTALLATION BY MANUFACTURER.
CORNER FLAGS	CFO-SL	KEEPER GOALS	SET OF 4	CONTRACTOR TO INSTALL USING DRIVEN ANCHORS
COMBOX FOR SYNTHETIC TURF	CBIT1830	SPORTSFIELD SPECIALTIES	1	CONTRACTOR TO INSTALL. CONNECT TO CONDUIT.



CREATE THE VISION TELL THE STORY

jsdinc.com

MILWAUKEE REGIONAL OFFICE
W238 N1610 BUSSE ROAD, SUITE 100
WAUKESHA, WISCONSIN 53188
P. 262.513.0666

CLIENT:
**CITY OF WAUKESHA
PARKS, RECREATION &
FORESTRY DEPARTMENT**

CLIENT ADDRESS:
**130 DELAFIELD STREET
WAUKESHA, WI 53188**

PROJECT:
**MINDIOLA PARK
PHASE II**

PROJECT LOCATION:
**WAUKESHA, WI
WAUKESHA COUNTY**

PLAN MODIFICATIONS:

#	Date:	Description:
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		

Designed By:
Reviewed By:
Approved By:

SHEET TITLE:
SITE PLAN

SHEET NUMBER:

M-C2.0

JSD PROJECT NO: 19-9387



THESE PLANS AND DESIGNS ARE COPYRIGHT PROTECTED AND MAY NOT BE USED IN WHOLE OR IN PART WITHOUT THE WRITTEN CONSENT OF JSD PROFESSIONAL SERVICES, INC.