



City of Waukesha
 Department of Public Works
 130 Delafield Street
 Waukesha, WI 53188
 Waukesha-wi.gov

Contract Change Order

Form C107
 (Rev 01/18)

Project: Greenmeadow Sanitary Interceptor Sewer

Date: 9/3/20

Contract Number: 4071

Branch: Engineering Department

Change Order Number: 9

Contractor: Super Excavators, Inc.

Amount of original contract\$18,461,976.00

Amount of Contract prior this Change Order \$19,655,078.50

Description of change:

Item #1 – Greenmeadow Interceptor Sewer Bid Items

Additional pavement and restoration quantities were requested by the City to remove and replace additional failed sidewalk, curb and gutter, HMA pavement and turf restoration. Paving limits were extended on Greenmeadow Dr to incorporate the additional sewer trench length that was required.

1. Increase of quantity for Line Item #17, Bid Item 03300 – Remove Existing Curb and Gutter
 Description: Increase of 316 LF of curb and gutter removal
 316 LF @ \$10.00/LF\$ 3,160.00

2. Increase of quantity for Line Item #18, Bid Item 03331 – Remove Existing Sidewalk
 Description: Increase of 173 SY of solid rock excavation
 173 SY @ \$20.00/SY\$ 3,460.00

3. Increase of quantity for Line Item #80, Bid Item 07130 – 30" Type A Concrete Curb & Gutter
 Description: Increase of 173 LF of curb and gutter placement
 173 LF @ \$40.00/LF\$ 6,920.00

4. Increase of quantity for Line Item #83, Bid Item 07304 – 4-Inch Concrete Sidewalk
 Description: Increase of 1,097 SF of concrete sidewalk
 1,097 SF @ \$7.00/SF\$ 7,679.00

5. Increase of quantity for Line Item #89, Bid Item 08206 – HMA Pavement
Type 3LT5828H
Description: Increase of 119 tons of HMA binder course
119 tons @ \$250.00/tons.....\$ 29,750.00
6. Increase of quantity for Line Item #90, Bid Item 08208 – HMA Pavement
Type 5LT5828H
Description: Increase of 25 tons of HMA surface course
25 tons @ \$80.00/tons\$ 2,000.00
7. Increase of quantity for Line Item #103, Bid Item 14003 – Topsoil,
Fertilizer, Seed & Erosion Mat
Description: Increase of 3212 SY of topsoil, fertilizer, seed & erosion
mat
3212 SY @ \$6.00/SY\$ 19,272.00
8. Credit for less quantities completed (various items) (\$ 5,407.40)

Dept of Public Works Garage Yard Lot Base Repairs - Greenmeadow Interceptor Sewer Bid Items

Following the directional drill operations in the Department of Public Works garage yard, an area of pavement base course and subgrade required removal and replacement due to unsuitable material prior to repaving the asphalt pavement.

1. Extra No. 10 DPW Yard Lot Base Replacement
Description: Removal and replacement of unsuitable pavement base
material
Lump Sum.....\$ 9,201.95

Joellen Dr Pavement Edge Milling - Greenmeadow Interceptor Sewer Bid Items

On Joellen Dr, the binder course was placed in fall 2019. However, weather temperatures did not permit placement of the surface course. Accordingly, the curb edge and utility structures in the pavement were ramped with temporary asphalt for snow removal operations. In spring 2020, the ramped asphalt was milled off to allow for placement of the surface course.

1. Extra No. 11 Joellen Dr Pavement Edge Milling
Description: Milling of temporary asphalt ramping
1411 LF @ \$4.00/LF.....\$ 5,644.00
- Subtotal\$ 81,679.55

Item #2 – Area 5 Storm Sewer Bid Items

Additional sod restoration was necessary in the median and terrace of S Moreland Blvd due to replacement of five (5) sanitary sewer laterals in conflict with the new 54-inch storm sewer. Additional sod placement was also necessary in Woodfield Park and along Dopp St.

1. Increase of quantity for Line Item #140, Bid Item 14005 – Topsoil and
Sod
Description: Increase of 1129 SY of topsoil and sod
1129 SY @ \$11.00/SY\$ 12,419.00

2. Credit for less quantities completed (various items) (\$ 7,558.95)
Subtotal \$ 4,860.05
Amount of this Change Order \$ 86,539.60
Net Contract Amount after this Change Order \$19,741,618.10

 

City of Waukesha Date
Director of Public Works

 9/8/2020

Contractor Date
Super Excavators, Inc.

