

City of Waukesha

Application for Development Review

Last Revision
Date:
6/18/2018

City of Waukesha Community Development Department - 201 Delafield Street, Suite 200, Waukesha, WI 53188 262-524-3750
City of Waukesha Department of Public Works Engineering Division—130 Delafield Street, Waukesha, WI 53188 262-524-3600
www.waukesha-wi.gov

APPLICANT INFORMATION

Applicant Name: Mr. Myles Multhauf, PM - Facility Planning & Dev.
Applicant Company Name: Froedtert Health, Inc.
Address: 9200 West Wisconsin Avenue
City, State: Wauwatosa, WI Zip: 53226
Phone: (414) 805-2649
E-Mail: Myles.Multhauf@froedtert.com

ARCHITECT/ENGINEER/SURVEYOR INFORMATION

Name: Mr. Mike Franz
Company Name: Kahler Slater Architects
Address: 111 West Wisconsin Avenue
City, State: Milwaukee, WI Zip: 53203
Phone: (414) 290-3739
E-Mail: mfranz@kahlerslater.com

PROPERTY OWNER INFORMATION

Applicant Name: Mr. John A. Balzer, VP - Facility Planning & Dev.
Applicant Company Name: Froedtert Health, Inc.
Address: 9200 West Wisconsin Avenue
City, State: Wauwatosa, WI Zip: 53226
Phone: (414) 805-2649
E-Mail: John.Balzer@froedtert.com

PROJECT & PROPERTY INFORMATION

Project Name: Sunset Drive Health Center
Property Address: SW Corner of Sunset Drive and Genesee Road
Tax Key Number(s): WAKT 1361-982-001
Zoning: _____
Total Acreage: 4.67 Existing Building Square Footage: N/A
Proposed Building/Addition Square Footage: 6,000
Current Use of Property: Vacant Land


PROJECT SUMMARY (please provide a brief project description)

A new free standing, 1 story clinic on the corner of W. Sunset Dr and Genesee Rd. The clinic will be approximately 6,000 SF with 8 exam rooms, 1 treatment room, a lab and staff support spaces.

All submittals require a complete scaled set of digital plans (Adobe PDF) and shall include a project location map showing a 1/2 mile radius, a COLOR landscape plan, COLOR building elevation plans, and exterior lighting photometric maps and cut sheets. A pre-application meeting is required prior to submittal of any applications for Subdivisions, Planned Unit Developments, and Site and Architectural Plan Review. **The deadline for all applications requiring Plan Commission Reviews is at 4:00 P.M, 30 days prior to the meeting date. The Plan Commission meets the Second and Fourth Wednesday of each month.**

APPLICATION ACKNOWLEDGEMENT AND SIGNATURES

I hereby certify that I have reviewed the City of Waukesha Development Handbook, City Ordinances, Submittal Requirements and Checklists and have provided one PDF of all required information. Any missing or incomplete information may result in a delay of the review of your application. By signing this I also authorize The City of Waukesha or its agents to enter upon the property for the purpose of reviewing this application.

Applicant Signature 
Applicant Name (Please Print) Myles Multhauf
Date: 4/22/19

For Internal Use Only:

Amount Due (total from page 2): _____ Amount Paid: _____ Check #: _____
Trakit ID(s) _____ Date Paid: _____

City of Waukesha Application for Development Review

TYPE OF APPLICATION & FEES (CHECK ALL THAT APPLY)

Fees

Please note that each application type has different submittal requirements. Detailed submittal checklists can be found in Appendix A of the Development Handbook.

- Plan Commission Consultation **\$200** _____
- Traffic Impact Analysis _____
 - Commercial, Industrial, Institutional, and Other Non-Residential **\$480**
 - Residential Subdivision or Multi-Family **\$480**
 - Resubmittal (3rd and all subsequent submittals) **\$480**
- Preliminary Site Plan Review \$2,200
 - Level 1: Buildings/additions less than 10,000 sq.ft. or sites less than 1 acre **\$2,200**
 - Level 2: Buildings/additions between 10,001-50,000 sq.ft. or sites between 1.01 and 10 acres **\$2,320**
 - Level 3: Buildings/additions between 50,001-100,000 sq.ft. or sites between 10.01 and 25 acres **\$2,440**
 - Level 4: Buildings/additions over 100,001 sq.ft. or sites greater than 25.01 acres. **\$2,560**
 - Resubmittal Fees (after 2 permitted reviews) **\$750**
- Final Site Plan Review _____
 - Level 1: Buildings/additions less than 10,000 sq.ft. or sites less than 1 acre **\$1,320**
 - Level 2: Buildings/additions between 10,001-50,000 sq.ft. or sites between 1.01 and 10 acres **\$1,440**
 - Level 3: Buildings/additions between 50,001-100,000 sq.ft. or sites between 10.01 and 25 acres **\$1,560**
 - Level 4: Buildings/additions over 100,001 sq.ft. or sites greater than 25.01 acres. **\$1,680**
 - Resubmittal Fees (3rd and all subsequent submittals) **\$750**
- Minor Site or Architectural Plans (total site disturbance UNDER 3,000 total square feet) _____
 - Projects that do not require site development plans **\$330**
 - Resubmittal Fees (3rd and all subsequent submittals) **\$330**
- Certified Survey Map (CSM) \$500
 - 1-3 Lots **\$500**
 - 4 lots or more **\$560**
 - Resubmittal (3rd and all subsequent submittals) **\$180**
 - Extra-territorial CSM **\$260**
- Preliminary Subdivision Plat _____
 - Up to 12 lots **\$1,270**
 - 13 to 32 lots **\$1,390**
 - 36 lots or more **\$1,510**
 - Resubmittal (3rd and all subsequent submittals) **\$630**
- Final Subdivision Plat _____
 - Up to 12 lots **\$660**
 - 13 to 32 lots **\$780**
 - 36 lots or more **\$900**
 - Resubmittal (3rd and all subsequent submittals) **\$480**
 - Extra-territorial Plat **\$540**
- Rezoning and/or Land Use Plan Amendment \$630
 - Rezoning **\$630**
 - Land Use Plan Amendment: **\$630**
- Conditional Use Permit _____
 - Conditional Use Permit with no site plan changes **\$480**
 - Conditional Use Permit with site plan changes **\$480** plus applicable preliminary and final site plan fees above
- Planned Unit Development or Developer's Agreement (Site Plan Review is also required) _____
 - New Planned Unit Development or Developer's Agreement **\$1,760**
 - Planned Unit Development or Developer's Agreement Amendment **\$610**
- Annexation **NO CHARGE**
- House/Building Move **\$150**
- Street or Alley Vacations **\$150**

TOTAL APPLICATION FEES:

\$3,330

City of Waukesha

Development Review Submittal Requirements

PLAN COMMISSION CONSULTATION SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

A Plan Commission Consultation may be submitted for review and comment for the owner/developer to ascertain the feasibility of a proposed project. A consultation is not required but may be submitted in advance of an actual submittal for a preliminary plat, CSM, Planned Unit Development, rezoning, conditional use or site plan. The Plan Commission will only provide feedback, no approvals will be given. Prior to applying for a Plan Commission Consultation you must discuss your project with the Planning Division to determine if a Plan Commission Consultation is recommended.

Review Time: Approximately 30 days

Reviewing Departments: Community Development Planning Division, Public Works Engineering Division, Fire Department, Water Utility.

Reviewing Boards: Plan Commission (optional)

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) copy of the plans you want conceptual review of
- Attachment A: Development Review Checklist. You should also review all other corresponding checklists that relate to the project that you are seeking conceptual review of and include as much information as possible.
- Cover letter outlining project details.

TRAFFIC IMPACT ANALYSIS SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

A Traffic Impact Analysis is required for projects that meet certain criteria. Please refer to the Developer's Handbook Section 4.4 to determine if your project requires a Traffic Impact Analysis

Review Time: Approximately 30 days

Reviewing Departments: Public Works Engineering Division

Reviewing Boards: None, however the Plan Commission may require a copy as part of site plan review process.

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) copy of the Traffic Impact Analysis

PRELIMINARY SITE AND ARCHITECTURAL PLAN SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

Preliminary site and architectural plans are required for any new residential development with 4 or more units and all non-residential developments. Preliminary site plan approval is also required for additions or modifications to existing developments and projects where a stormwater management plan is needed. Preliminary approval is required unless it is determined by City staff in the Pre-Application meeting that the project only needs Final Site and Architectural Review.

Review Time: Approximately 30 days (45 if Common Council review is needed)

Reviewing Departments: Community Development Planning Division, Public Works Engineering Division, Fire Department, Water Utility.

Reviewing Boards: Plan Commission. Common Council and Board of Public Works review may be required for certain projects.

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) that includes of items listed below
 - Cover letter outlining project details.
 - Color architectural elevations of all sides of the building and color perspective renderings
 - Conceptual Landscape Plan
 - Attachment A: Development Review Checklist
 - Site Plan (see Attachment B: Engineering Plan Checklist)
 - Grading Plan (see Attachment C: Site Grading and Drainage Plan Checklist)
 - Stormwater Management Plan (see Attachment D: Stormwater Management Plan Checklist)
 - Utility Plans (see Attachment H: Sewer Plan Review Checklist)
 - Any other attachments as applicable.

FINAL SITE AND ARCHITECTURAL PLAN SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

Final site and architectural plans are submitted only after the Plan Commission has approved Preliminary Site Plans for any new residential development with 4 or more units and all non-residential developments, including modifications to existing developments. Some projects may bypass Preliminary approval but only if it is determined by City staff in the Pre-Application meeting.

Review Time: Approximately 30 days (45 if Common Council review is needed)

Reviewing Departments: Community Development Planning Division, Public Works Engineering Division, Fire Department, Water Utility.

Reviewing Boards: Plan Commission. Common Council and Board of Public Works review may be required for certain projects.

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) that includes of items listed below
 - Cover letter outlining project details.
 - Color architectural elevations of all sides of the building and color perspective renderings
 - Landscape Plan (see Attachment I: Landscape Plan Checklist)
 - Attachment A: Development Review Checklist
 - Site Plan (see Attachment B: Engineering Plan Checklist)
 - Grading Plan (see Attachment C: Site Grading and Drainage Plan Checklist)
 - Stormwater Management Plan (see Attachment D: Stormwater Management Plan Checklist)
 - Utility Plans (see Attachment H: Sewer Plan Review Checklist)

MINOR SITE AND ARCHITECTURAL PLAN SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

Minor Site and Architectural review is intended for projects that may not need the extensive submittal requirements for Preliminary and Final Site Plan approval. Projects that qualify for Minor Site Plan submittal may include landscape, façade and building changes or minor site modifications that don't result in the addition of impervious surface.

Review Time: Approximately 30 days (45 if Common Council review is needed)

Reviewing Departments: Community Development Planning Division, Public Works Engineering Division, Fire Department, Water Utility.

Reviewing Boards: Plan Commission. Common Council and Board of Public Works review may be required for certain projects.

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) that includes of items listed below
 - Cover letter outlining project details.
 - Architectural elevations of all sides of the building being modified
- In addition, depending on the type of project, you may also need the following items:
 - Site Plan (see Attachment B: Engineering Plan Checklist)
 - Landscape Plan (see Attachment I: Landscape Plan Checklist)

CERTIFIED SURVEY MAP SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

A Certified Survey Map may be used to divide up to eight (8) lots in Commercial, Industrial, and Mixed Use zoning districts and up to four (4) lots in all other zoning districts.

Review Time: Approximately 45-60 days. An extension letter will be required if the approval process will take more than 90 days.

Reviewing Departments: Community Development Planning Division, Public Works Engineering Division, Fire Department, Water Utility.

Reviewing Boards: Plan Commission. Common Council and Board of Public Works review may be required for certain projects.

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) that includes of items listed below
 - Attachment E: Certified Survey Map Checklist
 - Attachment A: Development Review Checklist and other attachments as applicable.

**Please note If any exterior architectural, landscape, or site plan changes are required you must also go through Site Plan Review and meet all of those submittal requirements.*

PRELIMINARY PLAT SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

A Preliminary Plat shall be used to subdivide land in the City. The applicant is responsible for submitting the Preliminary Plat to Waukesha County and the State of Wisconsin for review.

Review Time: Approximately 45-60 days. An extension letter will be required if the approval process will take more than 90 days.

Reviewing Departments: Community Development Planning Division, Public Works Engineering Division, Fire Department, Water Utility.

Reviewing Boards: Plan Commission. Common Council and Board of Public Works review may be required for certain projects.

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) that includes of items listed below
 - Attachment F: Preliminary Plat Checklist
 - Cover letter outlining project details.
 - Attachment A: Development Review Checklist and other attachments as applicable
 - Stormwater Management Plan (see Attachment D: Stormwater Management Plan Checklist)

FINAL PLAT SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

A Final plat shall be used to subdivide land in the City. The applicant is responsible for submitting the Final Plat to Waukesha County and the State of Wisconsin for review.

Review Time: Approximately 45-60 days. An extension letter will be required if the approval process will take more than 90 days.

Reviewing Departments: Community Development Planning Division, Public Works Engineering Division, Fire Department, Water Utility.

Reviewing Boards: Plan Commission. Common Council and Board of Public Works review may be required for certain projects.

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) that includes of items listed below
 - Attachment G: Final Plat Checklist
 - Cover letter outlining project details.
 - Attachment A: Development Review Checklist and other attachments as applicable.
 - Stormwater Management Plan (see Attachment D: Stormwater Management Plan Checklist)

REZONING & COMPREHENSIVE PLAN AMENDMENT SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

This review is for any requests to rezone land or amend the City’s Comprehensive Master Plan. For rezonings all property owners within 300 feet of the property will be notified of your request.

Review Time: 45-60 Days

Reviewing Departments: Community Development Planning & Building Inspection Divisions, Public Works Engineering Division, Fire Department, Water Utility.

Reviewing Boards: Plan Commission, Common Council

Additional Information: Rezoning must be done in accordance with the Comprehensive Plan. Please consult with Planning staff to determine if a Comprehensive Plan Amendment is also required prior to submitting a rezoning application.

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) that includes of items listed below
 - Cover letter outlining project details and rationale for rezoning
 - Rezoning Form including legal description and notarized owner(s) signatures (rezoning applications only)
 - Conceptual Plan (if applicable)

**Please note this application fee only covers the rezoning and/or Comprehensive Plan Amendment. If you are proposing site plan changes or are subdividing land you will also need to meet the applicable submittal requirements for those proposals.*

CONDITIONAL USE PERMIT SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

Any use listed as a Conditional Use in Chapter 22 (Zoning Code) requires a Public Hearing in front of the Plan Commission prior to building or occupancy permits being issued. All property owners within 300 feet of the property will be notified of your request.

Review Time: 30-45 days

Reviewing Departments: Community Development Planning & Building Inspection Divisions, Public Works Engineering Division, Fire Department, Water Utility.

Reviewing Boards: Plan Commission

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) that includes of items listed below
 - Conditional Use Permit Application

**Please note If any exterior architectural, landscape, or site plan changes are required you must also go through Site Plan Review and meet all of those submittal requirements.*

PLANNED UNIT DEVELOPMENT OR DEVELOPER’S AGREEMENT SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

The PUD Overlay District is intended to permit development that will, over a period of time, be enhanced by coordinated area site planning, diversified location of structures, diversified building heights and types, and/or mixing of compatible uses. The PUD Overlay District under this Chapter will allow for flexibility of overall development design with benefits from such design flexibility intended to be derived by both the developer and the community, while at the same time maintaining insofar as possible the standards or use requirements set forth in the underlying basic zoning district.

Developer’s Agreements are used for any project that require public infrastructure improvements (sewer, storm sewer, sidewalks, etc) and other off-site improvements such as median openings, traffic signals, street widening, etc..

Review Time: 45-60 days

Reviewing Departments: Community Development Planning & Building Inspection Divisions, Public Works Engineering Division, Fire Department, Water Utility.

Reviewing Boards: Plan Commission, Common Council. Some projects will also require Board of Public Works review.

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) that includes of items listed below
 - Cover letter/statement that outlining project details and all of the required information set forth in the Zoning Ordinance Section 22.52 (4)(a)
 - Rezoning Form including legal description and notarized owner(s) signatures (rezoning applications only)
 - General Development Plan
 - Proposed Supplemental Design Elements (required for all PUDs under the minimum required acreage)

**Please note in addition to the PUD submittal requirements your project will also need additional application fees and submittal materials based on the project type. This may include Preliminary and Final Plats, Preliminary and Final Site and Architectural Plans, Certified Survey Maps, Traffic Impact Analysis. Staff will inform you of any additional submittal requirements at the Pre-Application meeting, which is required prior to submitting your application.*

ANNEXATION SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

Requests for annexation as permitted under Section 66.0217 Wisconsin Statutes.

Review Time: 45-60 days

Reviewing Departments: Community Development Planning & Building Inspection Divisions, Public Works Engineering Division, Fire Department, Water Utility.

Reviewing Boards: Plan Commission, Common Council

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) that includes of items listed below
 - Copy of your State of Wisconsin Request for Annexation Review Application
 - Signed City of Waukesha Direct Annexation Petition
 - Map of property of property to be annexed.
 - A boundary description (legal description of property to be annexed)
 - Any additional information on the annexation.

HOUSE/BUILDING MOVE SUBMITTAL REQUIREMENTS AND ADDITIONAL INFORMATION

Any application to move a home or building from one location to another in the City requires review by staff and the Plan Commission.

Review Time: 30-45 days

Reviewing Departments: Community Development Planning & Building Inspection Divisions, Public Works Engineering Division, Fire Department, Water Utility, Police Department, Any affected Public Utilities

Reviewing Boards: Plan Commission

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) that includes of items listed below
 - Address of existing structure and address of final destination for structure
 - Site Plan showing location of house/building at the new location
 - Proposed route for moving structure. Should also include any overhead wires, mailboxes, or other obstructions that will need to be temporarily relocated to allow for the house/building to get to the new site.

STREET VACATIONS

Street Vacations must be reviewed and approved by the Plan Commission.

Review Time: 45-60 days

Reviewing Departments: Community Development Planning & Building Inspection Divisions, Public Works Engineering Division, Fire Department, Water Utility.

Reviewing Boards: Plan Commission, Common Council

In addition to this application and corresponding application fee you will also need:

- One (1) digital (PDF) that includes a map and legal description of the areas to be vacated.



Attachment A - Application for Development Review Checklist


Project Name: Sunset Drive Health Center
 Engineering Design Firm: Kahler Slater / OTIE

Checklist Items	CSM	Preliminary Plat	Final Plat	Property Survey for Bldg Permit	Storm Water Plan	Erosion Control Plan	Site, Grading, Drainage Plan	Street Plan	Utility Plan	Landscape Plan	Traffic Control Plan	Traffic Impact Analysis	Conditional Use or Home Indus.	PUD or Developer's Ag.	Minor site or Arch. Change	Conditional Use	Rezoning & Comp. Plan Change
Followed Construction Drawing Sheet Layout standards in Development Handbook																	
Followed Development Handbook and Storm Water Ordinance standards for Erosion control plans																	
Obtained geotechnical evaluation for storm water and pavement design																	
Followed Development Handbook standards, and Wisconsin Administrative Code for Property Survey																	
Verified proposed basement floor elevation is at least 1 foot above the highest seasonal high water table elevation																	
Followed Development Handbook standards and Ordinance for Preliminary Plat																	
Followed Site, Grading, and Drainage Plan design standards in Development Handbook and Storm Water Ordinance																	
Followed Traffic impact analysis standards in Development Handbook																	
Specifications conform to current City Standard Specifications																	
Followed Lighting Plan standards in Development Handbook																	
Development site contains Contaminated Waste																	
Followed storm water management requirements in Development Handbook, and Ordinance																	
Site contains mapped FEMA floodplain or a local 100-year storm event high water limits																	
Site contains wetlands or Natural Resource limits (ie. Primary, Secondary, Isolated , shoreland limits)																	
CSM follows standards in Development Handbook, City Ordinance, and State Statutes																	
Followed Development Handbook standards for Street plans and profiles																	
Followed Development Handbook standards for utility plans and profiles																	
Existing sanitary sewer lateral has been televised																	

PLANNING


PERMITTING

CONSTRUCTION



LEGEND

- DEVELOPER'S ACTION ITEM
- PUBLIC MEETINGS
- CITY PLANNING / COMMUNITY DEVELOPMENT
- CITY FIRE DEPT
- CITY ENGINEERING
- WAUKESHA WATER UTILITY
- CITY'S ACTION ITEM



City of Waukesha
 Department of Public Works
 130 Delafield Street
 Waukesha, WI 53188
 Waukesha-wi.gov

Engineering Plan Checklist

Attachment B
 (Rev 12/18)

Project Name: Sunset Drive Health Center

Engineering & Design Firm: Kahler Slater / OTIE

General Information

Plans shall include the seal and signature of the Wisconsin licensed professional engineer responsible for the preparation of the construction plans on the cover sheet or on each sheet

YES	NO	N/A	
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Provide a copy of the WisDOT permit for any work in the State of Wisconsin right of way.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide a copy of the Waukesha County Department of Public Works permit for any work in right of way of Waukesha County. (in process)
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide a copy of Wisconsin Department of Natural Resources Water Resources Application for Project Permits (WRAPP) for all sites greater than one acre. (by contractor prior to construction)
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Provide a copy of US Army Corps of Engineers 404 permit.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide cross access agreements for use of entrances.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Provide off-site utility easements. (on ALTA survey)
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Provide hydraulic gradeline calculations for all storm sewer pipes signed and sealed by a professional engineer licensed in the State of Wisconsin. (sealed for final submittal)
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Provide a storm water management plan and calculations signed and sealed by a professional engineer licensed in the State of Wisconsin. (sealed for final submittal)

All Plan Sheets

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Plans prepared on sheets measuring 11" high by 17" wide or no larger than 24" high by 36" wide.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Sanitary Sewer, watermain and storm sewer system plans for the entire development are included.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	A profile view is located below a plan view on plan and profile sheets and both views are aligned by stationing whenever possible. In general, stationing is from left to right.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Plan and profile sheets start and terminate at match lines.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	The assumed bearing base, control monuments and stationing reference line(s)
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Right-of-way limits and easement limits
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Edge of pavement or flange, face and back of curb
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Name of each existing, proposed, and future roadway and any intersecting roadways
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Lot lines, lot and block numbers
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Addresses and names of Owners for existing parcels

<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	All obstructions located within the project limits including, but not limited to: trees, signs, utilities, fences, light poles, structures, etc.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	A note warning that underground utilities must be located by "Diggers Hotline" prior to start of construction
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Legend (relevant to each sheet) showing all special symbols, line types and hatch used
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Title block includes at a minimum, the following information: Name and address of engineering (design) firm and owner/developer Date of the drawing and last revision Scale Plan sheet number (# of #) Name and location description of development
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	North to the top or right of the sheet and shown by a north arrow, clearly shown without intrusion.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Scale of the plans 1" = 40' horizontally and 1" = 8' vertically for 11" by 17" plan sheets and 1" = 20' horizontally and 1" = 4' vertically for 22" by 34" sheets. Partial site plans have a scale of 1" = 20' or larger. The scale of details is such that the detail is clearly shown. The scale is shown with a line scale and text.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Existing surface objects indicated with screened lines and clearly labeled.

Cover Sheet

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Project title.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location Map (Proximity to two main streets minimum).
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Index of all plan sheets
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	For large or phased subdivisions, a key map of layout and phases.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	A minimum of two (2) current SEWRPC reference benchmarks. Survey documentation of tie to Wisconsin State Plane Coordinate System, South Zone (horizontal) and City of Waukesha datum (vertical) provided. Elevations shown based on City of Waukesha datum.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	All permanent or temporary benchmarks and elevations.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	A description of the locations of the benchmarks; and the basis or origin of the vertical control network.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Date of plan preparation and applicable revision date(s)
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The following statement: " <i>All site improvements and construction shown on the plans shall conform to the City of Waukesha <u>Development Handbook & Infrastructure Specifications</u>. Where the plans do not comply, it shall be the sole responsibility and expense of the Developer to make revisions to the plans and/or constructed infrastructure to comply.</i> " (to be added for final submittal)

Roadway

YES	NO	N/A	
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	For all new streets, a site specific geotechnical evaluation and pavement design submitted with the plans.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	A separate detail sheet showing typical cross-sections for each roadway standard width and cul-de-sac if applicable.

Plan View


YES	NO	N/A	
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	The assumed bearing base, control monuments and stationing reference line along the centerline of the roadway, including cul-de-sacs.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	At least one clearly labeled benchmark or control point per sheet.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Pavement and median dimensions.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Final grade elevations at 25' intervals at the right-of-way including at the edge of pavement for rural sections or at the flange of curb for urban sections.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Final grade elevations for cul-de-sacs at 25' intervals at the right-of-way including at the edge of pavement for rural sections or at the flange of curb for urban sections.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Label all PVC's, PVT's, and PC's, PT's for vertical and horizontal curves. Radii of all intersections (edge of pavement or flange of curb, with note indicating which is referenced).
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Driveways for all lots adjacent to storm inlets and intersections.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Sidewalks labeled and dimensioned.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Existing, proposed, future streets and drives labeled and dimensioned.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	All roadside ditch locations, flowline elevations at 50' intervals of the ditches.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Slope intercepts.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Invert profile for 200' downstream for any existing ditches receiving flow from a proposed road or street.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Limits of any areas which need special stabilization techniques.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Specific details of all existing connected roadways. Pavement, shoulders, ditches, curb alignment, and grades shall be shown as needed to adequately make the transition.

Intersection Details

YES	NO	N/A	
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Radii of all intersections (edge of pavement or flange of curb, with note indicating which is referenced).
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Sidewalks and accessible ramps labeled and dimensioned.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Right of way corner clips and sight visibility easements.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Spot grades as necessary to ensure proper drainage and compliant ADA slopes.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Spot grades shall be shown at end of radius for all curb and gutter and the end radius for all back of sidewalk.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Drainage clarified by flow arrows, high points, sags, ridges, etc. Slope intercepts shall be clearly labeled by station, elevation to the nearest 0.1', and offset distance (left or right) from the reference line.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Invert elevation of ditches (for rural roadway).
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Final subgrade elevation at the centerline of the street or roadway.

Cross Sections

YES	NO	N/A	
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Right of way limits.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Slope intercepts clearly labeled.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Elevations to the nearest 0.01'.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Offset distance (left or right) from the reference line.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Final grade elevations at back of walk, face of walk, top of curb, flange elevation (edge of pavement for rural section), and the centerline of the street or roadway.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Cross slope of sidewalk, terrace area, and roadway.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Invert elevation of ditches (for rural section)



City of Waukesha
 Department of Public Works
 130 Delafield Street
 Waukesha, WI 53188
 Waukesha-wi.gov

Site, Grading and Drainage Plan Conditional Use Permit Checklist

Attachment C
 (Rev 12/18)

Project Name: Sunset Drive Health Center

Engineering & Design Firm: Kahler Slater / OTIE

General Requirements

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Applicant's name
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Name and location of development
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Scale and north arrow
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Date of original and revisions noted
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	License number and professional seal (to be sealed for final submittal)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Digital Drawings in AutoCAD format of the site layout & building plan layout
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Pay impact fees

Building Plans

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Contact Community Development Department

Site Plans

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Dimensions of development site
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location, footprint, and outside dimensions
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Existing and proposed pedestrian access points
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Existing and proposed vehicular access points
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Parking lots, driveways shown
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Front, side and rear yard setbacks shown and labeled
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location, identification and dimensions of all existing or planned easements
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Identification of all land to be dedicated
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location, elevation, and dimensions of walls and fences
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location of outdoor lighting with lighting design plan and calculations
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Sign complies with City Code Book (to be completed for final submittal)
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Location of existing and proposed signs (to be completed for final submittal)

Site Access

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Legal description or certified survey of property
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Development compatible with its zoning district (rezoning is part of concurrent submittal)
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Sidewalks to be shown
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Site entrance drive dimensions
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Individual development vehicular entrances at least 125 feet apart
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Adjacent development share driveway where possible
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	At least one vehicular and pedestrian access point to each adjoining site granted by cross easements
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Cross access to be provided with minimum paved width of 24 feet
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Design detail for all new public streets

Parking/Traffic

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	5-foot wide (min) paved walkway to building entrance
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	7-foot parking separation from front of building
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Minimum parking spaces provided
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Service truck parking in designated service areas
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Parking spaces and layout dimensioned
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Lot paved with HMA or concrete
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Handicap parking provided
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Minimum required stacking distance
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Concrete curb and gutter around parking lot

Grading and Drainage Plans

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Show existing tree lines and any obstructions (fences, structures, power poles, etc.) within the project limits.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	All proposed lot lines and lot numbers or addresses
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Lot line dimensions
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Outline of buildable areas for each lot
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Typical setbacks of buildable area to front, side and back lot lines
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	All existing buildings, structures and foundations
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	All existing drainage channels and watercourses
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Emergency overflow routes
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Drainage clarified by flow arrows, high points, sags, ridges, and valley gutters
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Proposed retaining wall locations with top and bottom of wall elevations at key locations
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	100-year flood plain limit (both pre-and post-project)
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	100-year storm water surface elevation
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Wetlands. Wetland limits labeled with bearings and distances and dimensioned to lot lines. Bearings and distances may be shown in tabulated format.

<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	All environmental corridors, & or environmentally sensitive areas as required by DNR
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	All existing and proposed easements.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Existing topography of the site and all areas within 50 feet of the site shown at a one foot contour interval using City of Waukesha datum. Existing contours shown as thin, dashed screened or grey lines with a readily discernable heavier line used for the 5-foot contour intervals.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Proposed grading shown at a contour interval of 1 foot using City of Waukesha datum. Proposed contour lines shown as solid medium lines, with a discernible heavier line use for the 5-foot contour intervals.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	The yard grade and first floor elevation of proposed building and any existing buildings located within 150 feet of the parcel boundary.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Proposed road(s), curb and gutter, all storm sewer grates and storm sewer manholes (or cross-culverts for open ditches). Show any off-road storm inlets and discharge locations with surface entry elevations.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Spot grades as necessary to ensure proper drainage and compliant ADA slopes and routing where applicable.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	At front setback line show a typical house shell on each lot and the proposed yard grade to the nearest tenth of a foot (assumed to be 0.7' below the top of block) for each building. Show proposed finished elevations to the nearest tenth of a foot at all lot corners and alongside lot lines adjacent to the front and back corners of the typical house. Show proposed finished elevations to the nearest tenth of a foot at high and low points along any side or back lot lines, and at high and low points if roads to demonstrate proposed drainage.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	The grading plan for any house that will require special design due to topography, clearly show separate grades for the garage and yard grade if extra steps are needed. Separate spot finish elevations shown for rear or side exposure or walkout.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate minimum finished floor elevations adjacent to floodplains, ponds, creeks/channels, etc.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Proposed storm inlets shown on each grading plan. Each plan also includes specific details on all applicable retention/detention basins, ponds, overflows, etc. Separate sheets or notes as required.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Locations of existing and proposed streets, drives, alleys, easements, right-of-way, parking as required, vehicular and pedestrian access points, and sidewalks
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Outline of any development stages
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Location and details on any required emergency access roads
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Soil characteristics
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Existing and proposed topography shown for the site and or adjacent properties
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Floodplain, shore land, environmental and wetlands shown
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location and dimensions of on-site storm water drainage facilities
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location and footprint of all existing buildings
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Locations and species of existing trees (species not identified)
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Berm detail
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Lot grades and swales shown
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Drainage calculations provided

Erosion Control

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location Map
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Soils Survey Map
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Existing Land Use Mapping
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Predeveloped Site Conditions
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<ul style="list-style-type: none"> Existing contours
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<ul style="list-style-type: none"> Property lines
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<ul style="list-style-type: none"> Existing flow paths and direction
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<ul style="list-style-type: none"> Outlet locations
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<ul style="list-style-type: none"> Drainage basin divides and subdivides
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<ul style="list-style-type: none"> Existing drainage structures on and adjacent to the site
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<ul style="list-style-type: none"> Nearby watercourses
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<ul style="list-style-type: none"> Lakes, streams, wetlands, channels, ditches, etc.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<ul style="list-style-type: none"> Limits of the 100-year floodplain
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Practice location/layout/cross sections
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Construction Details
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Name of receiving waters
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Site description/Nature of construction activity
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Sequence of construction
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Estimate of site area and disturbance area
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Pre- and post-developed runoff coefficients
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Description of proposed controls, including
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<ul style="list-style-type: none"> Interim and permanent stabilization practices
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<ul style="list-style-type: none"> Practices to divert flow from exposed soils
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<ul style="list-style-type: none"> Practices to store flows or trap sediment
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<ul style="list-style-type: none"> Any other practices proposed to meet ordinance
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Existing topography of the site and all areas within 50 feet of the site shown at a one foot contour interval using City of Waukesha datum. Existing contours shown as thin, dashed screened or grey lines with a readily discernable heavier line used for the 5-foot contour intervals.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Proposed grading shown at a contour interval of 1 foot using City of Waukesha datum. Proposed contour lines shown as solid medium lines, with a discernible heavier line use for the 5-foot contour intervals.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	List the total disturbed acreage including offsite areas.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Provide free survey in accordance with City Erosion Control Ordinance
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Proposed limits of disturbance including proposed tree cutting areas.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Location and dimensions of all temporary topsoil and dirt stockpiles.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location and dimensions of all appropriate best management practices (BMP).
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Phasing of BMP's with the construction activities listed / described.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Schedule of anticipated starting and completion date of each land disturbing and land developing activity, including the installation of the BMP measures that are needed.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location of all channels, pipes, basins or other conveyances proposed to carry runoff to the nearest adequate outlet, including applicable design assumptions and computations.


<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Areas to be sodded or seeded and mulched or otherwise stabilized with vegetation, describing the type of final vegetative cover.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Areas of permanent erosion control (other than vegetation).
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Boundaries of the construction site
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Drainage patterns/slopes after grading activities
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Areas of land disturbance
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Locations of structural and nonstructural controls
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Drainage basin delineations and outfall locations


Optional Submittals as Determined by Review Authority

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Traffic impact analysis
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Environmental impact statement
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Soil and Site Evaluation Report per DNR Technical Standard 1002
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Plot of effect of exterior illumination on site and adjacent properties
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Description of any unusual characteristics
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Street perspectives showing view corridors
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Historic site
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Economic feasibility study
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Contaminated Waste Site

I hereby certify that I have reviewed the City ordinances and provided one (1) full-sized set of all required information along with all the required reduced copies of plans.

Applicant's Signature: _____





City of Waukesha
 Department of Public Works
 130 Delafield Street
 Waukesha, WI 53188
 Waukesha-wi.gov

Stormwater Management Plan

Attachment D
 (Rev 12/18)

Project Name: Sunset Drive Health Center

Engineer & Design Firm: Kahler Slater / OTIE

STORM WATER MANAGEMENT PLAN WORKSHEET

The City of Waukesha requires a Stormwater Management Plan to be submitted with the proposed development plans for site plan review. A Stormwater Management Plan is a document describing the storm water management practices constructed and implemented within the proposed development to ensure compliance with the storm water management criteria, as set forth by the City of Waukesha. The purpose of a Stormwater Management Plan is to protect the safety and health of the public, property and aquatic environment from the threats due to storm water from land development activity. The worksheet will provide a basis to the information that shall be provided when preparing a Stormwater Management Plan for a proposed development. This Plan shall include a set of complete plans and calculations, stamped by a registered professional engineer.

Stormwater Management Plans are required as listed in City Code Book Chapter 32.06(b)

Exemptions for Design and Plan Requirements

YES	NO	N/A	
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Site is associated with agricultural or silvicultural activities

Design Requirements: Total Suspended Solids

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Site is a New Development – 80% Reduction must be met
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Site is an Infill Development – 80% Reduction must be met
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Site is a Redevelopment – 40% Reduction must be met
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Site has areas of New Development and Redevelopment
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Calculations for % Reduction are included in the plan (WinSLAMM input and output)
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Storm water Management Facilities to address TSS removal are designed according to Chapter 32 of the City Code Book and DNR Technical Standards – Check all that apply: <ul style="list-style-type: none"> <input type="checkbox"/> Wet Detention Basin <input type="checkbox"/> Bio Retention Basin <input type="checkbox"/> Swales <input checked="" type="checkbox"/> Proprietary Devices <input checked="" type="checkbox"/> Other (specify): <u>Dry Pond</u>

Design Requirements: Peak Discharge

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Storm water Management Facilities to address Peak Discharge are designed according to Chapter 32 of City Code Book and DNR Technical Standards – Check all that apply: <ul style="list-style-type: none"> <input type="checkbox"/> Wet Detention Basin <input type="checkbox"/> Bio Retention Basin <input type="checkbox"/> Swales <input checked="" type="checkbox"/> Other (specify): <u>Dry Pond</u>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Downstream Capacity for 2-year, 10-year and 100-year, 24-hour design storms are met
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Calculations of available capacity, proportional share, and proposed utilized capacity under all design storms are included in plan
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Calculations of Peak Discharge are included in the plan

Design Requirements: Infiltration			
YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Hydraulic Soil Type: <input type="checkbox"/> Soil Type A – Proceed <input type="checkbox"/> Soil Type B – Proceed <input checked="" type="checkbox"/> Exemption or Exclusion – Provide documentation
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Site and Soil Evaluation Report per DNR Technical Standard 1002
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Low Imperviousness. Ex: low density residential parks, cemeteries Post-Development Infiltration Performance Standards: <input type="checkbox"/> Up to 40% Connected Impervious Surface <input type="checkbox"/> 90% of Pre-Development Infiltration volume met <input type="checkbox"/> 1% of site – Maximum Effective Infiltration Area
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Medium Imperviousness. Ex: Medium and high density residential, multi-family, industrial, institutional, office park. Post-Development Infiltration Performance Standards: <input type="checkbox"/> 40%-80% Connected Impervious Surface <input type="checkbox"/> 75% of Pre-Development Infiltration volume met <input type="checkbox"/> 2% of site – Maximum Effective Infiltration Area
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	High Imperviousness. Ex: commercial strip malls, shopping centers, commercial downtowns Post-Development Infiltration Performance Standards: <input checked="" type="checkbox"/> Greater than 80% Connected Impervious Surface <input type="checkbox"/> 60% of Pre-Development Infiltration volume met <input type="checkbox"/> 2% of site – Maximum Effective Infiltration Area
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Site has parking lots and new road construction: <input checked="" type="checkbox"/> Pretreatment included <input type="checkbox"/> 10% Infiltration of the runoff from the tow-year, 24-hour design storm with Type II Distribution
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Calculations of Infiltration Volumes are included in the plan and model input and output (WinSLAMM)
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Exclusions for Infiltration: <input type="checkbox"/> Tier 1 Industrial Facility <input type="checkbox"/> Storage and Loading Areas of Tier 2 Industrial Facility <input type="checkbox"/> Fueling and Vehicle Maintenance Facility <input type="checkbox"/> Areas within 1,000 feet up gradient of Karst Features <input type="checkbox"/> Areas within 100 feet downgradient of Karst Features <input type="checkbox"/> Areas with < 3 feet of separation from bottom of Infiltration System to seasonal high groundwater or top of bedrock (does not prohibit roof runoff) <input type="checkbox"/> Areas with runoff from industrial, commercial and institutional parking lots and roads with < 5 feet separation from bottom of infiltration system to elevation of seasonal high groundwater or top of bedrock <input type="checkbox"/> Areas within 400 feet of community water system well <input type="checkbox"/> Areas within 100 feet of private well <input type="checkbox"/> Areas where contaminants of concern (defined by NR720.03(2) are present in the soil through which infiltration will occur) <input type="checkbox"/> Area where soil does not meet any of the following characteristics between bottom of infiltration system and seasonal high groundwater and top of bedrock: <input type="checkbox"/> <i>At least 3-foot soil layer with 20% fines or greater</i> <input type="checkbox"/> <i>At least 5-foot soil layer with 10% fines or greater</i>

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Exemptions for Infiltration: <ul style="list-style-type: none"> <input checked="" type="checkbox"/> Areas where infiltration rate < 0.6 inches/hour <input type="checkbox"/> Parking Areas and Access Roads less than 5,000 square feet for commercial and industrial <input type="checkbox"/> Redevelopment Post-Construction Sites <input type="checkbox"/> Infill Development < 5 acres <input type="checkbox"/> Infiltration during periods when soil on the site is frozen <input type="checkbox"/> Roads in commercial, industrial and institutional land uses <input type="checkbox"/> Arterial Roads in Residential land uses
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Storm water Management Facilities to address Infiltration are designed according to Chapter 32 of the City Code Book and DNR Technical Standards – Check all that apply: <ul style="list-style-type: none"> <input type="checkbox"/> Bioretention Basin (1004) <input type="checkbox"/> Infiltration Basin (1003) <input type="checkbox"/> Infiltration Trench (1007) <input type="checkbox"/> Permeable Pavement (1008) <input type="checkbox"/> Rain Garden (1000) <input type="checkbox"/> Other (specify): _____

Design Requirements: Protective Areas

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Impervious areas are outside protective area. If not, provide a written explanation.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Land disturbing activities are within a protective area. If Yes , check all that apply: <ul style="list-style-type: none"> <input type="checkbox"/> If no impervious area is within protective area, adequate sod or self-sustaining vegetative cover of 70% or greater shall be established. <input checked="" type="checkbox"/> Adequate sod or self-sustaining vegetative cover is sufficient for bank stability, maintenance of fish habitat and filtering of pollutants from upslope overland flow areas under sheet flow conditions. <input type="checkbox"/> Non-Vegetative materials are employed on the bank as necessary to prevent erosion (steep slopes, high velocity areas).
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Best Management Practices are located within the protective area – Check all that apply: <ul style="list-style-type: none"> <input type="checkbox"/> Filter Strips <input type="checkbox"/> Swales <input type="checkbox"/> Wet Detention Basins <input checked="" type="checkbox"/> Other (specify): <u>Dry pond</u>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Non-Applicable Areas Apply: <ul style="list-style-type: none"> <input type="checkbox"/> Structures that cross or access surface water (boat landing, bridge, culvert) <input type="checkbox"/> Structures constructed in accordance with Section 59.692(1v) Wisconsin Statutes: <input checked="" type="checkbox"/> Post-Construction Runoff does not enter surface water except to the extent that vegetative groundcover necessary for bank stability

Design Requirements: Fuel and Maintenance Facilities

YES	NO	N/A	
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Are Fuel and Maintenance Facilities on the Site?
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Are Best Management Practices designed to reduce petroleum within runoff (no visible sheen)?


Design Requirements: Swale Treatment for Transportation Facilities			
YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<p>Does the site use swales for runoff conveyance and pollutant removal for transportation facilities? If Yes, must have the following:</p> <p><i>Groundcover:</i></p> <ul style="list-style-type: none"> <input checked="" type="checkbox"/> Vegetated <input type="checkbox"/> Non-Vegetated where appropriate to prevent erosion or provide runoff treatment (riprap, check dams) <p><i>Swale Velocity Control:</i></p> <ul style="list-style-type: none"> <input checked="" type="checkbox"/> Swale is 200 feet or more in length with a velocity no greater than 1.5 feet per second for the two-year, 24-hour design storm or two-year storm with duration equal to time of concentration <input type="checkbox"/> Swale is 200 feet or more in length with velocity > 1.5 feet per second then velocity is reduced to maximum extent practicable. Written explanation stating why requirement of > 1.5 feet per second cannot be met
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<p>Exemptions Apply:</p> <p>Average Daily Vehicles > 2,500 and initial surface water of the state that runoff directly enters is any of the following:</p> <ul style="list-style-type: none"> <input type="checkbox"/> An outstanding resource of water (ORW) <input type="checkbox"/> An exceptional resource water (ERW) <input type="checkbox"/> Water is listed in Section 303(d) of the Federal Clean Water Act and is identified as impaired in whole or in part due to non-point source impacts <input type="checkbox"/> Water where targeted performance standards are developed under NR 151.004 of the Wisconsin Administrative Code to meet water quality standards
Plan Requirements			
YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Provide permit application form, including contact information (name, address, telephone number) for the landowner, developer, land operator, certified project engineering, responsible party for installation of storm water management practices, responsible party for long-term maintenance of the storm water management practices.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Legal Description of proposed development.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Narrative describing the proposed development.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Brief summary of Design Criteria and methods used for development of Storm Water Management Practices.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Storm Water Management Maintenance Agreement shall be included with the Storm Water Management Plan (see Storm Water Management Maintenance Agreement template for additional information required).
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Certification by a Wisconsin registered professional engineer.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Financial Guarantee.

Description and Site Characteristics for Pre/Post Development conditions shall be delineated by one (1) or more site maps at a scale of not less than one (1") inch equals two hundred (200') feet. The map(s) shall include, at minimum, the following information:

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Site Location and Legal Description.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Pre-developed and revised topography by contours related to USGS survey datum or other datum approved by City. The topographic contours of the site shall not exceed 2 feet. The topography shall extend at minimum 100 feet outside the site boundaries to show runoff patterns onto, through and from the site.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	One hundred (100) year Floodplain boundary, shore land, environmental corridors, and wetland boundaries shall be delineated if applicable
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	All lakes, streams, and other water bodies illustrated on map shall be named as defined on a USGS 7.5 minute topographic map.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Predominant Soil Types and Hydraulic Soil Group Classifications per NRCS
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Coordinates of all manhole and inlets with reference to two nearest reference point monuments which shall be Section or ¼ Section corners.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location, capacity, and dimensions/details of on-site Pre-developed and Post-developed storm water management facilities such as, but not limited to, the following: manholes, pipes, curbs, gutters, curb inlets, filter strips, swales, detention basins, curb cuts, and drainage gates.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location, extent, detailed drawings, typical cross sections and slope ratios of all pre-developed and post-developed storm water retention and detention areas and drainage ways – list inlet/outlet elevations, permanent water surface elevation, high water surface elevation, and emergency spillway elevation, if applicable.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location and Elevations at top and bottom of pre-developed and post-developed buildings and structures.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Locations and names of pre-developed and post-developed streets and intersections and the location of parking lots, sidewalks, bike paths and impervious surfaces (excluding single family residences). Map(s) shall clearly differentiate pre-developed and post-developed surfaces.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Delineation and dimensions of all pre-developed and post-developed property boundaries, easements, right-of-way, building setbacks, maintenance easements, and other restrictions.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Pre-developed and post-developed land use boundaries, including cover type and condition.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Post-developed land use cover totals for Impervious and Pervious areas as well as permanent water surface area of all storm water management facilities.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Delineation of pre-developed and post-developed watershed and sub-watershed boundaries used in determination of Peak flow discharges and discharge volumes from the site. (If the watershed extends beyond the site boundaries, a separate watershed map can be supplied).
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location of the pre-developed and post-developed discharge points.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Pre/Post developed directional Flow Paths used to calculate existing/proposed time of concentrations.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location of the Emergency Overland Flow.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Location of any Regional Treatment Options (if applicable).
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Identify all pre-developed land cover features, such as, natural swales, natural depressions, native soil infiltrating capacity and natural groundwater recharge areas.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Location of any protective areas within the site.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Location of wells located within 1,200 feet of pre-developed and post-developed Storm Water Detention Basins, Infiltration Basins, or Infiltration Trenches.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Delineation of Wellhead protection areas defined under NR 811.16

Supportive Information and Calculation summaries shall be supplied for all storm water management requirements as dictated in the checklist under Design Requirements:

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Pre-developed and post-developed watershed, sub-watersheds, and land use areas (acres, watershed shall be delineated by property lines).
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Pre-developed and post-developed impervious areas (acres).
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Pre-developed and post-developed Runoff Curve Numbers.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Pre-developed and post-developed Time of Concentration.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Pre-developed and post-developed peak flows for the 2-year, 10-year and 100-year, 24-hour storm events for each discharge point.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Total suspended solids removal computations to show compliance.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Design computations for the runoff volume of the pre-developed and post-developed conditions to show compliance with the infiltration requirements.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Design computations for all storm water drainage facilities such as, but not limited to, inflow/outflow rates, hydrographs, water surface elevations, outlet design computations, runoff discharge volume, velocities, and stage/storage data.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Design computations for the 10-year Rational Method flows for all proposed storm conveyance systems.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Computation of the available downstream capacity flowing full, overflow level of ditches and the top of the upstream end of the pipe for any culverts.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Computation of the downstream capacity using the 5-year rational storm.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Tail water analysis included in storm water design for 2-year, 10-year and 100-year storm events.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Design computations to illustrate compliance with pollutant loading criteria (Storm Water Quality Management practices) with pre- and post-storm water management facilities.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Narrative describing all assumptions that were deemed appropriate for design.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Explanation of provisions to preserve and use natural topography and land cover features.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Explanation of restrictions on Storm Water Management practices by wellhead protection plans (if applicable).
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Results of investigations of soil and groundwater required for installation of Storm Water Management practices.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Impact assessment results on Wetland Functional Values (if applicable).
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Storm Water Management practices installation schedule.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Cost estimate for the construction, operation and maintenance of each Storm Water Management practice.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Any additional information that the City, or designee, may need to evaluate the impacts of the storm water discharge quality and quantity on the existing area and existing utilities.



City of Waukesha
 Department of Public Works
 130 Delafield Street
 Waukesha, WI 53188
 Waukesha-wi.gov

Certified Survey Map Checklist

Attachment E
 (Rev 12/18)

Project Name: Sunset Drive Health Center

Engineer & Design Firm: Kahler Slater / OTIE


Surveyor: Sigma

Checklist to be completed and signed:

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Scale and north arrow
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Scale of plans less than or equal to 1" = 100'
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Date of original and revisions noted
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Certification from surveyor that Plat complies with State Statute 236
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Digital PDF submitted
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location of all existing structures and first floor elevations
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Location of utility and drainage easements
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Exact length and bearing of the centerline of all streets
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Exact street width along the line of any obliquely intersecting street
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Railway rights-of way within and abutting the plat
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Location and size of all lands to be dedicated for public use (when required)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Comprehensive site grading drainage plan
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Special restrictions relating to access control, planting strips, restrictive yard requirements, etc. (when required)
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Map shows entirety of all parcels in proposed certified survey map
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Major street setback or WisDOT setbacks (if applicable)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Floodplain limits of the 100-year recurrence interval flood
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location of any wetlands, shore land, or other environmental areas (if applicable)

Plans to be submitted (when applicable):

YES	NO	N/A	
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Street plans and profiles
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Sanitary sewer plans and profiles
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Storm sewer plans
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Grading and drainage plans
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Water main plans and profiles
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Erosion control plans
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Landscape plans



City of Waukesha
 Department of Public Works
 130 Delafield Street
 Waukesha, WI 53188
 Waukesha-wi.gov

Sewer Plan Review Checklist

Attachment H
 (Rev 12/18)

Project Name: Sunset Drive Health Center

Engineering & Design Firm: Kahler Slater / OTIE

Sanitary System

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Minimum 4" sanitary sewer lateral from the main to the property line, PVC SDR 26 or 35 conforming to ASTM standards D 3034 with rubber gasket joints
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Sanitary sewer laterals shall have a green #12 locator wire installed along the entire length. Locator wire shall be brought to the surface at the edge of the building and enclosed in a curb box with "sewer" on the cover.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Sampling manhole required for all food service developments (or developments with the potential to become food service) and industrial/manufacturing facilities.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Industrial facilities must complete an industrial discharge form.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Outside drop manhole connection required where drop is greater than 24 inches.
Sanitary Plan View			
YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Ghost existing utilities and lateral locations in screened format. Label the pipe size of existing utilities.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Label the proposed sewer and laterals with length, size, and material type
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Material and size of the existing sanitary sewer being connected to.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Label the stub-outs with length, size, slope, and invert elevations (if not profiled).
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Dimensions showing offset from right-of-way to the sewer and separation distance between other utilities.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Show type and size of encasement where needed
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Show flow directions of all proposed mains.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Length of each sewer lateral and height of any lateral risers. Label proposed invert elevations at right-of-way lines.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Distance from downstream manhole to each upstream sewer lateral.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Proposed manholes and cleanouts labeled with a design plan number. Existing manholes labeled with numbers obtained from City records.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Rim and invert elevations at each manhole, based on City of Waukesha datum (for private sewer if not profiled)
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Show and label all easements
Sanitary Profile View			
YES	NO	N/A	
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Stationing.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Existing and proposed surface profiles and elevations over the sewer.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	All utility crossings. Label elevations if known.

<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Pipe material / class, size, length, and percent grade to two (2) decimal places.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Material and size of the existing sanitary sewer being connected to.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Length, type, and size of encasement as needed.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Proposed manholes. Indicate type and diameter.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label station, rim, and invert elevations, based on City of Waukesha datum, and design plan number for each manhole and cleanout. Existing manholes to be labeled with numbers obtained from City records.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Limits of gravel and/or slurry backfill.
Sanitary for Subdivisions/Large Developments			
<i>(Complete copies of City specifications for sanitary sewer are available upon request.)</i>			
YES	NO	N/A	
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Each parcel should have a separate sanitary sewer lateral.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Sanitary sewer – 8 ft. horizontal separation from water main per DNR requirements. 8" diameter minimum size, PVC SDR 26 for depths up to 25 ft.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Sanitary sewer manhole at every change of direction and a maximum distance of 400 ft.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	A chimney seal shall be required on all manholes.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Provide copies of all approved WDNR/WDOC submittals, including sewer sizing calculation worksheet and the area served.

Storm System

Storm Plan View			
YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Ghost existing utilities and lateral locations in screened format. Pipe size of existing utilities labeled.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Proposed sewer and laterals with length, size, and material type clearly labeled.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Material and size of the existing storm sewer being connected to.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Stub-outs labeled with length, size, slope, and invert elevations (if not profiled).
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Dimensions showing offset from right-of-way to the sewer and separation distance between other utilities.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Type and size of encasement where needed
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Length of any sewer lateral. Label proposed invert elevations at right-of-way lines.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Proposed inlets, manholes, and other drainage structures.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Proposed drainage structures labeled with a design plan number. Existing drainage structures labeled with numbers obtained from City records.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Details of outfall or ditch inlet protection requirements such as rip-rap, end sections or headwalls as needed.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Details of detention facilities, outfall, overflow and control structures as needed.
Storm Profile View			
YES	NO	N/A	
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Stationing.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Existing and proposed surface profiles and elevations over the sewer.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	All utility crossings. Label elevations if known.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Pipe material / class, size, length, and percent grade to two (2) decimal places.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Material and size of the existing storm sewer being connected to
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Length, type, and size of encasement as needed.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Proposed inlets, manholes, and other drainage structures. Label type and size.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label station, rim, and invert elevations, based on City of Waukesha datum, at each manhole, catch basin, inlet, and detention control structure.

<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Proposed drainage structures labeled with a design plan number. Existing drainage structures to be labeled with numbers obtained from City records.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Cross-section of open channels and detention facilities, including outfall, overflow, and control structures.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Limits of gravel and/or slurry backfill.

General System

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Show all easements, public or private.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	No structures allowed within a public easement.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Plantings or signs within public easements, if permitted by City, shall be at least 5 feet from the utilities.

General for Subdivisions/Large Developments

YES	NO	N/A	
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Provide plans sealed by Registered Professional Engineer
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Show benchmark, north arrow and scale.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Show existing/proposed sewer and water utilities.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	All sewer to be installed by the developer under the terms of a Development Agreement.

Utility Plans

YES	NO	N/A	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location of all utilities: storm and sanitary sewers, water mains, fire hydrants, electrical, natural gas, and communication (cable television, telephone, etc.) lines
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Exterior lighting for parking and other outdoor areas, outdoor signs, and building exteriors.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location of waste and trash collection, and indicate plans for snow removal.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location and footprint of any and all buildings
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location and names of existing and proposed streets
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location and size of existing and proposed storm sewer, sanitary sewer, and water utility systems shown
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Electric, gas, telephone, and cable lines shown
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	All new utilities are underground
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Exterior lighting detail provided
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location of all utility and private fire hydrants
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Sampling manhole shown (if applicable)
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Grease interceptor shown (if applicable)
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Location and size of existing and proposed water meters

Include the following notes on the Utility Plan:

YES	NO	N/A	
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	All sanitary sewer to be installed in accordance with City of Waukesha standards.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	All applications and fees for sanitary sewer must be completed and paid prior to connection to sewer systems.
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Any utility work in the right-of-way and all sanitary sewer connections to be inspected by City. Notify City 72 hours in advance of connecting to sewer.

The above list contains items that are commonly missed on Utility Plans. For subdivisions or other large or complex projects, a complete plan review includes many more checks too numerous to list here. Please call (262) 524-3600 for additional information. City typical sewer details can be provided upon request.

Note: For water main, contact Waukesha Water Utility at (262) 521-5272