



Tony Lanza
1222 E Broadway
Waukesha WI 53186

April 12, 2022
PH 2-573-1316

Estimate as follows

Window Unit Viewed Segment Head Out Square In To Fit M.O. of 33" x 70"
Manufactured in Clear Solid Northern White Pine
Machine & finish hand sanded, woodlife treated and oil-base primed In & Out

Frame...
6-9/16" Jamb Depth with 2-1/2" Flat Exterior Casing

1-3/8" Thick DH Sash...
Constructed with mortise and tenon glued joints
Single putty glazed with 1/8" clear glass
Each Sash true divided 4 lite -2 wide x 2 high-
Sash balanced with beige non-tilt vinyl jamb liners

OMISSIONS - All By Others •Interior Trim/Casing •Sash Locks & Lifts •Finish Painting •Installation

For the sum EACH of...\$4,402.00 + 5.5% sales tax

Segment Head DH Acker Combination
Manufactured in Clear Solid Northern White Pine
Machine & finish hand sanded, woodlife treated and oil-base primed In & Out
Upper Glass Lite FIXED - Non-Removable
Lower Lite Area with Interchangeable Storm & Screen Inserts

OMISSIONS - By Others •Finish Painting

OPTION 1 Combination Glazed with 1/8" clear glass
For the sum EACH of...\$1,127.00 + 5.5% sales tax

OPTION 2 Combination glazed with 1/2" clear insulating glass
For the sum EACH of...\$1,468.00 + 5.5% sales tax

Manufacturing time - TBD At this time Approx. 18-24 Weeks
50% deposit down Required on all orders
Balance due at pick up Our Plant

** Accepted Payment Methods - Check or Cash

Thank You...
- Pete Acker

Valid 30 Days

ACKER MILLWORK CO. INC. • 3300 West Pabst Avenue • Milwaukee, Wisconsin 53215 • Phone: (414) 672-2200
www.ackermillwork.com (33rd & Cleveland) Fax: (414) 672-2203