1 EXISTING WEST ELEVATION

SCALE: 1/4" = 1'-0"

ELEVATION DEMOLITION CODED NOTES:

1. RELOCATE EXISTING DX UNITS AND CONCRETE SLABS (SEE SITE PLAN)
2. REMOVE xxx DOOR. REMOVE CONCRETE FOUNDATION TO 12" BELOW GRADE AND WOOD STAIRS, SEE DETAIL XXX
3. REMOVE EXISTING HANDRAILS
4. EXISTING FENCE TO REMAIN
5. REMOVE WOOD DOOR, JAMB, AND SILL

2 PROPOSED NEW WEST ELEVATION

SCALE: 1/4" = 1'-0"

ELEVATION CODED NOTES:

1. NEW WOOD HANDRAIL, SEE DETAIL XXX
2. SCRAPE, PRIME, AND PAINT HOUSE. COLORS TO MATCH EXISTING
3. TUCKPOINT EXISTING FOUNDATION WALL AS REQUIRED
4. RELOCATE EXISTING DX UNITS, CONRETE PAD, AND LINE SETS
5. NEW HANICAP RAMP, SEE DETAIL XXX
6. ADD LATTIS VENEER TO MATCH EXISTING
7. NEW 3'-0"x6'-8" DOOR, SEE DOOR SCHEDULE
8. NEW MASONRY WALL TO ENCLOSE OPENING OF XXXX DOOR WHICH WAS REMOVED, SEE DETAIL
9. PATCH EXISTING CONCRETE FLOOR
10. PAINT AND SEAL EXISTING WALLS
11. PATCH EXISTING OPENING IN CHIMNEY W/ MASONRY
12. NEW 1 ½" DIAMETER WOOD HANDRAIL, STAIN AND SEAL
13. BACKFILL EXISTING FOUNDATION WITH CRUSHED STONE
14. INFILL DOOR OPENING WITH 12" CMU, WATERPROOF AND XXX EXTERIOR
15. CONCRETE SONOTUBE, SEE STRUCTURAL PLANS

Keller
Architectural Design, LLC.

Project:

CARROLL HEALTH CENTER

215 WRIGHT STREET
WAUKESHA, WI

Owner:

CARROLL UNIVERSITY

114 S. East Avenue
Waukesha, WI 53186

NOT FOR CONSTRUCTION - PRELIMINARY - FOR ESTIMATING AND REVIEW ONLY- DO NOT SCALE THESE DRAWINGS

COPYRIGHT ***Keller Architectural Design, LLC***. 2012
ALL RIGHTS RESERVED
THIS DRAWING IS NOT TO BE REPRODUCED, CHANGED, COPIED OR ASSIGNED TO ANY THIRD PARTY IN ANY FORM OR MANNER WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION OF ***Keller Architectural Design, LLC***. THE CLIENT AGREES TO INDEMNIFY AND HOLD THE ARCHITECT HARMLESS FROM ANY DAMAGES, LIABILITY, OR COST, INCLUDING ATTORNEY'S FEES AND COSTS OF DEFENSE ARISING FROM ANY CHANGES OR ALTERATIONS MADE BY ANYONE OTHER THAN THE ARCHITECT, OR FROM ANY REUSE OF THE DRAWINGS OR DATA WITHOUT THE PRIOR WRITTEN CONSENT OF THE ARCHITECT.

Revisions:

Date	Number	Description

Sheet Title:

Existing Demolition
and Proposed New West Elevations
and Construction Notes

Project No.: 12.01.20

Date: 03/11/2015

Sheet No.:

A2.1

L15-010 - CARROLL HEALTH CENTER - 03/11/2015