



| Summit Credit Union  
Moreland Blvd Branch Office  
Waukesha, WI

| Preliminary Plan Commission



To: City of Waukesha Planning Department and Plan Commission

Project: Summit Credit Union Branch Office  
2208 E. Moreland Blvd  
Waukesha, Wisconsin

Applicants' Contact: Summit Credit Union  
4800 American Parkway  
Madison Wisconsin 53718  
Attn: Jeremy Eppler  
608-243-5000, extension 4407

Architect: Strang, Inc.  
6411 Mineral Point Road  
Madison, WI 53705  
Attn: Peter Tan and Austen Conrad  
608-276-9200

Civil Engineer: JSD Professional Services  
161 Horizon Drive, Suite 101  
Verona, Wisconsin 53593  
Attn: Bill Dunlop  
608-848-5060

Landscape Architect: JSD Professional Services  
161 Horizon Drive, Suite 101  
Verona, Wisconsin 53593  
Attn: Bill Dunlop  
608-848-5060

### **Table of Contents**

1	Contact Information
2	Project description, narrative, and materials
6	Plan Commission Application
7	Civil and Landscaping Plans
18	Site Lighting
27	Building floor plan and elevations
30	Signage
31	Stormwater Management and Erosion Control Plan

### **Request**

Applicant is seeking preliminary Plan Commission feedback on the use of the property in general as well as the building brand & design prior to moving forward with further details.

### **Zoning Data**

Current Zoning: B-5 Community Business District

Proposed Use: Single story financial institution with drive-through teller facilities.

**Project Statistics**

Legal: Refer to site survey attached.

Lot Area: 49,364 sq. ft.

Lot Coverage: Impervious = 28,935 sq. ft. (58.62% of site)

- 3,891 sq. ft. building “footprint”
- 23,299 sq. ft. parking and drive aisles
- 1,745 sq. ft. sidewalk

Pervious area = 20,429 sq. ft. (41.38% of site)

- Lawn, landscaped areas, drainage ways

Building Area: Building: 3,891 gross square feet (GSF)  
Drive Thru Canopy: 892 GSF  
Total “footprint”: 4,783 GSF

Building height: 1 story  
24'-0” feet to top of highest coping

**Parking**

Employees = 8 max, 5 normal	8 stalls required.
Customer Floor Area = 1,883 sf	1,883 sf / 1 stall per 150 sf = 13 stalls required

21 parking stalls provided on site (including 1 handicapped accessible stall)

**Bicycle Parking**

Credit Union = 3,891 gross sq. ft.	3,891 sf / 1 stall per 2Hou000 = 2 stalls.
Employees = 8 max, 5 normal	8 employees / 1 stall per 20 employees = 1 stall required

3 bicycle parking stalls provided on site.\*

\* Current preliminary plans do not show bicycle parking. Applicant will be revising to add required bicycle parking in final submittal.

**Description of Intended Use**

**Financial Institution:**

Operational characteristics will be those of a typical financial institution. Three drive-through teller aisles and one drive-through ATM aisle will serve credit union members from their autos. The building will have a walk-in lobby for credit union members who wish to conduct business with a teller or financial adviser, and for people wishing to become members of the credit union. The “back of house” area will contain storage, a staff break room, and other support spaces.

For walk-in customers, the lobby will be open from approximately 9:00 am until 5:00 pm Monday through Thursday, 9:00am – 6:00pm Friday, and 9:00 am to noon on Saturday.

The drive-through teller lanes will be open from approximately 8:00 am to 6:00 pm Monday through Friday and from 8:30 am to 1:00pm on Saturday. An ATM machine on the outer-most drive-through lane will be available at all times.

Daily Traffic Expected: 100 walk-in customers, 200 drive-through customers

## **Design Narrative**

The site and building is designed in response to Summit Credit Union's desire for a highly visible facility that reaches out to the community, while being responsive to the integrity of its contextual fabric. The massing and design composition of the building is such that it presents a pleasing face to the public realm on all four sides of the site. The drive-up canopy design is fully integrated into the overall design composition of the facility.

Floor-to-ceiling windows allow for much of the building to rely on natural daylighting. To underscore Summit's commitment to sustainability, large southwest facing vertical sail-shaped fabric sunshades reduce solar heat gain and glare on the southwest facing curtainwall of the branch and provide cool, diffuse daylighting to the interior. Please refer to the attached photographs of the Summit Credit Union Monona branch for an idea of the design forms and details, as well as the exterior materials and finishes on the project.

As a member-owned cooperative, Summit Credit Union believes they have an obligation to do what is best for its members, and collectively be good citizens of the community. The design and architecture of the Summit Credit Union Moreland Blvd Branch clearly represents the credit union's mission and vision into the future.

## **Exterior Materials and Colors:**

Brick: Brick comprises more than 50% of the non-window exterior surface of the building. The brick proposed is Endicott Manganese Ironspot brick.

Exterior Walls Above Window Heads: Silver metallic ribbed metal panel.

Windows: Aluminum storefront system in a clear anodized aluminum finish.

Copings, window sills, rooftop mechanical equipment screen and accent trim on roof overhang fascias: Silver metallic metal to match finish of window frames.



Figure 1. Typical materials.



Figure 2. Summit Credit Union in Monona, WI. Proposed building will have a similar design language and material palette.




*Figure 3. Summit Credit Union in Monona, WI. Proposed building will have a similar design language and material palette.*



**CITY OF WAUKESHA  
PLAN COMMISSION**

**Application for Review**



*Date Submitted*

**Name of Project:** Summit Credit Union - Moreland Blvd Branch Office

**Address** (if no address, location): 2208 E. Moreland Blvd

**Applicant information:**

Name: Jeremy Eppler  
 Company Name: Summit Credit Union  
 Address: 4800 American Parkway  
Madison, WI 53718  
 Phone: 608/243-5000, EXT 4407

**Owner information:**

Name: Mr. James Rosen  
 Company Name: Pinnacle Waukesha Burgers, LLC  
 Address: 19035 W. Capitol Drive, Suite 108  
Brookfield, WI 53045  
 Phone: 414/708-1200

IMPORTANT: A DIGITAL copy must be submitted with this application (JPG and/or PDF) along with 4 full-size (one of which must be in COLOR) and 7 reduced copies unless waived by the department. The reduced set of copies should only include the project location map showing a 1/2 mile radius, a COLORED landscape plan, COLORED building elevations, and exterior light fixture cut sheets.

<u>TYPE OF REVIEW</u>	<u>FEE</u>
<input type="checkbox"/> <b>Rezoning:</b> Attach <u>COPY</u> of rezoning petition <u>along with fee</u> . Original <u>must</u> be submitted to City Clerk.	\$350
<input type="checkbox"/> <b>Certified Survey Map</b>	\$150 + \$50/lot
<input type="checkbox"/> <b>Plat Review -</b> <i>Plat Reviews</i> are held until next meeting. 9 copies must be submitted. You must also submit 4 to the County and 2 to State. (Check appropriate box)	<input type="checkbox"/> <b>prelim.:</b> \$500 + \$10/lot <input type="checkbox"/> <b>final:</b> \$300 + \$10/lot
<input checked="" type="checkbox"/> <b>** Site Plan &amp; Arch. Review -</b> Architectural changes do not need preliminary review. (Check appropriate box)	<input checked="" type="checkbox"/> <b>prelim.:</b> \$300 + \$15/1000 sq.ft. or res. unit <input type="checkbox"/> <b>final:</b> \$200 + \$10/1000 sq.ft. or res. unit
<input type="checkbox"/> <b>** Conditional Use with Site Plan</b> (Check appropriate box)	<input type="checkbox"/> <b>prelim.:</b> \$300 + \$15/1000 sq.ft. or res. unit <input type="checkbox"/> <b>final:</b> \$200 + \$10/1000 sq.ft. or res. unit
<input type="checkbox"/> <b>Conditional Use (No Site Plan)</b>	\$200
<input type="checkbox"/> <b>** Airport Hangar Review</b>	\$300
<input type="checkbox"/> <b>Home Industry</b> (Attach info sheet.)	\$100
<input type="checkbox"/> <b>House Move</b>	\$150
<input type="checkbox"/> <b>Street Vacation</b>	\$150
<input type="checkbox"/> <b>Other (specify):</b> _____	\$100
<input type="checkbox"/> <b>** PUD Review</b>	\$400 added to S.P.A.R. fee
<input type="checkbox"/> <b>PUD Amendment</b>	\$100
<input type="checkbox"/> <b>Annexations and/or Attachments -</b> Original must be submitted to City Clerk.	No Fee
<input type="checkbox"/> <b>Resubmittal</b>	\$150

\*\* Please attach to this form a Review Checklist if it involves an architectural and/or site plan review.

**DEADLINE FOR THE SUBMITTAL IS THE MONDAY FOUR WEEKS BEFORE THE MEETING BY 4:00 P.M.**

INTERNAL USE ONLY			
Amount Due: _____	Check #: _____	Amount Paid: _____	Rec'd By: _____

# ALTA/NSPS LAND TITLE SURVEY

LOT 1, CERTIFIED SURVEY MAP No. 10663, LOCATED IN THE NORTHWEST QUARTER OF THE NORTHWEST QUARTER OF SECTION 31, TOWNSHIP 07 NORTH, RANGE 20 EAST, CITY OF WAUKESHA, WAUKESHA COUNTY, WISCONSIN.



CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
KENOSHA | APPLETON | WAUSAU


MADISON REGIONAL OFFICE  
161 HORIZON DRIVE, SUITE 101  
VERONA, WISCONSIN 53583  
P. 608.848.5060

CLIENT:  
**SUMMIT CREDIT UNION**

CLIENT ADDRESS:  
**4800 AMERICAN PARKWAY  
MADISON, WI 53718-8308**

PROJECT:  
**WAUKESHA**

PROJECT LOCATION:  
**CITY OF WAUKESHA  
WAUKESHA COUNTY, WISCONSIN**



PLAN MODIFICATIONS:


#	Date	Description
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		

**ALTA/NSPS LAND TITLE SURVEY**

MAP No: E-\*

SHEET NUMBER:  
**1 OF 1**

JSD PROJECT NO: 18-8460



- LEGEND**
- GOVERNMENT CORNER
  - 1" IRON PIPE FOUND
  - CHISELED 'X' FOUND
  - COTTON SPINDLE SET
  - FINISHED FLOOR SHOT LOCATION
  - SDM
  - SANITARY MANHOLE
  - CLEAN OUT
  - HYDRANT
  - WATER VALVE
  - ROUND CASTED INLET
  - CURB INLET
  - GAS REGULATOR/METER
  - MANHOLE - GREASE TRAP
  - ELECTRIC MANHOLE
  - ELECTRIC PEDESTAL
  - POWER POLE W/GUY
  - LIGHT POLE
  - TELEPHONE PEDESTAL
  - TELEPHONE MANHOLE
  - DECIDUOUS TREE
  - CONIFEROUS TREE
  - BUSH
  - HANDICAP PARKING
  - PARCEL BOUNDARY
  - SECTION LINE
  - RIGHT-OF-WAY LINE
  - CENTERLINE
  - CHORD LINE
  - PLATTED LOT LINE
  - EASEMENT LINE
  - CONCRETE CURB & GUTTER
  - SANITARY SEWER
  - WATER LINE
  - STORM SEWER
  - NATURAL GAS
  - OVERHEAD ELECTRIC DISTRIBUTION
  - UNDERGROUND ELECTRIC
  - FIBER OPTIC
  - UNDERGROUND TELEPHONE
  - UNDERGROUND CABLE
  - EDGE OF WOODS OR BRUSH
  - BUILDING
  - WALL LINE
  - INDEX CONTOUR
  - INTERMEDIATE CONTOUR
  - SPOT ELEVATION
  - BITUMINOUS PAVEMENT
  - RETAINING WALL
  - CONCRETE PAVEMENT
  - NO ACCESS
  - PAVEMENT STRIPING
  - END OF FLAGGED UTILITIES
  - DENOTES RECORD DATA SECTION THE SAME LINE ON THE GROUND AS RELAYED BY THIS SURVEY
  - CANOPY COLUMN (TYP)
  - EDGE OF CANOPY

- NOTES**
- FIELD WORK PERFORMED BY JSD PROFESSIONAL SERVICES, INC. ON MARCH 29, 2018.
  - BEARINGS FOR THIS SURVEY AND MAP ARE BASED ON THE SOUTHEASTERN WISCONSIN REGIONAL PLANNING COMMISSION (SEWRPC), THE WEST LINE OF THE NORTHWEST QUARTER OF SECTION 31-07-20, BEARS 500°30'57"E.
  - ELEVATIONS ARE BASED ON THE NATIONAL GEODETIC VERTICAL DATUM OF 1929 (NGVD29). BENCHMARK IS A BRASS CAP IN CONCRETE MARKING THE NORTHWEST CORNER OF SECTION 31-07-20, ELEVATION = 931.30'
  - CONTOUR INTERVAL IS ONE FOOT.
  - SUBSURFACE UTILITIES AND FEATURES SHOWN ON THIS MAP HAVE BEEN APPROXIMATED BY LOCATING SURFICIAL FEATURES AND APPURTENANCES, LOCATING DIGGERS HOTLINE FIELD MARKINGS AND BY REFERENCE TO UTILITY RECORDS AND MAPS. BIGGER'S HOTLINE TICKET No.s 20181108335, 20181108347, 20181108366, 20181108372, 20181108416 AND 20181108425, WITH A CLEAR DATE OF MARCH 26, 2018.
  - UTILITY COMPANIES CONTACTED THRU DIGGERS HOTLINE: CITY OF DELAFIELD, DEPARTMENT OF PUBLIC WORKS WISCONSIN DOT-TS EQUIPMENT AT&T TRANSMISSION CENTURYLINK WE ENERGIES WISCONSIN DOT SOUTHEAST REGION LEVEL 3 COMMUNICATIONS TIME WARNER CABLE
  - BEFORE EXCAVATION, APPROPRIATE UTILITY COMPANIES SHOULD BE CONTACTED. FOR EXACT LOCATION OF UNDERGROUND UTILITIES, CONTACT DIGGERS HOTLINE, AT 1.800.242.8511.
  - JSD PROFESSIONAL SERVICES, INC. DOES NOT GUARANTEE THAT THE BENCHMARK ELEVATIONS LISTED ON THIS MAP HAVE NOT BEEN DISTURBED SINCE THE DATE OF THIS SURVEY AND SHOULD BE VERIFIED PRIOR TO CONSTRUCTION ACTIVITIES.
  - SET BACKS ARE BASED ON CHAPTER 22, 22.37(7). THERE ARE NO REFERENCES MADE TO CORNER LOTS. SET BACKS ALONG HERITAGE LANE MAY BE GREATER, CONTACT CITY OF WAUKESHA ZONING DEPARTMENT.
  - SANITARY SEWER AND WATER SERVICE LATERAL SIZE AND LOCATION ARE UNKNOWN.

- NOTES CORRESPONDING TO TABLE A REQUIREMENTS:**
- ITEM 3 THE SUBJECT PROPERTY LIES IN ZONE X (AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN) PER FEMA MAP NUMBER 5504790186F, EFFECTIVE DATE OF NOVEMBER 19, 2008.
  - ITEM 6(b) CURRENT ZONING CLASSIFICATION IS B-5, COMMUNITY BUSINESS, FROM CITY WEB SITE.
  - ITEM 9 THERE ARE 10 REGULAR PARKING SPACES AND 1 HANDICAP SPACE FOR A TOTAL OF 11 PARKING SPACES.
  - ITEM 10(a) THERE ARE NO DIVISION OR PARTY WALLS WITH RESPECT TO ADJOINING PROPERTIES.
  - ITEM 11 SOURCE INFORMATION FROM PLANS AND MARKING WILL BE COMBINED WITH OBSERVED EVIDENCE OF UTILITIES PURSUANT TO SECTION 9.6.IV, TO DEVELOP A VIEW OF THE UNDERGROUND UTILITIES. HOWEVER, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY, COMPLETELY, AND RELIABLY DEPICTED. IN ADDITION, IN SOME JURISDICTIONS, 811 OR OTHER SIMILAR UTILITY LOCATE REQUESTS FROM SURVEYORS MAY BE IGNORED OR RESULT IN AN INCOMPLETE RESPONSE. IN WHICH CASE, THE SURVEYOR SHALL NOTE ON THE PLAT OR MAP HOW THIS AFFECTED THE SURVEYOR'S ASSESSMENT OF THE LOCATION OF THE UTILITIES. WHERE ADDITIONAL OR MORE DETAILED INFORMATION IS REQUIRED, THE CLIENT IS ADVISED THAT EXCAVATION AND/OR A PRIVATE UTILITY LOCATE REQUEST MAY BE NECESSARY.
  - ITEM 16 THERE IS NO OBSERVED EVIDENCE OF CURRENT EARTH MOVING WORK, BUILDING CONSTRUCTION OR BUILDING ADDITIONS AT THE TIME OF THIS SURVEY.
  - ITEM 17 THERE ARE NO PROPOSED CHANGES IN THE STREET RIGHT-OF-WAY LINES PER CITY OF DELAFIELD. THERE IS NO OBSERVED EVIDENCE OF RECENT STREET OR SIDEWALK CONSTRUCTION OR REPAIRS.
  - ITEM 18 THERE HAS BEEN NO FIELD DELINEATION OF WETLANDS CONDUCTED FOR THIS SITE.
  - ITEM 19 ANY OFFSITE EASEMENT FOR THE SUBJECT PROPERTY IS SHOWN IN ITS ENTIRETY.

- NOTES CORRESPONDING TO SCHEDULE B-SECTION TWO EXCEPTIONS**  
(CHICAGO TITLE INSURANCE COMPANY, COMMITMENT No.: CO-7333, COMMITMENT DATE: MARCH 6, 2018)
- (10) EASEMENT(S) FOR THE PURPOSE(S) AND RIGHTS INCIDENTAL THERETO, AS GRANTED IN A DOCUMENT, GRANTED TO WISCONSIN TELEPHONE COMPANY AND WISCONSIN ELECTRIC POWER COMPANY, FOR UTILITY PURPOSES, RECORDED ON APRIL 6, 1960, AS DOCUMENT No. 520769. THIS ITEM DOES NOT AFFECT THE SUBJECT PROPERTY AND IS NOT PLOTTED HEREON. (S IN CURRENT HIGHWAY RIGHT-OF-WAY).
  - (11) ACCESS LIMITATIONS AND DEVELOPMENT RESTRICTIONS SET FORTH IN INDENTURE RECORDED FEBRUARY 9, 1966 AS DOCUMENT No. 655271. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (12) EASEMENT(S) FOR THE PURPOSE(S) AND RIGHTS INCIDENTAL THERETO, AS GRANTED IN A DOCUMENT, GRANTED TO WISCONSIN ELECTRIC POWER COMPANY AND WISCONSIN TELEPHONE COMPANY, FOR UTILITY PURPOSES, RECORDED ON MARCH 13, 1976, AS DOCUMENT No. 756797. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (13) RECITALS AS SHOWN ON CERTIFIED SURVEY MAP No. 2681 RECORDED ON SEPTEMBER 1, 1976, AS DOCUMENT No. 965499, WHICH AMONG OTHER THINGS RECITES EASEMENT FOR INGRESS AND EGRESS, RESTRICTIONS AND NOTES. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (14) MEMORANDUM OF AGREEMENT RECORDED MARCH 8, 1977 AS DOCUMENT No. 987077. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS NOT GRAPHIC IN NATURE, THEREFORE IT IS NOT PLOTTED HEREON.
  - (15) EASEMENT(S) FOR THE PURPOSE(S) AND RIGHTS INCIDENTAL THERETO, AS GRANTED IN A DOCUMENT, GRANTED TO THE CITY OF WAUKESHA, FOR SANITARY SEWER PURPOSES, RECORDED ON OCTOBER 25, 1977, AS DOCUMENT No. 1021809. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (16) EASEMENT(S) FOR THE PURPOSE(S) AND RIGHTS INCIDENTAL THERETO, AS GRANTED IN A DOCUMENT, GRANTED TO THE CITY OF WAUKESHA, FOR SANITARY SEWER PURPOSES, RECORDED ON NOVEMBER 2, 1977, AS DOCUMENT No. 1022917. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (17) EASEMENT(S) FOR THE PURPOSE(S) AND RIGHTS INCIDENTAL THERETO, AS GRANTED IN A DOCUMENT, GRANTED TO THE CITY OF WAUKESHA, FOR SANITARY SEWER PURPOSES, RECORDED ON JUNE 30, 1978, AS DOCUMENT No. 1054817. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (18) SANITARY SEWER EASEMENT RECORDED DECEMBER 7, 1978 AS DOCUMENT No. 1075472. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (19) RECITALS AS SHOWN ON CERTIFIED SURVEY MAP No. 10663 RECORDED ON MARCH 31, 2009, AS DOCUMENT No. 3641473, WHICH AMONG OTHER THINGS RECITES SIDEWALK EASEMENT, RESTRICTIONS, NOTES, INGRESS/EGRESS EASEMENT, CROSS ACCESS EASEMENT, TEMPORARY SLOPE EASEMENT FOR SIDEWALK CONSTRUCTION AND ACCESS LIMITATIONS. THIS ITEM MAY AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.

**LEGAL DESCRIPTION (AS FURNISHED)**  
(CHICAGO TITLE INSURANCE COMPANY, COMMITMENT No.: CO-7333, COMMITMENT DATE: MARCH 6, 2018)

LOT 1 OF CERTIFIED SURVEY MAP No. 10663, RECORDED MARCH 31, 2009, IN VOLUME 102 OF CERTIFIED SURVEY MAPS ON PAGES 309 TO 313 AS DOCUMENT No. 3641473, A DIVISION OF PARCEL 6 OF CERTIFIED SURVEY MAP No. 2681 AND LANDS IN THE NORTHWEST 1/4 OF THE NORTHWEST 1/4 OF SECTION 31, TOWN 7 NORTH, RANGE 20 EAST, IN THE CITY OF WAUKESHA, COUNTY OF WAUKESHA, STATE OF WISCONSIN.

TAX KEY No.: WAC 1130.115.001  
ADDRESS: 2208 E. MORELAND BLVD.

**SURVEYOR'S CERTIFICATE**

- TO:
- PINNACLE WAUKESHA BURGERS, LLC, A WISCONSIN LIMITED LIABILITY COMPANY,
  - BANK MUTUAL,
  - CHICAGO TITLE INSURANCE COMPANY.

THIS IS TO CERTIFY THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT IS BASED WERE MADE IN ACCORDANCE WITH THE 2016 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/NSPS LAND TITLE SURVEYS, JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS AND INCLUDES ITEMS 1, 2, 3, 4, 5, 6(b), 7(c), 7(d), 7(e), 8, 9, 10(c), 11, 13, 14, 16, 17, 18, 19 AND 20 OF TABLE A THEREOF. THE FIELD WORK WAS COMPLETED ON MARCH 28, 2018.

*John Krebs* 4/14/18  
JOHN KREBS, S-1878  
PROFESSIONAL LAND SURVEYOR DATE



**STORM SEWER MANHOLES**

STRUCT. ID	RIM ELEVATION	INVERT	ELEVATION	PIPE SIZE	PIPE TYPE
STM-1	930.77	NE	928.67	6"	PVC
		SW	928.68	6"	PVC
		NW	928.17	10"	PVC
STM-2	933.33	SE	930.98	6"	PVC
		NW	930.38	10"	PVC
		SE	929.62	10"	PVC
STM-3	932.92	SW	929.59	6"	PVC
		NW	930.29	6"	PVC
		NE	927.87	10"	PVC

**STORM SEWER INLETS**

INLET ID	RIM ELEVATION	INVERT	ELEVATION	PIPE SIZE	PIPE TYPE
INL-1	931.90	SW	928.12	10"	PVC
		SE	928.28	10"	PVC
		NE	924.22	10"	PVC
INL-2	918.30	SW	918.73	10"	PVC
		NE	915.75	12"	RCP
		SW	915.47	12"	RCP
INL-3	919.32	SW	915.47	12"	RCP
		NW	915.47	12"	RCP

**SANITARY SEWER MANHOLES**

STRUCT. ID	RIM ELEVATION	INVERT	ELEVATION	PIPE SIZE	PIPE TYPE
SAN-1	936.92	SE	930.66	6"	PVC
		SW	930.51	6"	PVC
		NW	930.58	6"	PVC
SAN-2	927.79	SE	922.65	8"	PVC
		NE	922.55	8"	PVC
		SW	913.99	8"	PVC
SAN-3	920.49	NE	913.79	8"	PVC
		SW	913.79	8"	PVC

**WATER VALVES**

VALVE No.	SIZE	RIM ELEVATION	INVERT	TOP NUT ELEVATION	PIPE INVERT
WV-1	10"	938.75	TN	932.45	930.70

TN=TOP NUT OF WATER VALVE


**BENCHMARKS**

BENCH MARK	ELEVATION	DESCRIPTION
BM-1	938.42	ARROW ON HYDRANT IN FRONT OF SITE
BM-2	935.18	RR SPIKE IN UTILITY POLE NORTHWEST CORNER OF SITE

\*JSD PROFESSIONAL SERVICES, INC. DOES NOT GUARANTEE THAT THE BENCHMARK ELEVATIONS LISTED ON THIS MAP HAVE NOT BEEN DISTURBED SINCE THE DATE OF THIS SURVEY AND SHOULD BE VERIFIED PRIOR TO CONSTRUCTION ACTIVITIES.

**CURVE TABLE**

CURVE	LENGTH	RADIUS	DELTA	CHORD	CHORD BEARING
C-1	120.51'	286.55'	24°05'43"	119.62'	N78°24'32"E
( )	120.51'	286.55'	24°05'43"	119.62'	N79°34'58"E
C-2	90.85'	63.96'	81°22'52"	83.40'	S73°24'58"E
( )	90.80'	63.96'	81°20'08"	83.36'	S72°10'24"E



VICINITY MAP  
SCALE 1" = 600'



**GENERAL NOTES**

- REFER TO THE EXISTING CONDITIONS SURVEY FOR EXISTING CONDITIONS NOTES AND LEGENDS.
- ALL WORK IN THE ROW SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR SEWER & WATER CONSTRUCTION IN WISCONSIN, LATEST EDITION AND CITY OF WAUKESHA REQUIREMENTS.
- NO SITE GRADING OUTSIDE OR DOWNSLOPE OF PROPOSED SILT FENCE LOCATION. NO LAND DISTURBANCE BEYOND PROPERTY LINES UNLESS OTHERWISE SHOWN.
- THIS PROJECT HAS BEEN DESIGNED AND WILL BE CONSTRUCTED IN COMPLIANCE WITH ALL OF THE WDNR WRAPP PERMIT APPLICATION STANDARDS.
- JSD SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER/CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY ANY OR ALL REGULATORY AGENCIES.

**DEMOLITION NOTES**

- THIS PLAN INDICATES ITEMS ON THE PROPERTY INTENDED FOR DEMOLITION BASED ON THE CURRENT SITE DESIGN THAT HAVE BEEN IDENTIFIED BY A REASONABLE OBSERVATION OF THE EXISTING CONDITIONS THROUGH FIELD SURVEY RECONNAISSANCE, "DIGGER'S HOTLINE" LOCATION, AND GENERAL "STANDARD OF CARE". THERE MAY BE ADDITIONAL ITEMS THAT CAN NOT BE IDENTIFIED BY A REASONABLE ABOVE GROUND OBSERVATION, OF WHICH THE ENGINEER WOULD HAVE NO KNOWLEDGE OR MAY BE A PART OF ANOTHER DESIGN DISCIPLINE. IT IS THE CONTRACTOR'S/BIDDER'S RESPONSIBILITY TO REVIEW THE PLANS, INSPECT THE SITE AND PROVIDE HIS OWN DUE DILIGENCE TO INCLUDE IN HIS BID WHAT ADDITIONAL ITEMS, IN HIS OPINION, MAY BE NECESSARY FOR DEMOLITION. ANY ADDITIONAL ITEMS IDENTIFIED BY THE CONTRACTOR/BIDDER SHALL BE IDENTIFIED IN THE BID AND REPORTED TO THE ENGINEER OF RECORD. JSD TAKES NO RESPONSIBILITY FOR ITEMS ON THE PROPERTY THAT COULD NOT BE LOCATED BY A REASONABLE OBSERVATION OF THE PROPERTY OR OF WHICH THEY WOULD HAVE NO KNOWLEDGE.
- CONTRACTOR SHALL KEEP ALL STREETS AND PRIVATE DRIVES FREE AND CLEAR OF ALL CONSTRUCTION RELATED DIRT, DUST AND DEBRIS.
- ALL TREES WITHIN THE CONSTRUCTION LIMITS SHALL BE REMOVED UNLESS SPECIFICALLY CALLED OUT FOR PROTECTION. ALL TREES TO BE REMOVED SHALL BE REMOVED IN THEIR ENTIRETY AND STUMPS SHALL BE GROUND TO PROPOSED SUBGRADE.
- ALL LIGHT POLES TO BE REMOVED SHALL BE REMOVED IN THEIR ENTIRETY, INCLUDING BASE AND ALL APPURTENANCES. SALVAGE FOR RELOCATION. COORDINATE RELOCATION AND/OR ABANDONMENT OF ALL ELECTRIC LINES WITH ELECTRICAL ENGINEER AND OWNER PRIOR TO DEMOLITION.
- ABANDONED/REMOVED ITEMS SHALL BE DISPOSED OF OFF SITE UNLESS OTHERWISE NOTED.
- CONTRACTOR TO REPLACE ALL SIDEWALK AND CURB AND GUTTER ABUTTING THE PROPERTIES, WHICH IS DAMAGED BY THE CONSTRUCTION, OR ANY SIDEWALK AND CURB AND GUTTER THAT THE CITY ENGINEER DETERMINES NEEDS TO BE REPLACED BECAUSE IT IS NOT AT A DESIRABLE GRADE REGARDLESS OF WHETHER THE CONDITION EXISTED PRIOR TO BEGINNING CONSTRUCTION.
- PRIOR TO CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR:
  - EXAMINE ALL SITE CONDITIONS RELATIVE TO THE CONDITIONS INDICATED ON THE ENGINEERING DRAWINGS. ANY DISCREPANCIES ARE TO BE REPORTED IMMEDIATELY TO THE ENGINEER AND RESOLVED PRIOR TO THE START OF CONSTRUCTION.
  - VERIFYING UTILITY ELEVATIONS AND NOTIFYING ENGINEER OF ANY DISCREPANCIES. NO WORK SHALL BE PERFORMED UNTIL THE DISCREPANCIES ARE RESOLVED.
  - NOTIFYING ALL UTILITIES PRIOR TO THE REMOVAL OF ANY UNDERGROUND UTILITIES.
  - NOTIFYING THE DESIGN ENGINEER AND LOCAL CONTROLLING MUNICIPALITY 48 HOURS PRIOR TO THE START OF CONSTRUCTION TO ARRANGE FOR APPROPRIATE CONSTRUCTION INSPECTION.
- ANY SANITARY SEWER, SANITARY SEWER SERVICES, WATER MAIN, WATER SERVICES, STORM SEWER, OR OTHER UTILITIES, WHICH ARE DAMAGED BY THE CONTRACTORS, SHALL BE REPAIRED TO THE OWNER'S SATISFACTION AT THE CONTRACTOR'S EXPENSE.
- CONTRACTOR IS RESPONSIBLE FOR SITE SAFETY DURING THE CONSTRUCTION OF THESE IMPROVEMENTS.
- CONTRACTOR TO COORDINATE PRIVATE UTILITY REMOVAL / ABANDONMENT AND NECESSARY RELOCATION WITH RESPECTIVE UTILITY COMPANY. COORDINATION REQUIRED PRIOR TO CONSTRUCTION.
- ALL DEMOLITION SHALL BE IN ACCORDANCE WITH THE APPROVED MUNICIPALITY RECYCLING PLAN.
- ANY CONTAMINATED SOILS SHALL BE REMOVED IN ACCORDANCE WITH FEDERAL AND STATE REGULATIONS TO AN APPROVED LANDFILL.
- ALL EXISTING UTILITIES TO BE FIELD LOCATED AND FLAGGED BY CONTRACTOR.
- EXISTING FIBER OPTIC LINE TO BE CLEARLY MARKED PRIOR TO ANY EXCAVATION. CONTRACTOR TO NOTIFY ENGINEER IMMEDIATELY IF ANY DISCREPANCIES OCCUR IN THE LOCATION SHOWN OR PROPOSED IMPROVEMENTS IMPACTING EXISTING FIBER OPTIC LINE LOCATION.
- SEWER ABANDONMENT SHALL BE IN ACCORDANCE WITH SECTION 3.2.24, OF THE STANDARD SPECIFICATIONS FOR WATER AND SEWER CONSTRUCTION IN WISCONSIN, LATEST ADDITION, AND CITY OF WAUKESHA SPECIFICATIONS.
- WATER ABANDONMENT SHALL BE IN ACCORDANCE WITH SECTION 4.14.0 OF THE STANDARD SPECIFICATIONS FOR WATER AND SEWER CONSTRUCTION IN WISCONSIN, LATEST ADDITION, AND CITY OF WAUKESHA SPECIFICATIONS.
- ALL PERIMETER EROSION CONTROL DEVICES SHALL BE INSTALLED PRIOR TO THE START OF DEMOLITION ACTIVITIES. CONTRACTOR SHALL KEEP ALL STREETS AND PAVEMENT FREE AND CLEAR OF ALL CONSTRUCTION RELATED DIRT, DUST AND DEBRIS.
- BUILDING REMOVALS SHALL BE BY A QUALIFIED CONTRACTOR. CONTRACTOR TO FOLLOW ALL DEMOLITION REGULATIONS, DISCONNECT ALL UTILITIES, OBTAIN ALL APPLICABLE PERMITS AND DISPOSE OF ALL BUILDING MATERIALS IN APPROPRIATE LANDFILLS. DEMOLISHED MATERIALS SHALL NOT BE BURIED ON SITE. IF ENCOUNTERED, ANY CONTAMINATED SOILS SHALL BE REMOVED TO A LANDFILL IN ACCORDANCE WITH APPROPRIATE STATE AND FEDERAL REGULATIONS.
- CONTRACTOR TO REMOVE EXISTING UTILITY PIPE OR PROVIDE PIPE BACK-FILLING AFTER REMOVAL OF EXISTING UTILITIES WITHIN BUILDING FOOTPRINT USING "LOW DENSITY CONCRETE/FLOWABLE FILL".
- RESTORATION OF THE EXISTING ROADWAY RIGHT-OF-WAYS ARE CONSIDERED INCIDENTAL AND SHOULD BE PART OF THE COST OF THE UNDERGROUND IMPROVEMENTS, DEMOLITION AND REMOVAL. THIS INCLUDES CURB & GUTTER, SIDEWALK, TOPSOIL, SEEDING AND MULCHING.
- WELL ABANDONMENT SHALL BE IN ACCORDANCE WITH WDNR AND LOCAL REGULATIONS. PROVIDE A COMPLETE RECORD OF CLOSURE (WDNR PERMIT 3300-005) COMPLETED BY A CONTRACTOR LICENSED TO PERFORM THAT WORK. CONTRACTOR SHALL SUBMIT DOCUMENTATION TO THE CITY OF WAUKESHA FOR CITY RECORDS.
- THIS SITE WAS IDENTIFIED AS A CLOSED LEAKING UNDERGROUND STORAGE TANK (LUST) SITE. IF THE CONTRACTOR IDENTIFIES POTENTIALLY CONTAMINATED SOILS, THEY SHALL STOP WORK AND NOTIFY THE OWNER'S CONSTRUCTION REPRESENTATIVE. CONTAMINATED SOIL, IF ENCOUNTERED, SHALL BE MANAGED AND REMOVED IN ACCORDANCE WITH STATE AND FEDERAL REQUIREMENTS. COPIES OF ALL DISPOSABLE MANIFESTS SHALL BE PROVIDED TO THE OWNER.



CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
KENOSHA | APPLETON | WAUSAU

MADISON REGIONAL OFFICE  
161 HORIZON DRIVE, SUITE 101  
VERONA, WISCONSIN 53593  
P. 608.848.5060

CLIENT:  
**SUMMIT CREDIT UNION**

CLIENT ADDRESS:  
**4800 American Parkway  
MADISON, WI 53718**

PROJECT:  
**SUMMIT CREDIT UNION - WAUKESHA BRANCH**

PROJECT LOCATION:  
**2208 E MORELAND BOULEVARD  
WAUKESHA COUNTY**

**PLAN MODIFICATIONS:**


#	Date:	Description:
1	04.09.18	CITY PLAN REVIEW
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		

Design/Drawn: KWH  
Approved: WHD

SHEET TITLE:  
**DEMOLITION PLAN**

SHEET NUMBER:  
**C1.0**

JSD PROJECT NO: 18-8469



File: I:\2018\188469\DWG\188469.dwg Con Des\_DEMO.dwg Layout: C1.0 User: chuhla Plotted: Apr 06, 2018 - 4:25pm Xref's:

THESE PLANS AND DESIGNS ARE COPYRIGHT PROTECTED AND MAY NOT BE USED IN WHOLE OR IN PART WITHOUT THE WRITTEN CONSENT OF JSD PROFESSIONAL SERVICES, INC.

**GENERAL NOTES**

1. REFER TO THE EXISTING CONDITIONS SURVEY FOR EXISTING CONDITIONS NOTES AND LEGENDS.
2. ALL WORK IN THE ROW SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR SEWER & WATER CONSTRUCTION IN WISCONSIN, LATEST EDITION AND CITY OF WAUKESHA REQUIREMENTS.
3. NO SITE GRADING OUTSIDE OR DOWNSLOPE OF PROPOSED SILT FENCE LOCATION. NO LAND DISTURBANCE BEYOND PROPERTY LINES UNLESS OTHERWISE SHOWN.
4. THIS PROJECT HAS BEEN DESIGNED AND WILL BE CONSTRUCTED IN COMPLIANCE WITH ALL OF THE WDR WRAPP PERMIT APPLICATION STANDARDS.
5. JSD SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER/CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY ANY OR ALL REGULATORY AGENCIES.

**SITE PLAN NOTES**

1. ALL DIMENSIONS TO FACE OF CURB AND/OR EDGING OF CONCRETE UNLESS OTHERWISE NOTED.
2. ALL RADII TO FACE OF CURB AND/OR EDGING OF CONCRETE UNLESS OTHERWISE NOTED.
3. ANY REQUIRED REPLACEMENT OF PUBLIC CURB AND GUTTER SHALL MATCH EXISTING AND MEET THE REQUIREMENTS OF THE CITY OF WAUKESHA.
4. CONTRACTOR SHALL PROVIDE CONTROL JOINTS AND CONSTRUCTION JOINTS OF ONE-QUARTER CONCRETE THICKNESS AT AN EQUAL RATIO OF LENGTH TO WIDTH WHEREVER POSSIBLE WITH A MAXIMUM LENGTH BETWEEN JOINTS OF 8' ON CENTER.
5. CONTRACTOR SHALL PROVIDE EXPANSION JOINTS IN SIDEWALKS AT A MAXIMUM 24' ON CENTER.
6. EXTERIOR CONCRETE SURFACES SHALL BE BROOM FINISHED.
7. ALL CONCRETE SURFACES TO BE SEALED WITH TYPE TK-26UV CONCRETE SEALANT.
8. USE 4" WIDE, HIGH VISIBILITY YELLOW LATEX PAINT FOR STALL LINES.
9. MARK AND STRIPE ADA PARKING SPACES APPROPRIATELY.
10. 2' x 4' TRUNCATED DOME WARNING DETECTION FIELD SHALL BE PLACED AT ALL ADA RAMP.
11. ALL PAVEMENT MARKINGS INCLUDING: STOP BARS, CROSSWALKS, DIRECTIONAL ARROWS, PARKING STALL LINES, ADA STALL MARKINGS, NO PARKING ZONES, DROP-OFF/PICK-UP ZONES SHALL BE PAINTED WITH LATEX PAINT PER MUNICIPALITY SPECIFICATIONS.

SITE INFORMATION BLOCK	
Owner Information:	SUMMIT CREDIT UNION 4800 AMERICAN PARKWAY MADISON, WI 53718
Site Address	LOT 1 OF CSM #10663 2208 EAST MORELAND, WAUKESHA, WI
Site Acreage (total)	1.133 ACRES
Number of Building Stories (above grade)	1
Total Square Footage of Building	3,900 S.F.
Number of parking stalls:	
Large car	19
Accessible	1
Total	20
Existing vs. Proposed Site Coverage:	
Existing Impervious Surface Area	32,752
Existing Pervious Surface Area	16,601
Proposed Impervious Surface Area	30,820
Proposed Pervious Surface Area	18,533
Proposed Impervious Surface Area Ratio	0.624

**LEGEND (PROPOSED)**

- PROPERTY LINE
- - - SETBACK LINE
- - - EASEMENT LINE
- ===== BUILDING LINE
- BUILDING OVERHANG LINE
- ===== EDGE OF CONCRETE
- ===== STANDARD CURB AND GUTTER
- ===== REJECT CURB AND GUTTER
- ===== PROPOSED CONCRETE PAVEMENT
- ===== PROPOSED HEAVY DUTY CONCRETE PAVEMENT
- ===== PROPOSED ASPHALT PAVEMENT
- ===== PROPOSED HEAVY DUTY ASPHALT PAVEMENT
- LIGHT POLE
- BOLLARD



CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
KENOSHA | APPLETON | WAUSAU

**MADISON REGIONAL OFFICE**  
161 HORIZON DRIVE, SUITE 101  
VERONA, WISCONSIN 53593  
P. 608.848.5060

CLIENT:  
**SUMMIT CREDIT UNION**

CLIENT ADDRESS:  
**4800 American Parkway  
MADISON, WI 53718**

PROJECT:  
**SUMMIT CREDIT UNION - WAUKESHA BRANCH**

PROJECT LOCATION:  
**2208 E MORELAND BOULEVARD  
WAUKESHA COUNTY**



PLAN MODIFICATIONS:		
#	Date:	Description:
1	04.09.18	CITY PLAN REVIEW
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		

Design/Drawn: CLH  
Approved: WHD

SHEET TITLE:  
**SITE PLAN**

SHEET NUMBER:  
**C2.0**

JSD PROJECT NO: 18-8469



File: I:\2018\188469\DWG\188469 Con Docs.dwg Layout: C2.0 User: chuhta Plotted: Apr 06, 2018 - 4:21pm Xref's:

THESE PLANS AND DESIGNS ARE COPYRIGHT PROTECTED AND MAY NOT BE USED IN WHOLE OR IN PART WITHOUT THE WRITTEN CONSENT OF JSD PROFESSIONAL SERVICES, INC.

**GENERAL NOTES**

- REFER TO THE EXISTING CONDITIONS SURVEY FOR EXISTING CONDITIONS NOTES AND LEGENDS.
- ALL WORK IN THE ROW SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR SEWER & WATER CONSTRUCTION IN WISCONSIN, LATEST EDITION AND CITY OF WAUKESHA REQUIREMENTS.
- NO SITE GRADING OUTSIDE OR DOWNSLOPE OF PROPOSED SILT FENCE LOCATION. NO LAND DISTURBANCE BEYOND PROPERTY LINES UNLESS OTHERWISE SHOWN.
- THIS PROJECT HAS BEEN DESIGNED AND WILL BE CONSTRUCTED IN COMPLIANCE WITH ALL OF THE WDNR WRAPP PERMIT APPLICATION STANDARDS.
- JSD SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER/CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY ANY OR ALL REGULATORY AGENCIES.

**CONSTRUCTION SITE EROSION CONTROL REQUIREMENTS (CSECR) NOTES:**

- ALL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE DESIGNED AND IMPLEMENTED IN ACCORDANCE WITH THE CURRENT DEPARTMENT OF NATURAL RESOURCES EROSION AND SEDIMENT CONTROL TECHNICAL STANDARDS WHICH ARE AVAILABLE AT: <http://www.dnr.state.wi.us/runoff/stormwater/techstds.htm>
- INSTALL EROSION CONTROL MEASURES PRIOR TO ANY SITE WORK, INCLUDING GRADING OR DISTURBANCE OF EXISTING SURFACE MATERIALS AS SHOWN ON PLAN. MODIFICATIONS TO SEDIMENT CONTROL DESIGN MAY BE CONDUCTED TO MEET UNFORESEEN FIELD CONDITIONS IF MODIFICATIONS CONFORM TO WDNR TECHNICAL STANDARDS.
- INSPECTIONS AND MAINTENANCE OF ALL EROSION CONTROL MEASURES SHALL BE ROUTINE (ONCE PER WEEK MINIMUM) TO ENSURE PROPER FUNCTION OF EROSION CONTROLS AT ALL TIMES. EROSION CONTROL MEASURES ARE TO BE IN WORKING ORDER AT THE END OF EACH WORK DAY.
- INSPECT EROSION CONTROL MEASURES AFTER EACH 1/2" OR GREATER RAINFALL. REPAIR ANY DAMAGE OBSERVED DURING THE INSPECTION.
- EROSION CONTROL MEASURES SHALL NOT BE REMOVED UNTIL ALL LAND DISTURBING CONSTRUCTION ACTIVITY AT THE SITE HAS BEEN COMPLETED AND THAT A UNIFORM PERENNIAL VEGETATIVE COVER HAS BEEN ESTABLISHED WITH A DENSITY OF AT LEAST 70% OF THE COVER FOR THE UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES OR THAT EMPLOY EQUIVALENT PERMANENT STABILIZATION MEASURES.
- INSTALL A TRACKING PAD, 50' LONG AND NO LESS THAN 12" THICK BY USE OF 3" CLEAR STONE. TRACKING PADS ARE TO BE MAINTAINED BY THE CONTRACTOR IN A MANNER WHICH WILL PREVENT THE TRACKING OF MUD OR DRY SEDIMENT ONTO THE ADJACENT PUBLIC STREETS AFTER EACH WORKING DAY OR MORE FREQUENTLY AS REQUIRED.
- INSTALL EROSION CONTROLS ON THE DOWNSTREAM SIDE OF STOCKPILES.
- INSTALL TEMPORARY SEDIMENT TRAPS PER LATEST EDITION OF WDNR STORM WATER CONSTRUCTION TECHNICAL CONSTRUCTION SITE EROSION & SEDIMENT CONTROL STANDARDS NOTE 1063. SEDIMENT TRAPS SHALL BE SIZED BASED ON MEDIUM SOIL TEXTURAL CLASS. SEDIMENT TRAPS SHALL BE INSPECTED WITHIN 24 HOURS AFTER EVERY RAIN EVENT PRODUCING 0.5 INCHES OF RAIN OR MORE AND AT A MINIMUM SEDIMENT SHALL BE REMOVED WHEN SEDIMENT REACHES A DEPTH OF 1 FOOT OR WHEN OUTLET BECOMES CLOGGED. SEDIMENT TRAPS SHALL BE REMOVED AND THE LOCATION STABILIZED AFTER THE DISTURBED AREA DRAINING TO THE SEDIMENT TRAP IS STABILIZED AND NO LONGER SUSCEPTIBLE TO EROSION. ALL SEDIMENT SHALL BE PROPERLY DISPOSED.
- INSTALL CHECK DAMS WITHIN DRAINAGE DITCHES AND IN FRONT OF SILT FENCING IN ANY LOW AREA ALL IN ACCORDANCE WITH WDNR TECHNICAL STANDARDS.
- EROSION CONTROL FOR UTILITY CONSTRUCTION (STORM SEWER, SANITARY SEWER, WATER MAIN, ETC.):
  - PLACE EXCAVATED TRENCH MATERIAL ON THE HIGH SIDE OF THE TRENCH.
  - BACKFILL, COMPACT, AND STABILIZE THE TRENCH IMMEDIATELY AFTER PIPE CONSTRUCTION.
  - DISCHARGE TRENCH WATER INTO A SEDIMENTATION BASIN OR FILTERING TANK IN ACCORDANCE WITH THE DEWATERING TECHNICAL STANDARD NO. 1061 PRIOR TO RELEASE INTO THE STORM SEWER, RECEIVING STREAM, OR DRAINAGE DITCH.
- ADDITIONAL EROSION CONTROL MEASURES, AS REQUESTED BY STATE INSPECTORS, LOCAL INSPECTORS, AND/OR ENGINEER SHALL BE INSTALLED WITHIN 24 HOURS OF REQUEST.
- ALL SLOPES 4:1 OR GREATER SHALL BE STABILIZED WITH CLASS I, TYPE B EROSION MATTING AND DRAINAGE SWALES SHALL BE STABILIZED WITH CLASS II, TYPE B EROSION MATTING, WITHIN 7 DAYS OF REACHING FINAL GRADE AND/OR AS SOON AS CONDITIONS ALLOW. REFER BELOW TO "CSECR" NOTE NO. SIXTEEN (16) FOR STABILIZATION PRACTICES FOR POTENTIAL INTERIM STABILIZATION.
- CONTRACTOR/OWNER SHALL FILE A NOTICE OF TERMINATION UPON VEGETATIVE STABILIZATION AND/OR PROPERTY SALE IN ACCORDANCE WITH WDNR REQUIREMENTS.
- CONTRACTOR SHALL TAKE ALL NECESSARY STEPS TO CONTROL DUST ARISING FROM CONSTRUCTION OPERATIONS. REFER TO WDNR TECHNICAL STANDARD 1068.
- SILT FENCE LOCATION REPRESENTED ON SHEET C2.0 INDICATES DISTURBANCE LIMITS. REFER TO CSECR NOTE 14 FOR DETAILS.
- STABILIZATION PRACTICES:
  - \* STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED. NO MORE THAN SEVEN (7) DAYS SHALL PASS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS CEASED UNLESS:
    - \* THE INITIATION STABILIZATION MEASURES BY THE SEVENTH (7) DAY AFTER CONSTRUCTION ACTIVITY HAS CEASED IS PRECLUDED BY SNOW COVER. IN THAT EVENT, STABILIZATION SHALL BE INITIATED AS SOON AS PRACTICABLE.
    - \* CONSTRUCTION ACTIVITY WILL RESUME ON A PORTION OF THE SITE WITHIN FOURTEEN (14) DAYS FROM WHEN ACTIVITY CEASED, (I.E. THE TOTAL TIME PERIOD THAT THE CONSTRUCTION ACTIVITY IS TEMPORARILY CEASED IS LESS THAN FOURTEEN (14) DAYS. IN THAT EVENT, STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE BY THE SEVENTH (7) DAY AFTER CONSTRUCTION ACTIVITY HAS TEMPORARILY CEASED.
    - \* STABILIZATION MEASURES SHALL BE DETERMINED BASED ON SITE CONDITIONS AT THE TIME OF CONSTRUCTION ACTIVITY HAS CEASED, INCLUDING BUT NOT LIMITED TO WEATHER CONDITIONS AND LENGTH OF TIME MEASURE MUST BE EFFECTIVE. THE FOLLOWING ARE ACCEPTABLE STABILIZATION MEASURES:
      - \* PERMANENT SEEDING; IN ACCORDANCE WITH APPROVED CONSTRUCTION SPECIFICATION
      - \* TEMPORARY SEEDING; MAY CONSIST OF SPRING OATS(100LBS/ACRE) AND/OR WHEAT OR CEREAL RYE (150LB/ACRE)
      - \* HYDRO-MULCHING WITH A TACKIFIER
      - \* GEOTEXTILE EROSION MATTING
      - \* SODDING

**LEGEND (GRADING AND EROSION CONTROL PLAN)**

- PROPERTY LINE
- SETBACK LINE
- EASEMENT LINE
- BUILDING OVERHANG LINE
- 978 --- EXISTING 1' CONTOUR
- 978 --- EXISTING 5' CONTOUR
- 978 --- PROPOSED 1' CONTOUR
- 978 --- PROPOSED 5' CONTOUR
- ST --- STORM SEWER
- GRADE BREAK
- SPOT ELEVATION
  - EP --- EDGE OF PAVEMENT
  - FG --- FINISH GRADE
  - EC --- EDGE OF CONCRETE
  - BC --- BACK OF CURB
  - TW --- TOP OF WALL
  - BW --- BOTTOM OF WALL
  - RIM --- RIM ELEVATION
- SILT FENCE
- SILT SOCK
- DISTURBANCE LIMITS
- INLET PROTECTION, TYPE D



CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
KENOSHA | APPLETON | WAUSAU

**MADISON REGIONAL OFFICE**  
161 HORIZON DRIVE, SUITE 101  
VERONA, WISCONSIN 53593  
P. 608.848.5060

CLIENT:  
**SUMMIT CREDIT UNION**

CLIENT ADDRESS:  
**4800 American Parkway  
MADISON, WI 53718**

PROJECT:  
**SUMMIT CREDIT UNION - WAUKESHA BRANCH**

PROJECT LOCATION:  
**2208 E MORELAND BOULEVARD  
WAUKESHA COUNTY**

PLAN MODIFICATIONS:

#	Date:	Description:
1	04.09.18	CITY PLAN REVIEW
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		



Design/Drawn: CLH  
Approved: WHD

SHEET TITLE:  
**GRADING AND EROSION CONTROL PLAN**

SHEET NUMBER:  
**C3.0**

JSD PROJECT NO: 18-8469

File: I:\2018\188469\DWG\188469 Con Docs.dwg Layout: C3.0 User: chuhta Plotted: Apr 06, 2018 - 4:22pm Xrefs:



THESE PLANS AND DESIGNS ARE COPYRIGHT PROTECTED AND MAY NOT BE USED IN WHOLE OR IN PART WITHOUT THE WRITTEN CONSENT OF JSD PROFESSIONAL SERVICES, INC.

**GENERAL NOTES**

- REFER TO THE EXISTING CONDITIONS SURVEY FOR EXISTING CONDITIONS NOTES AND LEGENDS.
- ALL WORK IN THE ROW SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR SEWER & WATER CONSTRUCTION IN WISCONSIN, LATEST EDITION AND CITY OF WAUKESHA REQUIREMENTS.
- NO SITE GRADING OUTSIDE OR DOWNSLOPE OF PROPOSED SILT FENCE LOCATION. NO LAND DISTURBANCE BEYOND PROPERTY LINES UNLESS OTHERWISE SHOWN.
- THIS PROJECT HAS BEEN DESIGNED AND WILL BE CONSTRUCTED IN COMPLIANCE WITH ALL OF THE WDNR WRAPP PERMIT APPLICATION STANDARDS.
- JSD SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER/CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY ANY OR ALL REGULATORY AGENCIES.

**CONSTRUCTION SITE EROSION CONTROL REQUIREMENTS (CSECR) NOTES:**

- ALL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE DESIGNED AND IMPLEMENTED IN ACCORDANCE WITH THE CURRENT DEPARTMENT OF NATURAL RESOURCES EROSION AND SEDIMENT CONTROL TECHNICAL STANDARDS WHICH ARE AVAILABLE AT: <http://www.dnr.state.wi.us/runoff/stormwater/techstds.htm>
- INSTALL EROSION CONTROL MEASURES PRIOR TO ANY SITE WORK, INCLUDING GRADING OR DISTURBANCE OF EXISTING SURFACE MATERIALS AS SHOWN ON PLAN. MODIFICATIONS TO SEDIMENT CONTROL DESIGN MAY BE CONDUCTED TO MEET UNFORESEEN FIELD CONDITIONS IF MODIFICATIONS CONFORM TO WDNR TECHNICAL STANDARDS.
- INSPECTIONS AND MAINTENANCE OF ALL EROSION CONTROL MEASURES SHALL BE ROUTINE (ONCE PER WEEK MINIMUM) TO ENSURE PROPER FUNCTION OF EROSION CONTROLS AT ALL TIMES. EROSION CONTROL MEASURES ARE TO BE IN WORKING ORDER AT THE END OF EACH WORK DAY.
- INSPECT EROSION CONTROL MEASURES AFTER EACH 1/2" OR GREATER RAINFALL. REPAIR ANY DAMAGE OBSERVED DURING THE INSPECTION.
- EROSION CONTROL MEASURES SHALL NOT BE REMOVED UNTIL ALL LAND DISTURBING CONSTRUCTION ACTIVITY AT THE SITE HAS BEEN COMPLETED AND THAT A UNIFORM PERENNIAL VEGETATIVE COVER HAS BEEN ESTABLISHED WITH A DENSITY OF AT LEAST 70% OF THE COVER FOR THE UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES OR THAT EMPLOY EQUIVALENT PERMANENT STABILIZATION MEASURES.
- INSTALL A TRACKING PAD, 50' LONG AND NO LESS THAN 12" THICK BY USE OF 3" CLEAR STONE. TRACKING PADS ARE TO BE MAINTAINED BY THE CONTRACTOR IN A CONDITION WHICH WILL PREVENT THE TRACKING OF MUD OR DRY SEDIMENT ONTO THE ADJACENT PUBLIC STREETS AFTER EACH WORKING DAY OR MORE FREQUENTLY AS REQUIRED.
- INSTALL EROSION CONTROLS ON THE DOWNSTREAM SIDE OF STOCKPILES.
- INSTALL TEMPORARY SEDIMENT TRAPS PER LATEST EDITION OF WDNR STORM WATER CONSTRUCTION TECHNICAL CONSTRUCTION SITE EROSION & SEDIMENT CONTROL STANDARDS NOTE 1063. SEDIMENT TRAPS SHALL BE SIZED BASED ON MEDIUM SOIL TEXTURAL CLASS. SEDIMENT TRAPS SHALL BE INSPECTED WITHIN 24 HOURS AFTER EVERY RAIN EVENT PRODUCING 0.5 INCHES OF RAIN OR MORE, AND AT A MINIMUM SEDIMENT SHALL BE REMOVED WHEN SEDIMENT REACHES A DEPTH OF 1 FOOT OR WHEN OUTLET BECOMES CLOGGED. SEDIMENT TRAPS SHALL BE REMOVED AND THE LOCATION STABILIZED AFTER THE DISTURBED AREA DRAINING TO THE SEDIMENT TRAP IS STABILIZED AND NO LONGER SUSCEPTIBLE TO EROSION. ALL SEDIMENT SHALL BE PROPERLY DISPOSED.
- INSTALL CHECK DAMS WITHIN DRAINAGE DITCHES AND IN FRONT OF SILT FENCING IN ANY LOW AREA ALL IN ACCORDANCE WITH WDNR TECHNICAL STANDARDS.
- EROSION CONTROL FOR UTILITY CONSTRUCTION (STORM SEWER, SANITARY SEWER, WATER MAIN, ETC.):
  - PLACE EXCAVATED TRENCH MATERIAL ON THE HIGH SIDE OF THE TRENCH.
  - BACKFILL, COMPACT, AND STABILIZE THE TRENCH IMMEDIATELY AFTER PIPE CONSTRUCTION.
  - DISCHARGE TRENCH WATER INTO A SEDIMENTATION BASIN OR FILTERING TANK IN ACCORDANCE WITH THE DEWATERING

- TECHNICAL STANDARD NO. 1061 PRIOR TO RELEASE INTO THE STORM SEWER, RECEIVING STREAM, OR DRAINAGE DITCH.
- ADDITIONAL EROSION CONTROL MEASURES, AS REQUESTED BY STATE INSPECTORS, LOCAL INSPECTORS, AND/OR ENGINEER SHALL BE INSTALLED WITHIN 24 HOURS OF REQUEST.
  - ALL SLOPES 4:1 OR GREATER SHALL BE STABILIZED WITH CLASS I, TYPE B EROSION MATTING AND DRAINAGE SWALES SHALL BE STABILIZED WITH CLASS II, TYPE B EROSION MATTING, WITHIN 7 DAYS OF REACHING FINAL GRADE AND/OR AS SOON AS CONDITIONS ALLOW. REFER BELOW TO "CSECR" NOTE NO. SIXTEEN (16) FOR STABILIZATION PRACTICES FOR POTENTIAL INTERIM STABILIZATION.
  - CONTRACTOR/OWNER SHALL FILE A NOTICE OF TERMINATION UPON VEGETATIVE STABILIZATION AND/OR PROPERTY SALE IN ACCORDANCE WITH WDNR REQUIREMENTS.
  - CONTRACTOR SHALL TAKE ALL NECESSARY STEPS TO CONTROL DUST ARISING FROM CONSTRUCTION OPERATIONS. REFER TO WDNR TECHNICAL STANDARD 1068.
  - SILT FENCE LOCATION REPRESENTED ON SHEET C2.0 INDICATES DISTURBANCE LIMITS. REFER TO CSECR NOTE 14 FOR DETAILS.
  - STABILIZATION PRACTICES:
    - \* STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED. NO MORE THAN SEVEN (7) DAYS SHALL PASS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS CEASED UNLESS:
      - \* THE INITIATION STABILIZATION MEASURES BY THE SEVENTH (7) DAY AFTER CONSTRUCTION ACTIVITY HAS CEASED IS PRECLUDED BY SNOW COVER. IN THAT EVENT, STABILIZATION SHALL BE INITIATED AS SOON AS PRACTICABLE.
      - \* CONSTRUCTION ACTIVITY WILL RESUME ON A PORTION OF THE SITE WITHIN FOURTEEN (14) DAYS FROM WHEN ACTIVITY CEASED, (I.E. THE TOTAL TIME PERIOD THAT THE CONSTRUCTION ACTIVITY IS TEMPORARILY CEASED IS LESS THAN FOURTEEN (14) DAYS. IN THAT EVENT, STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE BY THE SEVENTH (7) DAY AFTER CONSTRUCTION ACTIVITY HAS TEMPORARILY CEASED.
      - \* STABILIZATION MEASURES SHALL BE DETERMINED BASED ON SITE CONDITIONS AT THE TIME OF CONSTRUCTION ACTIVITY HAS CEASED, INCLUDING BUT NOT LIMITED TO WEATHER CONDITIONS AND LENGTH OF TIME MEASURE MUST BE EFFECTIVE. THE FOLLOWING ARE ACCEPTABLE STABILIZATION MEASURES:
        - \* PERMANENT SEEDING, IN ACCORDANCE WITH APPROVED CONSTRUCTION SPECIFICATION
        - \* TEMPORARY SEEDING, MAY CONSIST OF SPRING OATS(100LBS/ACRE) AND/OR WHEAT OR CEREAL RYE (150LB/ACRE)
        - \* HYDRO-MULCHING WITH A TACKIFIER
        - \* GEOTEXTILE EROSION MATTING
        - \* SOODING

**LEGEND (GRADING PLAN)**

- PROPERTY LINE
- SETBACK LINE
- EASEMENT LINE
- BUILDING LINE
- BUILDING OVERHANG LINE
- 978 ----- EXISTING 1' CONTOUR
- 978 ----- EXISTING 5' CONTOUR
- 978 ----- PROPOSED 1' CONTOUR
- 978 ----- PROPOSED 5' CONTOUR
- ST ----- STORM SEWER
- GRADE BREAK
- SPOT ELEVATION
- EP ----- EDGE OF PAVEMENT
- FG ----- FINISH GRADE
- EC ----- EDGE OF CONCRETE
- BC ----- BACK OF CURB
- TW ----- TOP OF WALL
- BW ----- BOTTOM OF WALL
- RM ----- RIM ELEVATION

934.20 FG



CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
KENOSHA | APPLETON | WAUSAU

MADISON REGIONAL OFFICE  
161 HORIZON DRIVE, SUITE 101  
VERONA, WISCONSIN 53593  
P. 608.848.5060

CLIENT:  
**SUMMIT CREDIT UNION**

CLIENT ADDRESS:  
**4800 American Parkway  
MADISON, WI 53718**

PROJECT:  
**SUMMIT CREDIT UNION - WAUKESHA BRANCH**

PROJECT LOCATION:  
**2208 E MORELAND BOULEVARD  
WAUKESHA COUNTY**

PLAN MODIFICATIONS:

#	Date	Description
1	04.09.18	CITY PLAN REVIEW
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		


Design/Drawn: CLH  
Approved: WHD

SHEET TITLE:  
**DETAILED GRADING PLAN**

SHEET NUMBER:  
**C3.1**

JSD PROJECT NO: 18-8469

File: I:\2018\188469\DWG\188469\_Con\_Docs.dwg Layout: C3.1 User: chuhta\_Plotter: Apr 06, 2018 - 4:23pm Xref:s



THESE PLANS AND DESIGNS ARE COPYRIGHT PROTECTED AND MAY NOT BE USED IN WHOLE OR IN PART WITHOUT THE WRITTEN CONSENT OF JSD PROFESSIONAL SERVICES, INC.

**GENERAL NOTES**

- REFER TO THE EXISTING CONDITIONS SURVEY FOR EXISTING CONDITIONS NOTES AND LEGENDS.
- ALL WORK IN THE ROW SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR SEWER & WATER CONSTRUCTION IN WISCONSIN, LATEST EDITION AND CITY OF WAUKESHA REQUIREMENTS.
- NO SITE GRADING OUTSIDE OR DOWNSLOPE OF PROPOSED SILT FENCE LOCATION. NO LAND DISTURBANCE BEYOND PROPERTY LINES UNLESS OTHERWISE SHOWN.
- THIS PROJECT HAS BEEN DESIGNED AND WILL BE CONSTRUCTED IN COMPLIANCE WITH ALL OF THE WDNR WRAPP PERMIT APPLICATION STANDARDS.
- JSD SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER/CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY ANY OR ALL REGULATORY AGENCIES.

PROPOSED STORM SEWER STRUCTURES SCHEDULE					
LABEL	INVERT ELEV. (FT)	RIM ELEV. (FT)	DEPTH (FT)	STRUCTURE DESCRIPTION	GRATE
STO INL-1	927.94	930.77	2.83	2'X3' INLET BOX	R-3067, CURB INLET FRAME, GRATE, CURB BOX - TYPE L GRATE
STO INL-2	927.78	930.05	2.27	2'X3' INLET BOX	R-3067, CURB INLET FRAME, GRATE, CURB BOX - TYPE L GRATE
STO INL-3	929.70	933.55	3.85	2'X3' INLET BOX	R-3067, CURB INLET FRAME, GRATE, CURB BOX - TYPE L GRATE
STO INL-4	929.50	934.04	4.54	2'X3' INLET BOX	R-3067, CURB INLET FRAME, GRATE, CURB BOX - TYPE L GRATE
STO INL-5	930.35	934.43	4.08	2'X3' INLET BOX	R-3067, CURB INLET FRAME, GRATE, CURB BOX - TYPE L GRATE
STO INL-6	930.95	934.02	3.07	2'X3' INLET BOX	R-3067, CURB INLET FRAME, GRATE, CURB BOX - TYPE L GRATE
STO MH 1	927.60	931.95	4.35	36" DIA. MANHOLE	R-1550A MANHOLE FRAME - SOLID LID NON-ROCKING
STM MH 2	924.22	934.51	10.29	36" DIA. MANHOLE	R-1550A MANHOLE FRAME - SOLID LID NON-ROCKING
WQ Chamber	926.25	934.87	8.62	2 - ACCESS RISERS	R-1550A MANHOLE FRAME - SOLID LID NON-ROCKING


PROPOSED STORM SEWER PIPE SCHEDULE							
PIPE LABEL	FROM	TO	LENGTH (FT)	INVERT ELEVATION (FT)	DISCHARGE ELEVATION (FT)	SLOPE (%)	PIPE SIZE & TYPE
P-1	STO INL-1	STO INL-2	23.00	927.88	927.94	0.25	10" PVC
P-2	STO INL-2	STO MH 1	20.00	927.70	927.78	0.40	12" PVC
P-3	STO MH 1	WQ Chamber	137.00	926.25	927.60	0.98	12" PVC
P-4	STO INL-3	WQ Chamber	19.00	928.75	929.70	5.00	6" PVC
P-5	STO INL-4	WQ Chamber	15.00	928.75	929.50	5.00	6" PVC
P-6	STO INL-5	WQ Chamber	32.00	928.75	930.35	5.00	6" PVC
P-7	STO INL-6	STO INL-5	10.00	930.45	930.95	5.00	6" PVC
P-8	RD	STO INL-6	37.00	931.05	932.90	5.00	8" PVC
P-9	WQ Chamber	STO MH 2	8.00	926.17	926.25	1.00	12" PVC

**LEGEND (UTILITY PLAN)**

- PROPERTY LINE
- SETBACK LINE
- EASEMENT LINE
- BUILDING LINE
- BUILDING OVERHANG LINE
- SAN ----- SANITARY SEWER
- W ----- WATERMAIN
- ST ----- STORM SEWER

**UTILITY NOTES:**

- IF ANY ERRORS, DISCREPANCIES, OR OMISSIONS WITHIN THE PLAN BECOME APPARENT, IT SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION SO THAT CLARIFICATION OR REDESIGN MAY OCCUR.
- LENGTHS OF ALL UTILITIES ARE TO CENTER OF STRUCTURES OR FITTINGS AND MAY VARY SLIGHTLY FROM PLAN. LENGTHS SHALL BE VERIFIED IN THE FIELD DURING CONSTRUCTION.
- THE CONTRACTOR SHALL INSTALL A PEDESTRIAN FENCE AROUND ALL EXCAVATIONS TO BE LEFT OPEN OVER NIGHT AS REQUIRED.
- THE PROPOSED IMPROVEMENTS MUST BE CONSTRUCTED IN ACCORDANCE WITH ENGINEERING PLANS DESIGNED TO MEET ORDINANCES AND REQUIREMENTS OF THE MUNICIPALITY AND WISDOT, WDSPS, AND WDNR.
- PRIOR TO CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR:
  - EXAMINING ALL SITE CONDITIONS RELATIVE TO THE CONDITIONS INDICATED ON THE ENGINEERING DRAWINGS. ANY DISCREPANCIES ARE TO BE REPORTED TO THE ENGINEER AND RESOLVED PRIOR TO THE START OF CONSTRUCTION.
  - OBTAINING ALL PERMITS INCLUDING PERMIT COSTS, TAP FEES, METER DEPOSITS, BONDS, AND ALL OTHER FEES REQUIRED FOR PROPOSED WORK TO OBTAIN OCCUPANCY.
  - VERIFYING UTILITY ELEVATIONS AND NOTIFYING ENGINEER OF ANY DISCREPANCY. NO WORK SHALL BE PERFORMED UNTIL THE DISCREPANCY IS RESOLVED.
  - NOTIFYING ALL UTILITIES PRIOR TO THE INSTALLATION OF ANY UNDERGROUND IMPROVEMENTS.
  - NOTIFYING THE DESIGN ENGINEER AND MUNICIPALITY 48 HOURS PRIOR TO THE START OF CONSTRUCTION TO ARRANGE FOR APPROPRIATE CONSTRUCTION OBSERVATION.
- THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING THE ENGINEER WITH AS-BUILT CONDITIONS OF THE DESIGNATED IMPROVEMENTS IN ORDER THAT THE APPROPRIATE DRAWINGS CAN BE PREPARED, IF REQUIRED. ANY CHANGES TO THE DRAWINGS OR ADDITIONAL ITEMS MUST BE REPORTED TO THE ENGINEER AS WORK PROGRESSES.
- THE PRIME CONTRACTOR IS RESPONSIBLE FOR COORDINATING ALL CONSTRUCTION WITH OTHER CONTRACTORS INVOLVED WITH CONSTRUCTION OF THE PROPOSED DEVELOPMENT AND FOR REPORTING ANY ERRORS OR DISCREPANCIES BETWEEN THESE PLANS AND PLANS PREPARED BY OTHERS.
- ANY SANITARY SEWER, SANITARY SEWER SERVICES, WATER MAIN, WATER SERVICES, STORM SEWER, OR OTHER UTILITIES, WHICH ARE DAMAGED BY THE CONTRACTORS, SHALL BE REPAIRED TO THE OWNER'S SATISFACTION AT THE CONTRACTOR'S EXPENSE.
- CONTRACTOR IS RESPONSIBLE FOR SITE SAFETY DURING THE CONSTRUCTION OF IMPROVEMENTS.
- CONTRACTOR SHALL CONTACT THE CITY OF WAUKESHA PUBLIC WORKS DEPARTMENT A MINIMUM OF 48 HOURS BEFORE CONNECTING TO PUBLIC UTILITIES. CONTRACTOR TO VERIFY SIZE AND DEPTH OF EXISTING UTILITY SERVICES AND REPORT ANY DISCREPANCIES TO THE ENGINEER PRIOR TO CONNECTING.
- CONTRACTOR MUST CONTACT AND IS REQUIRED TO NOTIFY THE CITY OF WAUKESHA WATER UTILITY 48 HOURS IN ADVANCE OF CONNECTING TO THE PUBLIC UTILITY.
- ALL WATER MAIN MUST BE GAPPED AT EVERY 2,000 FOOT INTERVAL. WATER MAIN MUST BE FILLED AND SAFE WATER TESTED PRIOR TO FILLING AND FLUSHING ANY ADDITIONAL 2,000 FOOT PIPE SEGMENTS, PER VILLAGE OF COTTAGE GROVE WATER & SEWER UTILITY. WATER MAIN INSTALLATION SEQUENCE:
  - INSTALL WATER MAIN - MUST LEAVE A GAP AT THE EXISTING MAIN.
  - FILL WATER MAIN (PRESSURE TEST THE WATER MAIN. CONTRACTOR OPTION)
  - OBTAIN A SAFE WATER SAMPLE
  - TAP SERVICES. TAPS MUST BE MADE UNDER SYSTEM PRESSURE
  - PRESSURE TEST MAIN
  - MAKE WET CONNECTION TO EXISTING WATER MAIN
  - CONNECTION WILL ALSO BE REQUIRED WHEN THE FOLLOWING CONDITIONS ARE MET: WATER MAIN INSTALLATION UP TO 2000' AND/OR 30 DAYS OF INACTIVITY OF WATER MAIN INSTALLATION, WHICH EVER COMES FIRST.
- ALL PRIVATE SANITARY BUILDING PIPE AND TUBING SHALL CONFORM TO SPS 384.30-2.
- ALL PRIVATE STORM BUILDING PIPE AND TUBING SHALL CONFORM TO SPS 384.30-3.
- ALL PRIVATE PIPE AND TUBING FOR WATER SERVICE SHALL CONFORM TO SPS 384.30-4.
- ALL PRIVATE STORM PIPE SHALL CONFORM TO SPS 382.40(B)(4).
- ALL PRIVATE PIPE SHALL BE INSTALLED PER SPS 382.40-8 INCLUDING AT LEAST 8' OF HORIZONTAL DISTANCE BETWEEN WATER PIPING AND SANITARY SEWER FROM CENTER OF PIPE TO CENTER OF PIPE AND 6' OF SEPARATION BETWEEN STORM SEWER AND WATER PIPING.
- ALL LOCATIONS WHERE STORM SEWER AND WATER MAIN ARE CROSSING AND LESS THAN 3 FEET OF VERTICAL/HORIZONTAL SEPARATION IS PROVIDED, WATER MAIN SHALL BE INSULATED PER STANDARD SPECIFICATIONS FOR SEWER AND WATER CONSTRUCTION IN WISCONSIN LATEST EDITION. INSULATION SHALL CREATE A "BOX" ENCLOSED THE TOP AND SIDES OF WATER MAIN.
- ADJUST ALL EXISTING PUBLIC WATER VALVE BOXES, HYDRANTS, MANHOLE CASTINGS, AND INLET CASTINGS TO GRADE WITH ACCORDANCE WITH THE STANDARDS OF THE MUNICIPALITY. REPLACE VALVE BOXES, HYDRANT SHOES, AND MANHOLE/INLET SECTIONS AS REQUIRED.
- SEE ELECTRICAL AND LIGHTING PLANS FOR SITE ELECTRIC, CABLE AND FIBER OPTICS FOR DETAILS AND ROUTING.



**EAST MORELAND BOULEVARD (USH 18)**

**HERITAGE LANE**



CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
KENOSHA | APPLETON | WAUSAU

**MADISON REGIONAL OFFICE**  
161 HORIZON DRIVE, SUITE 101  
VERONA, WISCONSIN 53593  
P. 608.848.5060

CLIENT:  
**SUMMIT CREDIT UNION**

CLIENT ADDRESS:  
**4800 American Parkway  
MADISON, WI 53718**

PROJECT:  
**SUMMIT CREDIT UNION - WAUKESHA BRANCH**

PROJECT LOCATION:  
**2208 E MORELAND BOULEVARD  
WAUKESHA COUNTY**













PLAN MODIFICATIONS:		
#	Date:	Description:
1	04.09.18	CITY PLAN REVIEW
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		

Design/Drawn: CLH  
Approved: WHD

SHEET TITLE:  
**UTILITY PLAN**

SHEET NUMBER:  
**C4.0**





CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
KENOSHA | APPLETON | WAUSAU

**MADISON REGIONAL OFFICE**  
161 HORIZON DRIVE, SUITE 101  
VERONA, WISCONSIN 53593  
P. 608.848.5060

CLIENT:  
**SUMMIT CREDIT UNION**

CLIENT ADDRESS:  
**4800 American Parkway  
MADISON, WI 53718**

PROJECT:  
**SUMMIT CREDIT UNION - WAUKESHA BRANCH**

PROJECT LOCATION:  
**2208 E MORELAND BOULEVARD  
WAUKESHA COUNTY**

PLAN MODIFICATIONS:

#	Date:	Description:
1	04.09.18	CITY PLAN REVIEW
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		



Design/Drawn:  
Approved:

SHEET TITLE:  
**DETAILS**

SHEET NUMBER:  
**C5.0**



File: I:\2018\188469\DWG\188469\_Details.dwg Layout: C5.1 User: chuhta Plotted: Apr. 06, 2018 - 4:16pm Xref's:



CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
KENOSHA | APPLETON | WAUSAU

MADISON REGIONAL OFFICE  
161 HORIZON DRIVE, SUITE 101  
VERONA, WISCONSIN 53593  
P. 608.848.5060

CLIENT:

**SUMMIT CREDIT UNION**

CLIENT ADDRESS:

**4800 American Parkway  
MADISON, WI 53718**

PROJECT:

**SUMMIT CREDIT UNION - WAUKESHA BRANCH**

PROJECT LOCATION:

**2208 E MORELAND BOULEVARD  
WAUKESHA COUNTY**

PLAN MODIFICATIONS:

#	Date:	Description:
1	04.09.18	CITY PLAN REVIEW
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		

Design/Drawn:

Approved:

SHEET TITLE:

**DETAILS**

SHEET NUMBER:

**C5.1**

JSD PROJECT NO:

18-8469



THESE PLANS AND DESIGNS ARE COPYRIGHT PROTECTED AND MAY NOT BE USED IN WHOLE OR IN PART WITHOUT THE WRITTEN CONSENT OF JSD PROFESSIONAL SERVICES, INC.

PLANT SCHEDULE					
Ø1-DECIDUOUS TREES	QTY	BOTANICAL NAME	COMMON NAME	CONT	SIZE
	3	<i>Acer rubrum</i> 'October Glory'™	October Glory Maple	B & B	2.5" Cal
	2	<i>Amelanchier x grandiflora</i> 'Autumn Brilliance'	Autumn Brilliance Serviceberry	B & B	1.5" Cal
	2	<i>Malus x 'Spring Snow'</i>	Spring Snow Crab Apple	B & B	1.5" Cal
	1	<i>Tilia cordata</i> 'Greenspire'	Greenspire Littleleaf Linden	B & B	2.5" Cal
Ø2-EVERGREEN TREES	QTY	BOTANICAL NAME	COMMON NAME	CONT	SIZE
	18	<i>Thuja occidentalis</i> 'Holmstrup'	Holmstrup Arborvitae	B & B	Min. 6" Ht.

PLANT SCHEDULE					
Ø3-DECIDUOUS SHRUBS	QTY	BOTANICAL NAME	COMMON NAME	CONT	SIZE
	22	<i>Cornus stolonifera</i> 'Farrow'	Arctic Fire Redtwig Dogwood	3 gal	18-24" Ht.
	7	<i>Genista tinctoria</i>	Golden Temple Woodwaxen	2 gal	18-12" Ht.
	16	<i>Physocarpus opulifolius</i> 'Dart's Gold'	Yellow Ninebark	3 gal	18-24" Ht.
	16	<i>Spiraea fritschiana</i>	Korean Spirea	2 gal	18-12" Ht.
	12	<i>Viburnum dentatum</i> 'Rastzam'	Raspberry Tart Viburnum	3 gal	18-24" Ht.
	2	<i>Viburnum opulus</i> 'Compactum'	Compact European Cranberrybush	3 gal	18-24" Ht.
Ø4-EVERGREEN SHRUBS	QTY	BOTANICAL NAME	COMMON NAME	CONT	SIZE
	35	<i>Juniperus horizontalis</i> 'Bar Harbor'	Bar Harbor Juniper	3 gal	18-12" Ht.
	11	<i>Microbiota decussata</i> 'Candrew'	Drew's Blue Siberian Carpet Cypress	3 gal	6" Ht.
	28	<i>Thuja occidentalis</i> 'Hetz Midget'	Hetz Midget Arborvitae	3 gal	18-24" Ht.

Ø5-ORNAMENTAL GRASSES				
QTY	BOTANICAL NAME	COMMON NAME	CONT	SIZE
68	<i>Calamagrostis brachytricha</i>	Reed Grass	1 gal	18-24" Ht.
67	<i>Deschampsia cespitosa</i> 'Goldtau'	Gold Dew Tufted Hair Grass	4" pot	18-12" Ht.
66	<i>Panicum virgatum</i> 'Heavy Metal'	Heavy Metal Switch Grass	1 gal	18-24" Ht.
68	<i>Panicum virgatum</i> 'Northwind'	Northwind Switch Grass	1 gal	18-24" Ht.
14	<i>Sporobolus heterolepis</i>	Prairie Dropseed	1 gal	18-12" Ht.
Ø6-PERENNIALS				
QTY	BOTANICAL NAME	COMMON NAME	CONT	SIZE
5	<i>Astilbe x arendsii</i> 'Bridal Veil'	Bridal Veil Astilbe	1 gal	18-12" Ht.
9	<i>Echinacea purpurea</i> 'White Swan'	White Swan Coneflower	1 gal	18-12" Ht.
16	<i>Echinacea purpurea</i> 'Ruby Star'	Ruby Star Coneflower	1 gal	18-12" Ht.
85	<i>Heemerocallis x 'Stella de Oro'</i>	Stella de Oro Daylily	4" pot	18-12" Ht.



CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
KENOSHA | APPLETON | WAUSAU

MADISON REGIONAL OFFICE  
161 HORIZON DRIVE, SUITE 101  
VERONA, WISCONSIN 53593  
P. 608.848.5060

CLIENT:  
**SUMMIT CREDIT UNION**

CLIENT ADDRESS:  
**4800 American Parkway  
MADISON, WI 53718**

PROJECT:  
**SUMMIT CREDIT UNION - WAUKESHA BRANCH**

PROJECT LOCATION:  
**2208 E MORELAND BOULEVARD  
WAUKESHA COUNTY**

PLAN MODIFICATIONS:		
#	Date:	Description:
1	04.09.18	CITY PLAN REVIEW
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		

Design/Drawn: ABK  
Approved: MAS

SHEET TITLE:  
**LANDSCAPE PLAN**

SHEET NUMBER:  
**L1.0**


JSD PROJECT NO: 18-8469

**LEGEND (PROPOSED)**


- PROPERTY LINE
- SETBACK LINE
- EASEMENT LINE
- BUILDING LINE
- BUILDING OVERHANG LINE
- EDGE OF CONCRETE
- STANDARD CURB AND GUTTER
- REJECT CURB AND GUTTER
- PROPOSED CONCRETE PAVEMENT
- PROPOSED HEAVY DUTY CONCRETE PAVEMENT
- PROPOSED ASPHALT PAVEMENT
- PROPOSED HEAVY DUTY ASPHALT PAVEMENT
- LIGHT POLE
- BOLLARD

**GENERAL NOTES:**

- REFER TO THE EXISTING CONDITIONS SURVEY FOR EXISTING CONDITIONS NOTES AND LEGEND.
- ALL WORK IN THE ROW SHALL BE IN ACCORDANCE WITH THE CITY OF WAUKESHA STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION.
- JSD SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER/CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY ANY OR ALL REGULATORY AGENCIES.
- DRAWING FOR REVIEW - NOT FOR CONSTRUCTION UNLESS OTHERWISE NOTED IN THE TITLE BLOCK.
- THE LANDSCAPE CONTRACTOR SHALL COORDINATE ALL FINE GRADING AND TOPSOILING WITH GENERAL CONTRACTOR
- REFER TO SHEET L2.0 FOR ADDITIONAL DETAILS, NOTES AND SPECIFICATION INFORMATION INCLUDING MATERIALS, GUARANTEE AND EXECUTION RELATED TO LANDSCAPE PLAN




**EAST MORELAND BOULEVARD  
(USH 18)**




File: I:\2018\188469\DWG\188469 Landscape.dwg Layout: L1.0 User: akoniewski Plotted: Apr 05, 2018 - 4:47pm Xref's: 188469 Summit Credit Union - Waukesha






STRAPPING ATTACHMENT AND STAKING DETAIL




DECIDUOUS TREE PLANTING DETAIL

N.T.S.




EVERGREEN TREE PLANTING DETAIL

N.T.S.




DECIDUOUS SHRUB PLANTING DETAIL

N.T.S.





EVERGREEN SHRUB PLANTING DETAIL

N.T.S.



PERENNIAL/ORNAMENTAL GRASS PLANTING DETAIL

N.T.S.




TREE NOTES:

1. CONTRACTOR SHALL INSTALL TREE PROTECTION FENCING IN THE AREA SURROUNDING THE TREE WITHIN THE CRITICAL ROOT RADIUS
2. NO EXCAVATION IS PERMITTED WITHIN THE CRITICAL ROOT RADIUS
3. IF EXCAVATION WITHIN THE CRITICAL ROOT RADIUS OF ANY TREE IS NECESSARY, CONTRACTOR SHALL CONTACT CITY FORESTER PRIOR TO EXCAVATION TO ASSESS THE IMPACT TO THE TREE AND ROOT SYSTEM.


TREE PROTECTION DETAIL

N.T.S.



LANDSCAPE EDGING DETAIL

N.T.S.



TYPICAL PARKING ISLAND DETAIL

N.T.S.

GENERAL NOTES

1. GENERAL: ALL WORK IN THE R-O-W AND PUBLIC EASEMENTS SHALL BE IN ACCORDANCE WITH LOCAL MUNICIPAL REQUIREMENTS. JSD SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER/CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY ANY OR ALL REGULATORY AGENCIES. LOCATE ALL UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR REPAIRING ANY DAMAGE DONE TO UTILITIES. CONTRACTOR MUST CALL 1-800-382-5444 FOR UTILITY LOCATIONS AT LEAST THREE DAYS PRIOR TO DIGGING. HAND DIG AND INSTALL ALL PLANTS THAT ARE NEAR EXISTING UTILITIES. PROTECT PREVIOUSLY INSTALLED WORK OF OTHER TRADES. CONTRACTOR IS RESPONSIBLE FOR STAKING THE PLANT MATERIALS FOR REVIEW BY OWNER PRIOR TO DIGGING AND PLACEMENT AND SHALL COORDINATE ALL FINE GRADING AND RESTORATION WITH THE GRADING CONTRACTOR.
2. DELIVERY AND HANDLING: DO NOT DELIVER MORE PLANT MATERIALS THAN CAN BE PLANTED IN ONE DAY, UNLESS ADEQUATE, APPROPRIATE AND SECURE STORAGE IS PROVIDED AND APPROVED BY OWNER'S REPRESENTATIVE. AT ALL TIMES, PROTECT ALL PLANT MATERIALS FROM WIND AND DIRECT SUN. DELIVER PLANTS WITH LEGIBLE IDENTIFICATION LABELS. PROTECT PLANTS DURING DELIVERY AND DO NOT PRUNE PRIOR TO DELIVERY. ALL TREES AND SHRUBS SHALL BE PLANTED ON THE DAY OF DELIVERY; IF THIS IS NOT POSSIBLE, PROTECT THE PLANT MATERIALS NOT PLANTED BY STORING THEM IN A SHADED, SECURE AREA, PROTECTING THE ROOT MASS WITH WET SOIL, MULCH, HAY OR OTHER SUITABLE MEDIUM. CONTRACTOR TO KEEP ALL PLANT MATERIALS ADEQUATELY WATERED TO PREVENT ROOT DESICCATION. DO NOT REMOVE CONTAINER GROWN STOCK FROM CONTAINERS BEFORE TIME OF PLANTING. DO NOT PICK UP CONTAINER OR BALLED PLANTS BY STEM OR ROOTS. ALL PLANTS SHALL BE LIFTED AND HANDLED FROM THE BOTTOM OF THE CONTAINER OR BALL. PERFORM ACTUAL PLANTING ONLY WHEN WEATHER AND SOIL CONDITIONS ARE SUITABLE IN ACCORDANCE WITH LOCALLY ACCEPTED BEST HORTICULTURAL PRACTICES.
3. MATERIALS - PLANTS: ALL PLANTS SHALL CONFORM TO THE AMERICAN STANDARD FOR NURSERY STOCK ANSI Z60.1-2004. PLANTS SHALL BE TRUE TO SPECIES AND VARIETY SPECIFIED AND NURSERY GROWN IN ACCORDANCE WITH GOOD HORTICULTURAL PRACTICES UNDER CLIMATIC CONDITIONS SIMILAR TO THOSE IN THE LOCALITY OF THE PROJECT FOR AT LEAST 2 YEARS. PLANTS SHALL BE FRESHLY DUG (DURING THE MOST RECENT FAVORABLE HARVEST SEASON). PLANTS SHALL BE SO TRAINED IN DEVELOPMENT AND APPEARANCE AS TO BE UNQUESTIONABLY SUPERIOR IN FORM, COMPACTNESS, AND SYMMETRY. PLANTS SHALL BE SOUND, HEALTHY, VIGOROUS, WELL BRANCHED AND DENSELY FOLIATED WHEN IN LEAF, AND FREE OF DISEASE AND INSECTS (ADULT EGGS, PUPAE OR LARVAE). THEY SHALL HAVE HEALTHY, WELL-DEVELOPED ROOT SYSTEMS AND SHALL BE FREE FROM PHYSICAL DAMAGE OR OTHER CONDITIONS THAT WOULD PREVENT THRIVING GROWTH. PLANTS SHALL BE OF THE HIGHEST QUALITY, POSSESS TYPICAL GROWTH HABITS AND FORM FOR THEIR SPECIES AND BE FREE OF INJURY. PARKWAY TREES AND PARKING LOT TREES SHALL HAVE A MINIMUM BRANCHING HEIGHT OF SIX (6) FEET ABOVE THE GROUND TO ALLOW ADEQUATE VISUAL AND PHYSICAL CLEARANCE.
4. PRUNING: THE CONTRACTOR SHALL PRUNE ALL TREES AND REPAIR ANY INJURIES THAT OCCURRED DURING THE PLANTING PROCESS. DOUBLE LEADERS, DEAD BRANCHES, AND LIMBS DAMAGED OR BROKEN DURING THE PLANTING PROCESS SHALL BE PRUNED. THIS SHALL BE THE ONLY PRUNING ALLOWED AT PLANTING. PRUNING SHALL CONFORM TO AMERICAN STANDARD FOR TREE CARE OPERATIONS, ANSI A300. PRUNE TREES IN ACCORDANCE WITH NAA GUIDELINES. DO NOT TOP TREES. PRUNE SHRUBS ACCORDING TO STANDARD HORTICULTURAL PRACTICES. ON CUTS OVER 3/4" IN DIAMETER AND BRUISES OR SCARS ON BARK, TRACE THE INJURED CAMBIAL LAYER BACK TO LIVING TISSUE AND REMOVE. SMOOTH AND SHAPE WOUNDS SO AS NOT TO RETAIN WATER. TREAT THE AREA WITH AN APPROVED INCONSPICUOUS LATEX BASED ANTISEPTIC TREE PAINT, IF PRUNING OCCURS "IN SEASON", DO NOT PRUNE ANY OAK TREES DURING THE MONTHS FROM APRIL TO OCTOBER.
5. CLEANUP: DISPOSED OF EXCESS SOIL. REMOVE ALL CUTTINGS AND WASTE MATERIALS. SOIL, BRANCHES, BINDING AND WRAPPING MATERIALS, REJECTED PLANTS, OR OTHER DEBRIS RESULTING FROM ANY PLANTING SHALL BE PROMPTLY CLEANED UP AND REMOVED. THE WORK AREA SHALL BE KEPT SAFE AND NEAT AT ALL TIMES. UNDER NO CIRCUMSTANCES SHALL THE ACCUMULATION OF SOIL, BRANCHES OR OTHER DEBRIS BE ALLOWED UPON A PUBLIC PROPERTY IN SUCH A MANNER AS TO RESULT IN A PUBLIC SAFETY HAZARD. LIKEWISE, UNDER NO CIRCUMSTANCES SHALL ANY DEBRIS OR INCIDENTAL MATERIALS BE ALLOWED UPON ADJACENT PRIVATE PROPERTY.

LANDSCAPE MATERIAL NOTES

1. MATERIALS - SOIL: PLANTING SOIL SHALL MEET THESE REQUIREMENTS:
  - A. PLANTING AREAS = 24"
  - B. TREE PITS = SEE DETAILS
2. PLANTING SOIL TO BE A MINIMUM 24" DEPTH, UNLESS OTHERWISE SPECIFIED AS ABOVE OR ON DETAILS. TOPSOIL TO BE CLEAN, FRIABLE LOAM FROM A LOCAL SOURCE, FREE FROM STONES OR DEBRIS OVER 3/4" IN DIAMETER, AND FREE FROM TOXINS. TOPSOIL SHALL HAVE A pH VALUE BETWEEN 6 AND 7. TOPSOIL AND PLANTING SOIL SHALL BE TESTED TO CONFORM TO THESE SPECIFICATIONS AND SHALL BE AMENDED TO MEET THESE SPECIFICATIONS. PROVIDE TEST RESULTS TO OWNER'S REPRESENTATIVE PRIOR TO PLACEMENT DO NOT PLACE FROZEN OR MUDDY TOPSOIL. APPLY SOIL AMENDMENTS TO ALL LANDSCAPE AREAS PER SOIL TEST.
3. MATERIALS - SHREDDED HARDWOOD BARK MULCH: ALL PLANTING AREAS LABELED ON PLAN SHALL RECEIVE CERTIFIED WEED FREE SHREDDED HARDWOOD BARK MULCH OVER ALL PLANTING AREAS. SHREDDED HARDWOOD BARK MULCH SIZE & COLOR TO BE APPROVED BY OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION. FERTILIZER SHALL BE IN ACCORDANCE WITH APPLICABLE LOCAL, COUNTY AND STATE OF WISCONSIN REQUIREMENTS. SHREDDED HARDWOOD BARK MULCH AREAS SHALL NOT RECEIVE WOVEN WEED BARRIER FABRIC.
4. MATERIALS - STONE MULCH: ALL PLANTING AREAS LABELED ON PLAN SHALL RECEIVE DECORATIVE STONE MULCH SPREAD TO A CONSISTENT DEPTH OF THREE INCHES OVER ENTIRE PLANTING AREA. DECORATIVE STONE MULCH TYPE, SIZE & COLOR TO BE APPROVED BY OWNER IN ACCORDANCE WITH APPLICABLE LOCAL, COUNTY AND STATE OF WISCONSIN REQUIREMENTS. STONE MULCH AREAS SHALL RECEIVE WOVEN WEED BARRIER FABRIC.
5. MATERIALS - TREE & SHRUB RINGS: ALL TREES AND/OR SHRUBS PLANTED IN SEEDED LAWN AREAS TO BE INSTALLED WITH A MINIMUM 5' DIAMETER SHREDDED HARDWOOD BARK MULCH TREE RING SPREAD TO A CONSISTENT DEPTH OF 4 INCHES. ALL TREE RINGS SHOULD BE INSTALLED WITH A 5" DEPTH SHOVEL CUT EDGE, ANGLED 45 DEGREES INTO SOIL AT A 5" DIAMETER ABOUT THE CENTER OF THE TREE. PLANTING. A PRE-EMERGENT GRANULAR HERBICIDE WEED-PREVENTER SHOULD BE MIXED WITH MULCH USED TO INSTALL TREE RING AS WELL AS TOPICALLY APPLIED TO FINISHED INSTALLATION OF TREE RING.
6. MATERIALS - WEED BARRIER FABRIC: ALL DECORATIVE STONE MULCH PLANTING AREAS SHALL BE INSTALLED WITH WOVEN WEED BARRIER FABRIC. NO PLASTIC/IMPERVIOUS BARRIERS WILL BE PERMITTED. EXAMPLE: BLACK VISQUEEN. SHREDDED HARDWOOD BARK MULCH AREAS SHALL NOT RECEIVE WOVEN WEED BARRIER FABRIC.
7. MATERIALS - EDGING: EDGING SHALL BE 5" DEEP, POLYETHYLENE EDGING. OWNER'S REPRESENTATIVE SHALL APPROVE PRODUCT SPECIFICATION PROVIDED BY LANDSCAPE CONTRACTOR.
8. MATERIALS - SEED: DISTURBED LAWN AREAS LABELED ON PLAN AS SUCH, SHALL BE SPREAD BY HAND BROADCAST METHOD OR APPROPRIATE SPREADER EQUIPMENT WITH EARTH CARPET'S "MADISON PARKS" OR EQUIVALENT AS APPROVED BY THE OWNER'S REPRESENTATIVE, INSTALLED PER MANUFACTURER'S RECOMMENDATIONS. IN ADDITION TO LAWN SEED, ANNUAL RYE SHALL BE APPLIED TO ALL DISTURBED AREAS AT A RATE OF 1 1/2 LBS PER 1000 SQUARE FEET. FERTILIZE AND MULCH PER MANUFACTURER'S RECOMMENDATIONS.
9. MATERIALS - SOD: ALL AREAS SPECIFIED ON PLAN PER THESE NOTES: TURFGRASS SOD: CLASS OF TURFGRASS SOD SHALL BE PREMIUM GRADE APPROVED TURFGRASS SOD. ONLY IMPROVED TYPES OF SOD (ELITE) ARE ACCEPTABLE. TURFGRASS SHALL BE MACHINE CUT AT A UNIFORM THICKNESS OF .60 INCH, PLUS OR MINUS .25 INCH. AT TIME OF CUTTING, MEASUREMENT FOR THICKNESS SHALL EXCLUDE TOP GROWTH AND THATCH AND LAKE ROLL TURFGRASS. SOD SHALL BE CUT TO THE SUPPLIER'S STANDARD WIDTH (36-48 INCHES) AND LENGTH. BROKEN PADS AND TORN OR UNEVEN ENDS WILL NOT BE ACCEPTABLE. STANDARD SIZE SECTIONS OF TURFGRASS SOD SHALL BE STRONG ENOUGH SO THAT THEY CAN BE PICKED UP AND HANDLED WITHOUT DAMAGE. TURFGRASS SOD SHALL NOT BE HARVESTED OR TRANSPORTED WHEN MOISTURE CONTENT IS EXCESSIVELY DRY OR WET, AS THIS MAY ADVERSELY AFFECT ITS SURVIVAL. POST-PLANT IRRIGATION WILL BE NECESSARY TO ENSURE SOD STAYS ALIVE AND ROOTS INTO SOIL. THE CONTRACTOR IS RESPONSIBLE FOR WATERING SOD UNTIL TIME OF ACCEPTANCE BY THE OWNER. TURFGRASS SOD SHALL BE HARVESTED, DELIVERED, AND INSTALLED/TRANSPORTED WITH A PERIOD OF 24 HOURS. TURFGRASS SOD SHALL BE RELATIVELY FREE OF THATCH, UP TO .5 INCH ALLOWABLE (UNCOMPRESSED). TURFGRASS SOD SHALL BE REASONABLY FREE (10 WEEDS/100 SQ. FT.) OF DISEASES, NEMATODES AND SOIL-BORNE INSECTS. ALL TURFGRASS SOD SHALL BE FREE OF GRASSY AND BROAD LEAF WEEDS. THE SOD SUPPLIER SHALL MAKE RECOMMENDATIONS TO THE CONTRACTOR REGARDING WATERING SCHEDULE. THE WATERING SCHEDULE SHOULD BEGIN IMMEDIATELY AFTER SOD IS INSTALLED.
10. MATERIALS - IRRIGATION: DRIP IRRIGATION TO BE INSTALLED SURROUNDING FOUNDATION. SEE PLUMBING DRAWINGS AND SPECIFICATIONS.
11. MATERIALS - IRRIGATION:
  - 11.1. BASE BID: TEMPORARY DRIP IRRIGATION (DARK BROWN IN COLOR) TO BE INSTALLED IN ALL PLANT BEDS SURROUNDING THE BUILDING.
  - 11.2. ALTERNATE BID: PERMANENT IN-GROUND IRRIGATION SYSTEM TO BE INSTALLED WITH COVERAGE AREA TO INCLUDE ALL PERIMETER PLANT BEDS, PARKING LOT ISLANDS AND TURFGRASS AREAS.

CONTRACTOR AND OWNER RESPONSIBILITY NOTES

1. GUARANTEE: THE CONTRACTOR SHALL GUARANTEE ALL PLANTS THROUGH ONE (1) YEAR AFTER ACCEPTANCE BY THE OWNER'S REPRESENTATIVE. PLANTS SHALL BE ALIVE AND IN HEALTHY AND FLOURISHING CONDITION AT THE END OF THE GUARANTEE PERIOD. THE CONTRACTOR SHALL REPLACE (AT NO COST TO OWNER) ANY PLANTS THAT ARE DEAD OR NOT IN A VIGOROUS THRIVING CONDITION. REPLACEMENT PLANTS SHALL BE OF THE SAME KIND AND SIZE AS ORIGINALLY SPECIFIED UNLESS OTHERWISE DIRECTED BY OWNER'S REPRESENTATIVE. RESTORE BEDS AS NECESSARY FOLLOWING PLANT REPLACEMENT, INCLUDING BUT NOT LIMITED TO BEDDING, EDGING, MULCH, ETC. REPLACE PLANTS DAMAGED AT TIME OF PLANTING. REPAIR AREAS DISTURBED IN ANY WAY DURING PLANT REPLACEMENT AT NO COST TO OWNER. CONTRACTOR SHALL PROVIDE A TWO (2)-YEAR STRAIGHTENING GUARANTEE FOR ALL TREES.
2. CONTRACTOR IS RESPONSIBLE FOR STAKING THE PLANT MATERIALS FOR REVIEW BY OWNER'S REPRESENTATIVE PRIOR TO DIGGING AND PLACEMENT AND SHALL COORDINATE ALL FINE GRADING AND RESTORATION WITH THE GRADING CONTRACTOR.
3. MAINTENANCE: (CONTRACTOR) FOR ALL PLANTINGS, SEEDED AREAS AND SODDED LAWN AREAS: THE CONTRACTOR SHALL MAINTAIN ALL PLANTINGS AND LAWN AREAS FOR A MINIMUM TIME PERIOD OF 60 DAYS, UNTIL FINAL ACCEPTANCE BY OWNER'S REPRESENTATIVE. THE CONTRACTOR IS RESPONSIBLE FOR ADEQUATELY WATERING PLANTS AND LAWN/TURFGRASS DURING THIS 60 DAY ESTABLISHMENT PERIOD. CONTRACTOR IS RESPONSIBLE FOR THE ESTABLISHMENT OF HEALTHY VIGOROUS PLANT MATERIALS AND LAWN/TURFGRASS GROWTH. CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ANY PRUNING OF PLANT MATERIALS AND SHAPING AND/OR REPLACEMENT OR SUPPLEMENT OF DEFICIENT SHREDDED HARDWOOD BARK MULCH DURING THIS PERIOD. LONG TERM PLANT MATERIALS AND LAWN/TURFGRASS MAINTENANCE AND ANY PROGRAM FOR SUCH IS THE RESPONSIBILITY OF THE OWNER. ALL PLANTINGS AND LAWN/TURFGRASS AREAS SHALL BE MAINTAINED IN A MANICURED CONDITION UNTIL THE TIME WHEN THE OWNER'S ACCEPTANCE IS GIVEN.
4. MAINTENANCE: (OWNER) THE OWNER IS RESPONSIBLE FOR THE CONTINUED MAINTENANCE, REPAIR AND REPLACEMENT OF ALL LANDSCAPING MATERIALS AND WEED BARRIER FABRIC AS NECESSARY FOLLOWING THE ONE (1) YEAR CONTRACTOR GUARANTEE PERIOD.



CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
KENOSHA | APPLETON | WAUSAU

MADISON REGIONAL OFFICE  
161 HORIZON DRIVE, SUITE 101  
VERONA, WISCONSIN 53593  
P. 608.848.5060

CLIENT:

SUMMIT CREDIT UNION

CLIENT ADDRESS:

4800 American Parkway  
MADISON, WI 53718

PROJECT:

SUMMIT CREDIT UNION - WAUKESHA BRANCH

PROJECT LOCATION:

2208 E MORELAND BOULEVARD  
WAUKESHA COUNTY

PLAN MODIFICATIONS:

#	Date:	Description:
1	04.09.18	CITY PLAN REVIEW
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		

Design/Drawn: ABK  
Approved: MAS

SHEET TITLE:


LANDSCAPE DETAILS, NOTES, AND SPECIFICATIONS

SHEET NUMBER:


L2.0

JSD PROJECT NO:

18-8469



Toll Free (800) 242-8511



**1**  
**EXTERIOR LIGHTING CALCULATIONS**  
 LC100 SCALE 1/16"=1'-0"

LUMINAIRE SCHEDULE		
SYMBOL	LABEL	DESCRIPTION
○	OB1.180	180 DEGREE DISTRIBUTION BOLLARD
○	OB1.360	360 DEGREE DISTRIBUTION BOLLARD
□	OP1.TFTM	LED SITE LIGHT ON 18 FT POLE WITH A 6 INCH TALL CONCRETE BASE
□	OP1.T3M	LED SITE LIGHT ON 18 FT POLE WITH A 6 INCH TALL CONCRETE BASE
—	OL1	LINEAR AIMABLE UP-LIGHT MOUNTED IN STRUCTURE OF CANOPY
○	OD1	EXTERIOR DOWNLIGHT

## LED bollards with 180° light distribution

**Post construction:** One piece extruded aluminum with internally welded die-cast aluminum base. Die casting is marine grade, copper free ( $\leq 0.3\%$  copper content) A360.0 aluminum alloy.

**Enclosure:** Heavy walled, die-cast aluminum cap. Clear 1/4" thick borosilicate glass with pure anodized aluminum reflector. Fully gasketed for weather tight operation using high temperature silicone gasket.

**Electrical:** 7.2W LED luminaire, 10 total system watts,  $-30^{\circ}\text{C}$  start temperature. Integral 120V through 277V electronic LED driver, 0-10V dimming. LED module(s) are available from factory for easy replacement. Standard LED color temperature is 3000K with a  $>80$  CRI. Available in 4000K ( $>80$  CRI); add suffix K4 to order. **Note:** LEDs supplied with luminaire. Due to the dynamic nature of LED technology, LED luminaire data on this sheet is subject to change at the discretion of BEGA-US. For the most current technical data, please refer to [www.bega-us.com](http://www.bega-us.com).


**Anchor base:** Heavy cast aluminum, slotted for precise alignment. Mounts to BEGA 79 824 anchorage kit. Bollard secures to base with one stainless steel set screw. The mounting system allows the luminaire to be adjusted independent of anchor bolt orientation.

**Finish:** All BEGA standard finishes are polyester powder coat with minimum 3 mil thickness. Available in four standard BEGA colors: Black (BLK); White (WHT); Bronze (BRZ); Silver (SLV). To specify, add appropriate suffix to catalog number. Custom colors supplied on special order.

CSA certified to U.S. and Canadian standards, suitable for wet locations. Protection class IP65

**Weight:** 19.0 lbs.

**Luminaire Lumens:** 411



LED bollards · 180°

	Lamp	A	B	Anchorage
<b>77 753</b>	7.2W LED	6 1/2	39 3/8	<b>79 817</b>

Type:  
 BEGA Product:  
 Project:  
 Voltage:  
 Color:  
 Options:  
 Modified:



1000 BEGA Way, Carpinteria, CA 93013 (805) 684-0533 FAX (805) 566-9474 [www.bega-us.com](http://www.bega-us.com)  
 ©copyright BEGA 2017 Updated 10/17

SUMMIT CREDIT UNION  
 MORELAND

TYPE: OB1\_180

## LED Bollards with rotationally symmetrical distribution

**Post construction:** One piece extruded aluminum, with a one piece aluminum top housing and base, internally welded into an assembly. Die castings are marine grade, copper free ( $\leq 0.3\%$  copper content) A360.0 aluminum alloy.

**Enclosure:** Heavy walled, die-cast aluminum cap. Clear  $\frac{3}{16}$ " thick borosilicate glass with pure anodized aluminum cone reflector. Fully gasketed using high temperature silicone rubber O-ring gaskets.

**Electrical:** 14.4W LED luminaire, 20 total system watts,  $-20^{\circ}\text{C}$  start temperature. Integral 120V through 277V electronic LED driver, 0-10V, TRIAC, and ELV dimmable. LED module(s) are available from factory for easy replacement.

Standard LED color temperature is 3000K with a  $>80$  CRI. Available in 4000K ( $>80$  CRI); add suffix K4 to order.

**Note:** Due to the dynamic nature of LED technology, LED luminaire data on this sheet is subject to change at the discretion of BEGA-US. For the most current technical data, please refer to [www.bega-us.com](http://www.bega-us.com).

**Anchor base:** Heavy cast aluminum, slotted for precise alignment. Mounts to BEGA 79817 anchorage kit (supplied).

**Finish:** All BEGA standard finishes are polyester powder coat with minimum 3 mil thickness. Available in four standard BEGA colors: Black (BLK); White (WHT); Bronze (BRZ); Silver (SLV). To specify, add appropriate suffix to catalog number. Custom colors supplied on special order.

UL listed for US and Canadian Standards, suitable for wet locations. Protection class IP65.

**Luminaire Lumens:** 746



	Lamp	A	B	Anchorage
<b>99 570</b>	14.4W LED	6 1/2	39 3/8	<b>79 817</b>

Type:  
 BEGA Product:  
 Project:  
 Voltage:  
 Color:  
 Options:  
 Modified:



1000 BEGA Way, Carpinteria, CA 93013 (805) 684-0533 FAX (805) 566-9474 [www.bega-us.com](http://www.bega-us.com)  
 ©copyright BEGA 2017 Updated 09/17

SUMMIT CREDIT UNION  
 MORELAND

TYPE: OB1\_360

**Juno**

# 2" IC 600 AND 1000 LUMENS LED ROUND ADJUSTABLE 2LEDTRIM G2 ADJ



Project: \_\_\_\_\_

Fixture Type: \_\_\_\_\_

Location: \_\_\_\_\_

Contact/Phone: \_\_\_\_\_

## PRODUCT DESCRIPTION

2 inch aperture recessed downlight is IC rated for insulated or non-insulated applications • Luminaire produces up to 1000 lumens and is available with optical distributions approximating that of 75W MR16 halogen lamps

- Low profile form factor allows luminaire to fit in 2 x 6 construction
- Designed to provide 50,000 hours of life • 5 year limited warranty on LED Components.

## ENVIRONMENTALLY FRIENDLY, ENERGY EFFICIENT

- No harmful ultraviolet or infrared wavelengths
- No lead or mercury, RoHS compliant
- Comparable light output up to a 75W MR16 halogen lamp

## PRODUCT SPECIFICATIONS

**LED Light Engine** Exceptional fixture to fixture color consistency within a 3-step MacAdam ellipse • 2700K, 3000K, 3500K, and 4000K color temperatures are available with 80 CRI or 90 CRI minimum.

**Modular Optics** Available with field interchangeable optics in 18° Spot, 24° Narrow Flood, or 40° Flood distributions • Gimbal provides up to 35° vertical aiming and 360° horizontal aiming.

**Aesthetic Trim** Trim features die cast beveled knife edge trim ring for clean ceiling interface available in white, black, satin nickel, or brushed bronze • Die cast baffles are available in white, black, satin nickel, or brushed bronze

**LED Driver** Choice of dedicated 120 volt (120) driver or universal voltage (MVOLT) driver that accommodates input voltages from 120-277 volts AC at 50/60Hz • Power factor > 0.9 • Dedicated 120 volt driver (120) is dimmable with the use of most incandescent, magnetic low voltage and electronic low voltage dimmers • Universal voltage driver (MVOLT) is dimmable with the use of most 0-10V protocol dimmers • For a list of compatible dimmers, see [JUNO2ING2-DIM](#).

**Life** Rated for 50,000 hours at 70% lumen maintenance.

**Labels** ENERGY STAR® Certified • 90CRI fixtures are certified to the high efficacy requirements of California T24 JA8-2016 • Meets energy code Air Leakage requirements per ASTM E283 • UL and cUL listed for damp locations.

**Junction Box** Includes (2) ½" knock-outs equipped with pryout slots • Push-in electrical connectors for field connections.

**Mounting** Remodel style plaster frame installs from below the ceiling and accommodates ceiling thicknesses from ½" to 1" • For thicker ceilings up to 1 ½", order 2JCTA150 • New Construction mounting frame, 2NCF, is also available with Patented (US Patent D552,969) Real Nail 3° telescoping bar hangers to position fixture and locate wiring prior to ceiling installation • Recommend a minimum of 5.5" cavity depth to install properly • Flexible supply is recommended and non-flexible supply requires top access.


Specifications subject to change without notice.



## Trim Finishes



## DIMENSIONS



## ENGINEERING DATA (600L)

	Dedicated 120V (120)		Universal Voltage (MVOLT)	
	Voltage	120	120	277
Input Power	7.5 (±5%)	7.2	7.5 (±5%)	
Input Current	.06	.06	.03	
Frequency	50/60Hz	50/60Hz		
Power Factor	>0.9	>0.9	>0.9	

## ENGINEERING DATA (1000L)

	Dedicated 120V (120)		Universal Voltage (MVOLT)	
	Voltage	120	120	277
Input Power	11.5 (±5%)	10.9	11.4 (±5%)	
Input Current	.10	.09	.04	
Frequency	50/60Hz	50/60Hz		
Power Factor	>0.9	>0.9	>0.9	

**AcuityBrands.**

1300 S. Wolf Road • Des Plaines, IL 60018 • Phone (847) 827-9880 • Fax (847) 827-2925 • Visit us at [www.acuitybrands.com/juno-recessed](http://www.acuitybrands.com/juno-recessed)  
Printed in U.S.A. ©2015 - 2017 Acuity Brands Lighting, Inc. Rev. Rev. 12/7/17

1 of 5

SUMMIT CREDIT UNION  
MORELAND

TYPE: OD1

# 2" IC 600 AND 1000 LUMENS LED ROUND ADJUSTABLE 2LEDTRIM G2 ADJ


**ORDERING INFORMATION** DRIVER AND TRIM EACH ORDERED SEPARATELY.

**DRIVER:**

Example: 2LEDDRIVER G2 06LM 120 FRPC

Series	Generation	Lumens	Voltage	Driver
2LEDDRIVER Juno Recessed 2" Driver	G2 Generation 2	06LM 600 Nominal Lumens 10LM 1000 Nominal Lumens	120 120V MVOLT Multi-Volt (120-277V)	FRPC Forward/Reverse Phase Cut ZT 0-10V Dimming

Note: 120V must be ordered with FRPC.  
MVOLT must be ordered with ZT




MOUNTING FRAME/DRIVER ASSEMBLY

Note: Driver assembly only intended for use with Gen2 LED trim modules. Not backward compatible with previous generation.

**TRIM:**

Example: 2LEDTRIM G2 ADJ 27K 80CRI FL BL



Series	Generation	Trim Designation	Color Temperature	CRI	Distribution	Trim Finish
2LEDTRIM Juno Recessed 2" LED Trim	G2 Generation 2	ADJ Round Adjustable	27K 2700K 30K 3000K 35K 3500K 40K 4000K	80CRI 80+ CRI 90CRI 90+ CRI	FL Flood NFL Narrow Flood SP Spot	BL Black BZ Bronze SN Satin Nickel WH White



TRIM/LED ASSEMBLY

**ACCESSORIES**

Catalog No.	Description
2NCFM	New Construction Mounting Frame with Real Nail® 3 bar hangers
2JCTA150	Thick Ceiling adapter for 1" - 1½" thick ceiling
LEDOPTIC2 SP	18° Spot Optic
LEDOPTIC2 NFL	24° Narrow Flood Optic
LEDOPTIC2 FL	40° Flood Optic



DATE	PROJECT	FIRM	TYPE
------	---------	------	------

THE L50 INCLUDES PATENTED OPTICAL DESIGN THAT DELIVERS THE WIDEST RANGE OF BEAM ANGLE OPTIONS FOR PRECISE COVE, WALL GRAZING, WALL WASHING OR LINE OF LIGHT APPLICATIONS. EXCLUSIVE FLIP TO FLAT™ HINGE DESIGN PROVIDES FLEXIBILITY WHEN MANAGING SMALL COVE DETAILS. TRÖV OFFERS SMOOTH, FLICKER FREE DIMMING DOWN TO 0%.

**FEATURES :**

- DIM TO 0%, ELV REVERSE PHASE
- 24 BEAM ANGLES
- MULTI-VOLT
- FLIP TO FLAT™
- 6 CCT OPTIONS
- 80+ AND 90+ CRI OPTIONS
- IP54 INTERIOR AND IP66 EXTERIOR OPTIONS



MODEL/ SIZE	INTERIOR/ EXTERIOR	LENGTH	POWER	CCT	CRI	VOLTAGE	OPTICS
L50	I E	12" 48"	02 04 06 08 10 12	WHITE CCT 22 27 30 35 40 50	MONO COLOR GR**** BL AM RD***	80 90* Blank For Color	MULT (120-277V)  GRAZING 9 x 9 9 x 17 9 x 29 9 x 59 15 x 15 15 x 23 15 x 35 15 x 65 COVE 120" Asym LINE OF LIGHT LOL WASHING 25 x 25 25 x 33 25 x 45 25 x 75 39 x 9 55 x 25 40 x 40 40 x 48 40 x 60 40 x 90 45 x 15 70 x 40 70 x 70

**EXAMPLE:** L50-I-48-10-27-90-MULT-15x65 \*90 CRI not available in 2200K or 5000K \*\*120 is only available with Exterior option. See L35 spec sheet for interior cove options. \*\*\*Red is not available in 12W or 10W. \*\*\*\*Green is not available in 12W.

PERFORMANCE	WATTS	OPTIC	LUMEN OUTPUT	EFFICACY
	2W	ASYM	110 lm/LF ( 361 lm/m )	55 lm/W
	4W	ASYM	302 lm/LF ( 1037 lm/m )	76 lm/W
	6W	ASYM	482 lm/LF ( 1614 lm/m )	80 lm/W
	8W	ASYM	675 lm/LF ( 2224 lm/m )	84 lm/W
	10W	ASYM	785 lm/LF ( 2644 lm/m )	79 lm/W
	12W	ASYM	923 lm/LF ( 2752 lm/m )	77 lm/W

ALL LUMEN DATA IS FROM 4000K 80CRI FIXTURES. PLEASE SEE PHOTOMETRY SPEC SHEET FOR ADDITIONAL LUMEN DATA.

<b>COLOR RENDERING INDEX</b>	80+, 90+				
<b>COLOR CONSISTENCY</b>	2-STEP MACADAM ELLIPSE				
<b>LUMEN DEPRECIATION / RATED LIFE</b>	WATTS	L70 @ 25C	L70 @ 50C	L90 @ 25C	L90 @ 50C
	2W-12W	>150,000	>70,000	>50,000	>25,000

\* CALCULATIONS FOR LED FIXTURES ARE BASED ON MEASUREMENTS THAT COMPLY WITH IES LM-80 TESTING PROCEDURES AND IES TM-21 CALCULATOR

<b>ELECTRICAL</b>	<b>POWER CONSUMPTION</b>	2W*/LF (6.6W/M); 4W/LF (13.2W/M); 6W/LF (19.8W/M); 8W/LF (26.4W/M); 10W/LF (33W/M); 12W/FL (39.6W/M) * 3W/LF (9.9W/M) at 220V -277V																																																																	
	<b>MAX FIXTURE RUN LENGTH</b>	<table border="1"> <thead> <tr> <th></th> <th colspan="2">2W/LF</th> <th colspan="2">4W/LF</th> <th colspan="2">6W/LF</th> <th colspan="2">8W/LF</th> <th colspan="2">10W/LF</th> <th colspan="2">12W/LF</th> </tr> <tr> <th>Volts</th> <th>Max Run all 1'</th> <th>Max Run all 4'</th> <th>Max Run all 1'</th> <th>Max Run all 4'</th> <th>Max Run all 1'</th> <th>Max Run all 4'</th> <th>Max Run all 1'</th> <th>Max Run all 4'</th> <th>Max Run all 1'</th> <th>Max Run all 4'</th> <th>Max Run all 1'</th> <th>Max Run all 4'</th> </tr> </thead> <tbody> <tr> <td>120</td> <td>214</td> <td>214</td> <td>186</td> <td>186</td> <td>152</td> <td>152</td> <td>114</td> <td>114</td> <td>91</td> <td>91</td> <td>76</td> <td>76</td> </tr> <tr> <td>220</td> <td>374</td> <td>392</td> <td>340</td> <td>340</td> <td>277</td> <td>277</td> <td>209</td> <td>209</td> <td>95</td> <td>167</td> <td>95</td> <td>139</td> </tr> <tr> <td>277</td> <td>374</td> <td>494</td> <td>374</td> <td>428</td> <td>349</td> <td>349</td> <td>263</td> <td>263</td> <td>95</td> <td>190</td> <td>95</td> <td>175</td> </tr> </tbody> </table>		2W/LF		4W/LF		6W/LF		8W/LF		10W/LF		12W/LF		Volts	Max Run all 1'	Max Run all 4'	Max Run all 1'	Max Run all 4'	Max Run all 1'	Max Run all 4'	Max Run all 1'	Max Run all 4'	Max Run all 1'	Max Run all 4'	Max Run all 1'	Max Run all 4'	120	214	214	186	186	152	152	114	114	91	91	76	76	220	374	392	340	340	277	277	209	209	95	167	95	139	277	374	494	374	428	349	349	263	263	95	190	95	175
	2W/LF		4W/LF		6W/LF		8W/LF		10W/LF		12W/LF																																																								
Volts	Max Run all 1'	Max Run all 4'	Max Run all 1'	Max Run all 4'	Max Run all 1'	Max Run all 4'	Max Run all 1'	Max Run all 4'	Max Run all 1'	Max Run all 4'	Max Run all 1'	Max Run all 4'																																																							
120	214	214	186	186	152	152	114	114	91	91	76	76																																																							
220	374	392	340	340	277	277	209	209	95	167	95	139																																																							
277	374	494	374	428	349	349	263	263	95	190	95	175																																																							
	<b>POWER FACTOR</b>	4W, 6W, 8W, 10W, 12W >0.9, 2W<0.9																																																																	
	<b>OPERATING VOLTAGE DRIVER</b>	MULTIVOLT: 110-277VAC, 50/60 Hz																																																																	
	<b>STARTUP TEMPERATURE</b>	INTEGRAL TO FIXTURE; DE-RATED POWER AND SYNCHRONOUS START-UP AT FULL BRIGHTNESS																																																																	
	<b>OPERATING TEMPERATURE</b>	-40°F TO 122°F (-40°C TO 50°C)																																																																	
	<b>STORAGE TEMPERATURE</b>	-40°F TO 176°F (-40°C TO 80°C)																																																																	

ECOSENSE LIGHTING INC.  
837 NORTH SPRING STREET  
SUITE 103  
LOS ANGELES, CA 90012

P • 310.496.6255  
F • 310.496.6256  
T • 855.632.6736  
855.6.ECOSEN


SPECIFICATIONS SUBJECT TO CHANGE WITHOUT NOTICE. VISIT [ECOSENSELIGHTING.COM](http://ECOSENSELIGHTING.COM) FOR THE MOST CURRENT SPECIFICATIONS.  
© 2017 ECOSENSE LIGHTING INC. ALL RIGHTS RESERVED. ECOSENSE, THE ECOSENSE LOGO, RISE, TRÖV, SLIM COVE AND ECOSPEC ARE REGISTERED TRADEMARKS OF ECOSENSE LIGHTING INC.  
FREEDOM TO CREATE™

[ECOSENSELIGHTING.COM](http://ECOSENSELIGHTING.COM)


1/3

20171120

DATE	PROJECT	FIRM	TYPE
------	---------	------	------



Fine Adjustable L-Bracket:



ECOSENSE LIGHTING INC.  
837 NORTH SPRING STREET  
SUITE 103  
LOS ANGELES, CA 90012

P • 310.496.6255  
F • 310.496.6256  
T • 855.632.6736  
855.6.ECOSEN

SPECIFICATIONS SUBJECT TO CHANGE WITHOUT NOTICE. VISIT  
ECOSENSELIGHTING.COM FOR THE MOST CURRENT SPECIFICATIONS.  
© 2017 ECOSENSE LIGHTING INC. ALL RIGHTS RESERVED. ECOSENSE,  
THE ECOSENSE LOGO, RISE, TRÖV, SLIM COVE AND ECOSPEC ARE  
REGISTERED TRADEMARKS OF ECOSENSE LIGHTING INC.  
FREEDOM TO CREATE™

ECOSENSELIGHTING.COM

3/3

20171120





# D-Series Size 0 LED Area Luminaire



Catalog Number
Notes
Type

Hit the Tab key or mouse over the page to see all interactive elements.

## A+ Capable Luminaire

This item is an A+ capable luminaire, which has been designed and tested to provide consistent color appearance and system-level interoperability.





- All configurations of this luminaire meet the Acuity Brands' specification for chromatic consistency
- This luminaire is A+ Certified when ordered with DTL® controls marked by a **shaded background**. DTL DLL equipped luminaires meet the A+ specification for luminaire to photocontrol interoperability<sup>1</sup>
- This luminaire is part of an A+ Certified solution for ROAM® or XPoint™ Wireless control networks, providing out-of-the-box control compatibility with simple commissioning, when ordered with drivers and control options marked by a **shaded background**<sup>1</sup>

To learn more about A+, visit [www.acuitybrands.com/aplus](http://www.acuitybrands.com/aplus).

- See ordering tree for details.
- A+ Certified Solutions for ROAM require the order of one ROAM node per luminaire. Sold Separately: [Link to Roam](#); [Link to DTL DLL](#)

## Specifications

EPA:	0.95 ft <sup>2</sup> (.09 m <sup>2</sup> )
Length:	26" (66.0 cm)
Width:	13" (33.0 cm)
Height:	7" (17.8 cm)
Weight (max):	16 lbs (7.25 kg)



## Ordering Information

**EXAMPLE: DSX0 LED P6 40K T3M MVOLT SPA DDBXD**

Series	LEDs	Color temperature	Distribution	Voltage	Mounting	
<b>DSX0 LED</b>	<b>Forward optics</b> P1 P4 P7 P2 <b>P5</b> P3 P6 <b>Rotated optics</b> P10 <sup>1</sup> P12 <sup>1</sup> P11 <sup>1</sup> P13 <sup>1</sup>	<b>30K 3000 K</b> 40K 4000 K 50K 5000 K AMBPC Amber phosphor converted <sup>2</sup>	T1S Type I short T2S Type II short T2M Type II medium T3S Type III short <b>T3M Type III medium</b> T4M Type IV medium <b>TFTM Forward throw medium</b> T5VS Type V very short	T5S Type V short T5M Type V medium T5W Type V wide BLC Backlight control <sup>2,3</sup> LCCO Left corner cutoff <sup>2,3</sup> RCCO Right corner cutoff <sup>2,3</sup>	MVOLT <sup>4,5</sup> <b>120<sup>6</sup></b> 208 <sup>5,6</sup> 240 <sup>5,6</sup> 277 <sup>6</sup> 347 <sup>5,6,7</sup> 480 <sup>5,6,7</sup>	<b>Shipped included</b> <b>SPA</b> Square pole mounting RPA Round pole mounting WBA Wall bracket SPUMBA Square pole universal mounting adaptor <sup>8</sup> RPUMBA Round pole universal mounting adaptor <sup>8</sup> <b>Shipped separately</b> KMA8 DDBXD U Mast arm mounting bracket adaptor (specify finish) <sup>9</sup>

Control options	Other options	Finish (required)
<b>Shipped installed</b> NLTAIR2 nLight AIR generation 2 enabled <sup>10</sup> PER NEMA twist-lock receptacle only (control ordered separate) <sup>11</sup> PER5 Five-wire receptacle only (control ordered separate) <sup>11,12</sup> PER7 Seven-wire receptacle only (control ordered separate) <sup>11,12</sup> DMG 0-10V dimming extend out back of housing for external control (control ordered separate) PIR Bi-level, motion/ambient sensor, 8-15' mounting height, ambient sensor enabled at 5fc <sup>5,13,14</sup> PIRH Bi-level, motion/ambient sensor, 15-30' mounting height, ambient sensor enabled at 5fc <sup>5,13,14</sup> PIRHN Network, Bi-Level motion/ambient sensor <sup>15</sup> PIR1FC3V Bi-level, motion/ambient sensor, 8-15' mounting height, ambient sensor enabled at 1fc <sup>5,13,14</sup>	PIRH1FC3V Bi-level, motion/ambient sensor, 15-30' mounting height, ambient sensor enabled at 1fc <sup>5,13,14</sup> BL30 Bi-level switched dimming, 30% <sup>5,16,17</sup> BL50 Bi-level switched dimming, 50% <sup>5,16,17</sup> PNMTDD3 Part night, dim till dawn <sup>5,18</sup> PNMTSD3 Part night, dim 5 hrs <sup>5,18</sup> PNMT6D3 Part night, dim 6 hrs <sup>5,18</sup> PNMT7D3 Part night, dim 7 hrs <sup>5,18</sup> FAO Field adjustable output <sup>19</sup>	<b>Shipped installed</b> HS House-side shield <sup>20</sup> SF Single fuse (120, 277, 347V) <sup>6</sup> DF Double fuse (208, 240, 480V) <sup>6</sup> L90 Left rotated optics <sup>1</sup> R90 Right rotated optics <sup>1</sup> DDL Diffused drop lens <sup>20</sup> <b>Shipped separately</b> BS Bird spikes <sup>21</sup> EGS External glare shield <sup>21</sup>
		DDBXD Dark bronze DBLXD Black <b>DNAXD Natural aluminum</b> DWHXD White DDBTXD Textured dark bronze DBLTXD Textured black DNATXD Textured natural aluminum DWHGXD Textured white



One Lithonia Way • Conyers, Georgia 30012 • Phone: 800.279.8041 • [www.lithonia.com](http://www.lithonia.com)  
© 2011-2018 Acuity Brands Lighting, Inc. All rights reserved.

DSX0-LED  
Rev. 03/21/18  
Page 1 of 7

# Performance Data

## Lumen Output


Lumen values are from photometric tests performed in accordance with IESNA LM-79-08. Data is considered to be representative of the configurations shown, within the tolerances allowed by Lighting Facts. Contact factory for performance data on any configurations not shown here.

Forward Optics																															
LED Count	Drive Current	Power Package	System Watts	Dist. Type	30K (3000 K, 70 CRI)					40K (4000 K, 70 CRI)					50K (5000 K, 70 CRI)					AMBPC (Amber Phosphor Converted)											
					Lumens	B	U	G	LPW	Lumens	B	U	G	LPW	Lumens	B	U	G	LPW	Lumens	B	U	G	LPW							
40	700	P5	89W	T1S	10,831	2	0	2	122	11,668	2	0	2	131	11,816	2	0	2	133												
				T2S	10,820	2	0	2	122	11,656	2	0	2	131	11,803	2	0	2	133												
				T2M	10,876	2	0	2	122	11,716	2	0	2	132	11,864	2	0	2	133												
				T3S	10,532	2	0	2	118	11,346	2	0	2	127	11,490	2	0	2	129												
				T3M	10,849	2	0	2	122	11,687	2	0	2	131	11,835	2	0	2	133												
				T4M	10,613	2	0	3	119	11,434	2	0	3	128	11,578	2	0	3	130												
				TFTM	10,842	2	0	2	122	11,680	2	0	2	131	11,828	2	0	2	133												
				TSVS	11,276	3	0	1	127	12,148	3	0	1	136	12,302	3	0	1	138												
				TSS	11,286	3	0	1	127	12,158	3	0	1	137	12,312	3	0	1	138												
				TSM	11,257	4	0	2	126	12,127	4	0	2	136	12,280	4	0	2	138												
				TSW	11,344	4	0	3	127	12,221	4	0	3	137	12,375	4	0	3	139												
				BLC	8,890	1	0	2	100	9,576	1	0	2	108	9,698	1	0	2	109												
				LCCO	6,615	1	0	3	74	7,126	1	0	3	80	7,216	1	0	3	81												
				RCCO	6,615	1	0	3	74	7,126	1	0	3	80	7,216	1	0	3	81												
				40	1050	P6	134W	T1S	14,805	3	0	3	110	15,949	3	0	3	119	16,151	3	0	3	121	6,206	2	0	2	68			
								T2S	14,789	3	0	3	110	15,932	3	0	3	119	16,134	3	0	3	120	6,322	2	0	2	69			
T2M	14,865	3	0					3	111	16,014	3	0	3	120	16,217	3	0	3	121	6,201	2	0	2	68							
T3S	14,396	3	0					3	107	15,509	3	0	3	116	15,705	3	0	3	117	6,247	1	0	2	69							
T3M	14,829	2	0					3	111	15,975	3	0	3	119	16,177	3	0	3	121	6,308	2	0	2	69							
T4M	14,507	2	0					3	108	15,628	3	0	3	117	15,826	3	0	3	118	6,275	1	0	2	69							
TFTM	14,820	2	0					3	111	15,965	3	0	3	119	16,167	3	0	3	121	6,203	1	0	2	68							
TSVS	15,413	4	0					1	115	16,604	4	0	1	124	16,815	4	0	1	125	6,671	2	0	0	73							
TSS	15,426	3	0					1	115	16,618	4	0	1	124	16,828	4	0	1	126	6,569	2	0	0	72							
TSM	15,387	4	0					2	115	16,576	4	0	2	124	16,786	4	0	2	125	6,491	3	0	1	71							
TSW	15,506	4	0					3	116	16,704	4	0	3	125	16,915	4	0	3	126	6,504	3	0	2	71							
BLC	12,151	1	0					2	91	13,090	1	0	2	98	13,255	1	0	2	99												
LCCO	9,041	1	0					3	67	9,740	1	0	3	73	9,863	1	0	3	74												
RCCO	9,041	1	0					3	67	9,740	1	0	3	73	9,863	1	0	3	74												
40	1300	P7	166W					T1S	17,023	3	0	3	103	18,338	3	0	3	110	18,570	3	0	3	112								
								T2S	17,005	3	0	3	102	18,319	3	0	3	110	18,551	3	0	3	112								
				T2M	17,092	3	0	3	103	18,413	3	0	3	111	18,646	3	0	3	112												
				T3S	16,553	3	0	3	100	17,832	3	0	3	107	18,058	3	0	3	109												
				T3M	17,051	3	0	3	103	18,369	3	0	3	111	18,601	3	0	3	112												
				T4M	16,681	3	0	3	100	17,969	3	0	3	108	18,197	3	0	3	110												
				TFTM	17,040	3	0	3	103	18,357	3	0	4	111	18,590	3	0	4	112												
				TSVS	17,723	4	0	1	107	19,092	4	0	1	115	19,334	4	0	1	116												
				TSS	17,737	4	0	2	107	19,108	4	0	2	115	19,349	4	0	2	117												
				TSM	17,692	4	0	2	107	19,059	4	0	2	115	19,301	4	0	2	116												
				TSW	17,829	5	0	3	107	19,207	5	0	3	116	19,450	5	0	3	117												
				BLC	13,971	2	0	2	84	15,051	2	0	2	91	15,241	2	0	2	92												
				LCCO	10,396	1	0	3	63	11,199	1	0	3	67	11,341	1	0	3	68												
									10,396	1	0	3	63	11,199	1	0	3	67	11,341	1	0	3	68								




One Lithonia Way • Conyers, Georgia 30012 • Phone: 800.279.8041 • [www.lithonia.com](http://www.lithonia.com)  
 © 2011-2018 Acuity Brands Lighting, Inc. All rights reserved.


DSX0-LED  
 Rev. 03/21/18  
 Page 5 of 7



INTERIOR FLOOR PLAN AVAILABLE ON REQUEST.  
NOT INCLUDED IN SUBMITTAL DUE TO SECURITY CONCERNS.

N  
1  
201  
**FIRST FLOOR PLAN**  
SCALE: 1/8" = 1'-0"  
0 4 8 16





INTERNALLY ILLUMINATED SIGNAGE

FABRIC SUNSHADE


ALUMINUM STOREFRONT SYSTEM. CLEAR ANODIZED ALUMINUM FINISH.

SILVER METALLIC RIBBED METAL PANEL. MATCHES FINISH OF WINDOW FRAMES.

SILVER METALLIC SILL FLASHING

ENDICOTT MANGANESE IRONSPOT BRICK

1  
401  
**NORTHEAST ELEVATION**  
SCALE: 1/8" = 1'-0"  
0 4 8 16



22' - 2"

23' - 11 1/2"


2  
401  
**SOUTHWEST ELEVATION**  
SCALE: 1/8" = 1'-0"  
0 4 8 16






1  
402 **NORTHWEST ELEVATION**  
SCALE: 1/8" = 1'-0"  
0 4 8 16


- SILVER METALLIC RIBBED METAL PANEL. MATCHES FINISH OF WINDOW FRAMES.
- SILVER METALLIC SILL FLASHING
- ENDICOTT MANGANESE IRONSPOT BRICK



2  
402 **SOUTHEAST ELEVATION**  
SCALE: 1/8" = 1'-0"  
0 4 8 16


- ALUMINUM STOREFRONT SYSTEM. CLEAR ANODIZED ALUMINUM FINISH.
- FABRIC SUNSHADE






**1** **NORTHEAST ELEVATION SIGNAGE**

403B SCALE: 1/8" = 1'-0"




**2** **SOUTHWEST ELEVATION SIGNAGE**

403B SCALE: 1/8" = 1'-0"




**4** **HERITAGE LN MONUMENT EAST ELEVATION**

403B SCALE: 1/4" = 1'-0"




**5** **MONUMENT SIGN LOCATIONS**

403B SCALE: NTS




**3** **HERITAGE LN MONUMENT WEST ELEVATION**

403B SCALE: 1/4" = 1'-0"




**6** **MORELAND MONUMENT WEST**

403B SCALE: 1/8" = 1'-0"



**7** **MORELAND MONUMENT EAST**

403B SCALE: 1/8" = 1'-0"



# Summit Credit Union – Waukesha Branch Waukesha, Wisconsin Stormwater Management and Erosion Control Plan

[www.JSDinc.com](http://www.JSDinc.com)



Planning & Development  
Site/Civil Engineering  
Transportation Engineering  
Structural Engineering  
Water Resources  
Landscape Architecture  
Surveying & Mapping  
Construction Management

Prepared for:  
**Summit Credit Union**  
4800 American Parkway  
Madison, WI 53718

JSD Project No.: 18-8469

April 6, 2018

Prepared by: Corey Huhta, P.E., C.F.M

**JSD** Professional Services, Inc.  
• Engineers • Surveyors • Planners

# TABLE OF CONTENTS

1.0 INTRODUCTION .....	1
2.0 EXISTING CONDITIONS.....	1
3.0 DESIGN CRITERIA.....	1
3.1 Municipal Code of the City of Waukesha, Wisconsin .....	1
3.3 Waukesha County Code of Ordinances.....	1
3.4 Wisconsin Administrative Code .....	1
4.0 ANALYSIS.....	1
5.0 DESIGN.....	2
5.1 Peak Discharge .....	3
5.2 Sediment Control .....	3
6.0 EROSION CONTROL .....	3
7.0 CONCLUSION.....	4

## APPENDICES

APPENDIX 1 – ALTA/NSPS LAND TITLE SURVEY

APPENDIX 2 – SOILS INFORMATION

APPENDIX 3 – PRELIMINARY PLANS

APPENDIX 4 – PRE-DEVELOPMENT HYDROLOGIC CALCULATIONS

APPENDIX 5 – POST-DEVELOPMENT HYDROLOGIC CALCULATIONS

APPENDIX 6 – SEDIMENT CALCULATIONS

APPENDIX 7 – STORM SEWER SIZING CALCULATIONS

APPENDIX 8 – USLE INFORMATION

APPENDIX 9 – MAINTAINANCE AGREEMENT

### Future questions and comments can be directed to:

Corey Huhta, P.E., C.F.M.  
Project Engineer

[corey.huhta@jsdinc.com](mailto:corey.huhta@jsdinc.com)  
Phone: 608.848.5060  
Fax: 608.848.2255

**JSD Professional Services, Inc.**  
• Engineers • Surveyors • Planners  
*Madison Regional Office*

161 Horizon Drive, Suite 101  
Verona, WI 53593  
[www.jsdinc.com](http://www.jsdinc.com)



## 1.0 INTRODUCTION

This technical report shall serve as the stormwater management design report for the Summit Credit Union project in the City of Waukesha, Waukesha County, Wisconsin.

The proposed project is a 1.13-acre project located on Lot of Certified Survey Map (CSM) 10663. The site is a redevelopment of the existing Sonic Drive-in restaurant between East Moreland Road (USH 18) and Heritage Lane. The project scope includes the demolition of the existing building, drive-in, parking canopies, and associated parking lots. The project consists of a 3,900 square foot building, 20 parking stalls, reconnection of access drives, and an underground water quality chamber. The stormwater facilities are reconnected to the storm sewer pipe connection in Heritage Lane. The proposed construction start date is anticipated for Spring 2019 with project completion by Fall 2019.

## 2.0 EXISTING CONDITIONS

The existing impervious area of the site is 0.752 acres consisting of asphalt parking, driveways, sidewalk, and building footprint. The proposed impervious of the site is 0.706 acres consisting of the same. There is a decrease of 0.044 acres of impervious area with an overall site impervious ratio of 62.4%. The existing site drains to an existing private stormwater system that connects to public storm sewer within Heritage Lane to the north. The existing site generally slopes to the north with a relief of 11 feet across the site. Refer to **Appendix 1** for the ALTA/NSPS Land Title Survey for the project.

A geotechnical report is being prepared for the site and will be provided during permitting. The NRCS web soil survey report was consulted for hydrologic soil groups. The NRCS web soil survey report is located in **Appendix 2**.

Stormwater runoff from the existing site consists of a single watershed. An existing watershed map can be found in **Appendix 4**.

## 3.0 DESIGN CRITERIA

### *3.1 Municipal Code of the City of Waukesha, Wisconsin*

Chapter 32 – Stormwater Management and Erosion Control

### *3.3 Waukesha County Code of Ordinances*

Chapter 14, Article VIII – Stormwater Management and Erosion Control Ordinance

### *3.4 Wisconsin Administrative Code*

WDNR – Technical Standards (NR 151 and NR 216)

The site will need to meet the criteria for a redevelopment site. Therefore, the requirements for this site include:

- Maintain pre-development peak discharges for the 1-, 5-, and 100-year, 24-hour storm events.
- Reduce the total suspended solids by 40% during the 1-year, 24-hour storm event assuming no re-suspension.

## 4.0 ANALYSIS

The stormwater management and erosion control plan have been written and analyzed for the development. Construction will include both on-site stormwater management and erosion control.

HydroCAD® stormwater modeling system (Version 10.00-20) has been used to analyze stormwater characteristics for the development. HydroCAD uses the accepted TR-55 – Urban Hydrology for Small Watersheds methodology for determining peak discharge runoff rates. The NOAA Atlas 14 rainfall depths for Waukesha County and the MSE 3 rainfall distribution were used in the hydrologic model. Due to the urbanization of the site, the minimum time of concentration of 6 minutes has been used per TR-55 standard methodology.

Curve numbers for the post-development ground cover were selected using the standard values specified TR-55. The maximum pre-development curve numbers were set per the WDNR Technical Standard NR 151. The curve number used for grassland was used in post-development conditions for pervious ground cover.

See **Table 1** below for the curve numbers that used for hydrologic modeling.

Runoff Curve Number	Hydrologic Soil Group			
	A	B	C	D
Woodland	30	55	70	77
Grassland	39	61	71	78
Cropland	55	69	78	83
Impervious	98	98	98	98
Water Bodies	100	100	100	100

Refer to **Appendix 4 and 5** for further information on pre-development and post-development hydrologic modeling for the development.

Sediment control used separate WinSLAMM Version 10.3 to account for total suspended solids (TSS) removal for the site. Refer to **Appendix 7** for further information on sediment control calculations.

The storm sewer peak flow rates were calculated using the Rational Method to determine peak flow rates for the 10-year storm event. The storm sewer was analyzed per the Wisconsin Department of Natural Resources Facility Design Manual (FDM) for a closed conduit system. Refer to **Appendix 9** for further information on the storm sewer sizing.

## 5.0 DESIGN

The underground water quality chamber proposed will provide total suspended solids reduction and peak discharge control for the project. Parking lot runoff will be collected within private storm sewer, treated within the underground water quality chamber, and ultimately discharged to the existing storm sewer within Heritage Lane. The roof runoff will be collected through roof drain connections and route to the private storm sewer system. A small portion of the access driveways and pervious area totaling 0.30 acres will match existing drainage patterns and will leave the site untreated and drain to Heritage Road public storm sewer.

The private storm sewer system consist of 5 curb inlets which are connected to an underground water quality chamber. The underground chamber will have a three foot sump below the outlet which acts as a sedimentation basin and provides settlement for suspended solids. The water quality chamber ultimately connects to the public storm sewer in Heritage Lane. The water quality chamber will settle out up to 20 micron particle. As designed, the stormwater management facility provides approximately 40.5% TSS reduction for the site.

Due to existing drainage patterns, approximately 0.13 acres of off-site area surface drains onto the project. This runoff will be collected into the private storm sewer and routed through the chamber. However, this off-site drainage was not considered in the TSS calculations as it is an off-site area.

A proposed watershed map can be referenced in **Appendix 5**. Preliminary construction plans of improvements can be found in **Appendix 3**.

### 5.1 Peak Discharge

#### Municipal Code of the City of Waukesha, WI Sec. 13.10 (d)(1). Total Sediment Control

*A. Minimum requirement. To minimize downstream bank erosion and the failure of downstream conveyance systems, the calculated post-development peak storm water discharge rate shall not exceed the calculated pre-development discharge rates for the 2-year, 10-year, and 100-year, 24-hour design storms.*

The proposed redevelopment of the site maintains existing drainage patterns and removes existing impervious surfaces on-site. This reduction reduces the uncontrolled peak discharges for the 2-, 10-, and 100-year, 24-hour design storms. The water quality chamber provides additional peak discharge reduction as runoff is routed through the system.

TABLE 2: PRE-SETTLEMENT VERSUS POST-DEVELOPMENT PEAK RUNOFF RATES

	2-year	10-year	100-year
Rainfall for each 24-hour storm event (inches)	4.17	6.47	11.35
Pre-development peak discharge rate (cfs)	4.17	6.47	11.35
Post-Development peak discharge rate without controls (cfs)	4.04	6.34	11.23
Post-Development peak discharge rate with detention (cfs)	3.30	5.10	10.74
Difference: Post-Development peak discharge rates with detention vs. Pre-Development peak discharge Rate (cfs)	-0.87	-1.37	-0.61

**Table 2** above shows the overall development pre-development, the uncontrolled post-development, and post-development peak runoff rates comparison.

### 5.2 Sediment Control

#### Municipal Code of the City of Waukesha, WI Sec. 13.10 (d)(2). Total Sediment Control

*By design, each storm water management plan shall meet the following post-development total suspended solids reduction targets, based on average annual rainfalls, as compared to no runoff management controls:*

- (i.) *For new land development, 80% reduction in total suspended solids load;*
- (ii.) *For redevelopment, 40% reduction of total suspended solids load;*
- (iii.) *For in-fill development that occurs prior to October 1, 2012, 40 % reduction total suspended solids load.*
- (iv.) *For in-fill development that occurs after October 1, 2012, 80% reduction of total suspended solids load.*

The underground water quality chamber has been designed to provide sediment control for the site. Due to existing drainage patterns, approximately 0.30 acres of drainage area will bypass treatment. The overall development yields approximately 470 pounds of particulate solids. The underground water quality chamber removes approximately 190 pounds of particulate solids for a 40.5% total suspended solids reduction. The development was modeled using WinSLAMM Version 10.3.4. See **Appendix 6** for the sediment control modeling inputs and outputs.

## 6.0 EROSION CONTROL

Erosion control measures onsite will conform to the Wisconsin Department of Natural Resources Technical Standards and City of Waukesha requirements. These measures include, but are not

limited to: construction entrances, silt fencing, check dams, grading, seeding, mulching, and erosion matting. Construction sequencing shall be as follows:

1. Install silt fence in the appropriate locations and stone tracking pads on the entrances to be used by the construction vehicles to access the site.
2. Remove existing pavement and structures.
3. Install storm sewer system.
4. Excavate building foundations.
5. Complete all other grading.
6. Install storm sewer and inlet protection measures.
7. Install aggregate base course and paving in parking areas.
8. Stabilize newly graded soils.
9. Complete exterior building work and downspouts
10. Remove temporary erosion control practices.

For more detailed requirements regarding erosion control, refer to the proposed construction plans in **Appendix 3** and Universal Soil Loss Equation (USLE) worksheet in **Appendix 9**.

## 7.0 CONCLUSION

Stormwater management features for Summit Credit Union – Waukesha Branch have been designed in accordance with applicable standards per Chapter 32 of the Municipal Code of the City of Waukesha, Chapter 14 of the Waukesha County Code of Ordinances, and WDNR standards NR151 and NR216. The development features an underground water quality chamber and public storm sewer. These facilities will treat for sediment, oil and grease, runoff rate, infiltration, and outlet controls. Erosion control practices will limit soil loss to 7.5 tons per acre annually, and regulate soil transportation within development boundaries.

# **APPENDIX 1**

## **ALTA/NSPS LAND TITLE SURVEY**

# ALTA/NSPS LAND TITLE SURVEY

LOT 1, CERTIFIED SURVEY MAP No. 10663, LOCATED IN THE NORTHWEST QUARTER OF THE NORTHWEST QUARTER OF SECTION 31, TOWNSHIP 07 NORTH, RANGE 20 EAST, CITY OF WAUKESHA, WAUKESHA COUNTY, WISCONSIN.



CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
KENOSHA | APPLETON | WAUSAU


MADISON REGIONAL OFFICE  
161 HORIZON DRIVE, SUITE 101  
VERONA, WISCONSIN 53593  
P. 608.848.5060

CLIENT:  
**SUMMIT CREDIT UNION**

CLIENT ADDRESS:  
**4800 AMERICAN PARKWAY  
MADISON, WI 53718-8308**

PROJECT:  
**WAUKESHA**

PROJECT LOCATION:  
**CITY OF WAUKESHA  
WAUKESHA COUNTY, WISCONSIN**




PLAN MODIFICATIONS:

#	Date	Description
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		

**ALTA/NSPS LAND TITLE SURVEY**

MAP No: E-#  
SHEET NUMBER:  
**1 OF 1**

JSD PROJECT NO: 18-8460



- LEGEND**
- GOVERNMENT CORNER
  - 1" IRON PIPE FOUND
  - CHISELED 'X' FOUND
  - COTTON SPINDLE SET
  - FINISHED FLOOR SHOT LOCATION
  - SDM
  - SANITARY MANHOLE
  - CLEAN OUT
  - HYDRANT
  - WATER VALVE
  - ROUND CASTED INLET
  - CURB INLET
  - GAS REGULATOR/METER
  - MANHOLE - GREASE TRAP
  - ELECTRIC MANHOLE
  - ELECTRIC PEDESTAL
  - POWER POLE W/GUY
  - LIGHT POLE
  - TELEPHONE PEDESTAL
  - TELEPHONE MANHOLE
  - DECIDUOUS TREE
  - CONIFEROUS TREE
  - BUSH
  - HANDICAP PARKING
  - PARCEL BOUNDARY
  - SECTION LINE
  - RIGHT-OF-WAY LINE
  - CENTERLINE
  - CHORD LINE
  - PLATTED LOT LINE
  - EASEMENT LINE
  - CONCRETE CURB & GUTTER
  - SANITARY SEWER
  - WATER LINE
  - STORM SEWER
  - NATURAL GAS
  - OVERHEAD ELECTRIC DISTRIBUTION
  - UNDERGROUND ELECTRIC
  - FIBER OPTIC
  - UNDERGROUND TELEPHONE
  - UNDERGROUND CABLE
  - EDGE OF WOODS OR BRUSH
  - BUILDING
  - WALL LINE
  - INDEX CONTOUR
  - INTERMEDIATE CONTOUR
  - SPOT ELEVATION
  - BITUMINOUS PAVEMENT
  - RETAINING WALL
  - CONCRETE PAVEMENT
  - NO ACCESS
  - PAVEMENT STRIPING
  - END OF FLAGGED UTILITIES
  - DENOTES RECORD DATA DEPICTED THE SAME LINE ON THE GROUND AS RELAYED BY THIS SURVEY
  - CANOPY COLUMN (TYP)
  - EDGE OF CANOPY

- NOTES**
- FIELD WORK PERFORMED BY JSD PROFESSIONAL SERVICES, INC. ON MARCH 29, 2018.
  - BEARINGS FOR THIS SURVEY AND MAP ARE BASED ON THE SOUTHEASTERN WISCONSIN REGIONAL PLANNING COMMISSION (SEWRPC), THE WEST LINE OF THE NORTHWEST QUARTER OF SECTION 31-07-20, BEARS 50073057"E.
  - ELEVATIONS ARE BASED ON THE NATIONAL GEODETIC VERTICAL DATUM OF 1929 (NGVD29). BENCHMARK IS A BRASS CAP IN CONCRETE MARKING THE NORTHWEST CORNER OF SECTION 31-07-20, ELEVATION = 931.30'
  - CONTOUR INTERVAL IS ONE FOOT.
  - SUBSURFACE UTILITIES AND FEATURES SHOWN ON THIS MAP HAVE BEEN APPROXIMATED BY LOCATING SURFICIAL FEATURES AND APPURTENANCES, LOCATING DIGGERS HOTLINE FIELD MARKINGS AND BY REFERENCE TO UTILITY RECORDS AND MAPS. BIGGER'S HOTLINE TICKET No.s 20181108335, 20181108347, 20181108366, 20181108372, 20181108416 AND 20181108425, WITH A CLEAR DATE OF MARCH 26, 2018.
  - UTILITY COMPANIES CONTACTED THRU DIGGERS HOTLINE: CITY OF DELAFIELD, DEPARTMENT OF PUBLIC WORKS, WISCONSIN DOT-TS EQUIPMENT, AT&T TRANSMISSION, WE ENERGIES, WISCONSIN DOT SOUTHEAST REGION, LEVEL 3 COMMUNICATIONS, TIME WARNER CABLE, CENTURYLINK.
  - BEFORE EXCAVATION, APPROPRIATE UTILITY COMPANIES SHOULD BE CONTACTED. FOR EXACT LOCATION OF UNDERGROUND UTILITIES, CONTACT DIGGERS HOTLINE, AT 1.800.242.8511.
  - JSD PROFESSIONAL SERVICES, INC. DOES NOT GUARANTEE THAT THE BENCHMARK ELEVATIONS LISTED ON THIS MAP HAVE NOT BEEN DISTURBED SINCE THE DATE OF THIS SURVEY AND SHOULD BE VERIFIED PRIOR TO CONSTRUCTION ACTIVITIES.
  - SET BACKS ARE BASED ON CHAPTER 22, 22.37(7). THERE ARE NO REFERENCES MADE TO CORNER LOTS. SET BACKS ALONG HERITAGE LANE MAY BE GREATER, CONTACT CITY OF WAUKESHA ZONING DEPARTMENT.
  - SANITARY SEWER AND WATER SERVICE LATERAL SIZE AND LOCATION ARE UNKNOWN.

- NOTES CORRESPONDING TO TABLE A REQUIREMENTS:**
- ITEM 3 THE SUBJECT PROPERTY LIES IN ZONE X (AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN) PER FEMA MAP NUMBER 5504790186F, EFFECTIVE DATE OF NOVEMBER 19, 2008.
  - ITEM 6(b) CURRENT ZONING CLASSIFICATION IS B-5, COMMUNITY BUSINESS, FROM CITY WEB SITE.
  - ITEM 9 THERE ARE 10 REGULAR PARKING SPACES AND 1 HANDICAP SPACE FOR A TOTAL OF 11 PARKING SPACES.
  - ITEM 10(a) THERE ARE NO DIVISION OR PARTY WALLS WITH RESPECT TO ADJOINING PROPERTIES.
  - ITEM 11 SOURCE INFORMATION FROM PLANS AND MARKING WILL BE COMBINED WITH OBSERVED EVIDENCE OF UTILITIES PURSUANT TO SECTION 9.6.IV, TO DEVELOP A VIEW OF THE UNDERGROUND UTILITIES. HOWEVER, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY, COMPLETELY, AND RELIABLY DEPICTED. IN ADDITION, IN SOME JURISDICTIONS, 811 OR OTHER SIMILAR UTILITY LOCATE REQUESTS FROM SURVEYORS MAY BE IGNORED OR RESULT IN AN INCOMPLETE RESPONSE. IN WHICH CASE, THE SURVEYOR SHALL NOTE ON THE PLAT OR MAP HOW THIS AFFECTED THE SURVEYOR'S ASSESSMENT OF THE LOCATION OF THE UTILITIES. WHERE ADDITIONAL OR MORE DETAILED INFORMATION IS REQUIRED, THE CLIENT IS ADVISED THAT EXCAVATION AND/OR A PRIVATE UTILITY LOCATE REQUEST MAY BE NECESSARY.
  - ITEM 16 THERE IS NO OBSERVED EVIDENCE OF CURRENT EARTH MOVING WORK, BUILDING CONSTRUCTION OR BUILDING ADDITIONS AT THE TIME OF THIS SURVEY.
  - ITEM 17 THERE ARE NO PROPOSED CHANGES IN THE STREET RIGHT-OF-WAY LINES PER CITY OF DELAFIELD. THERE IS NO OBSERVED EVIDENCE OF RECENT STREET OR SIDEWALK CONSTRUCTION OR REPAIRS.
  - ITEM 18 THERE HAS BEEN NO FIELD DELINEATION OF WETLANDS CONDUCTED FOR THIS SITE.
  - ITEM 19 ANY OFFSITE EASEMENT FOR THE SUBJECT PROPERTY IS SHOWN IN ITS ENTIRETY.

- NOTES CORRESPONDING TO SCHEDULE B-SECTION TWO EXCEPTIONS**  
(CHICAGO TITLE INSURANCE COMPANY, COMMITMENT No.: CO-7333, COMMITMENT DATE: MARCH 6, 2018)
- (10) EASEMENT(S) FOR THE PURPOSE(S) AND RIGHTS INCIDENTAL THERETO, AS GRANTED IN A DOCUMENT, GRANTED TO WISCONSIN TELEPHONE COMPANY AND WISCONSIN ELECTRIC POWER COMPANY, FOR UTILITY PURPOSES, RECORDED ON APRIL 6, 1960, AS DOCUMENT No. 520795. THIS ITEM DOES NOT AFFECT THE SUBJECT PROPERTY AND IS NOT PLOTTED HEREON. (S IN CURRENT HIGHWAY RIGHT-OF-WAY).
  - (11) ACCESS LIMITATIONS AND DEVELOPMENT RESTRICTIONS SET FORTH IN INDENTURE RECORDED FEBRUARY 9, 1966 AS DOCUMENT No. 655271. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (12) EASEMENT(S) FOR THE PURPOSE(S) AND RIGHTS INCIDENTAL THERETO, AS GRANTED IN A DOCUMENT, GRANTED TO WISCONSIN ELECTRIC POWER COMPANY AND WISCONSIN TELEPHONE COMPANY, FOR UTILITY PURPOSES, RECORDED ON MARCH 13, 1976, AS DOCUMENT No. 756797. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (13) RECITALS AS SHOWN ON CERTIFIED SURVEY MAP No. 2681 RECORDED ON SEPTEMBER 1, 1976, AS DOCUMENT No. 965499, WHICH AMONG OTHER THINGS RECITES EASEMENT FOR INGRESS AND EGRESS, RESTRICTIONS AND NOTES. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (14) MEMORANDUM OF AGREEMENT RECORDED MARCH 8, 1977 AS DOCUMENT No. 987077. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS NOT GRAPHIC IN NATURE, THEREFORE IT IS NOT PLOTTED HEREON.
  - (15) EASEMENT(S) FOR THE PURPOSE(S) AND RIGHTS INCIDENTAL THERETO, AS GRANTED IN A DOCUMENT, GRANTED TO THE CITY OF WAUKESHA, FOR SANITARY SEWER PURPOSES, RECORDED ON OCTOBER 25, 1977, AS DOCUMENT No. 1021809. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (16) EASEMENT(S) FOR THE PURPOSE(S) AND RIGHTS INCIDENTAL THERETO, AS GRANTED IN A DOCUMENT, GRANTED TO THE CITY OF WAUKESHA, FOR SANITARY SEWER PURPOSES, RECORDED ON NOVEMBER 2, 1977, AS DOCUMENT No. 1022917. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (17) EASEMENT(S) FOR THE PURPOSE(S) AND RIGHTS INCIDENTAL THERETO, AS GRANTED IN A DOCUMENT, GRANTED TO THE CITY OF WAUKESHA, FOR SANITARY SEWER PURPOSES, RECORDED ON JUNE 30, 1978, AS DOCUMENT No. 1054817. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (18) SANITARY SEWER EASEMENT RECORDED DECEMBER 7, 1978 AS DOCUMENT No. 1075472. THIS ITEM DOES AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.
  - (19) RECITALS AS SHOWN ON CERTIFIED SURVEY MAP No. 10663 RECORDED ON MARCH 31, 2009, AS DOCUMENT No. 3641473, WHICH AMONG OTHER THINGS RECITES SIDEWALK EASEMENT, RESTRICTIONS, NOTES, INGRESS/EGRESS EASEMENT, CROSS ACCESS EASEMENT, TEMPORARY SLOPE EASEMENT FOR SIDEWALK CONSTRUCTION AND ACCESS LIMITATIONS. THIS ITEM MAY AFFECT THE SUBJECT PROPERTY AND IS PLOTTED HEREON.

**LEGAL DESCRIPTION (AS FURNISHED)**  
(CHICAGO TITLE INSURANCE COMPANY, COMMITMENT No.: CO-7333, COMMITMENT DATE: MARCH 6, 2018)


LOT 1 OF CERTIFIED SURVEY MAP No. 10663, RECORDED MARCH 31, 2009, IN VOLUME 102 OF CERTIFIED SURVEY MAPS ON PAGES 309 OT 313 AS DOCUMENT No. 3641473, A DIVISION OF PARCEL 6 OF CERTIFIED SURVEY MAP No. 2681 AND LANDS IN THE NORTHWEST 1/4 OF THE NORTHWEST 1/4 OF SECTION 31, TOWN 7 NORTH, RANGE 20 EAST, IN THE CITY OF WAUKESHA, COUNTY OF WAUKESHA, STATE OF WISCONSIN.

TAX KEY No.: WAC 1130.115.001  
ADDRESS: 2208 E. MORELAND BLVD.

**SURVEYOR'S CERTIFICATE**  
TO:  
1) PINNACLE WAUKESHA BURGERS, LLC, A WISCONSIN LIMITED LIABILITY COMPANY,  
2) BANK MUTUAL,  
3) CHICAGO TITLE INSURANCE COMPANY.

THIS IS TO CERTIFY THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT IS BASED WERE MADE IN ACCORDANCE WITH THE 2016 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/NSPS LAND TITLE SURVEYS, JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS AND INCLUDES ITEMS 1, 2, 3, 4, 5, 6(a), 7(a), 7(b), 7(c), 8, 9, 10(c), 11, 13, 14, 16, 17, 18, 19 AND 20 OF TABLE A THEREOF. THE FIELD WORK WAS COMPLETED ON MARCH 28, 2018.

JOHN KREBS, S-1878  
PROFESSIONAL LAND SURVEYOR



**STORM SEWER MANHOLES**

STRUCT. ID	RIM ELEVATION	INVERT	ELEVATION	PIPE SIZE	PIPE TYPE
STM-1	930.77	NE	928.67	6"	PVC
		SW	928.68	6"	PVC
		NW	928.17	10"	PVC
STM-2	933.33	SE	930.98	6"	PVC
		NW	930.38	10"	PVC
		SE	929.62	10"	PVC
STM-3	932.92	SW	929.59	6"	PVC
		NW	930.29	6"	PVC
		NE	927.87	10"	PVC

**STORM SEWER INLETS**

INLET ID	RIM ELEVATION	INVERT	ELEVATION	PIPE SIZE	PIPE TYPE
INL-1	931.90	SW	928.12	10"	PVC
		SE	928.28	10"	PVC
		NE	924.22	10"	PVC
INL-2	918.30	SW	918.73	10"	PVC
		NE	915.75	12"	RCP
		SW	915.47	12"	RCP
INL-3	919.32	NW	915.47	12"	RCP
		NW	915.47	12"	RCP

**SANITARY SEWER MANHOLES**

STRUCT. ID	RIM ELEVATION	INVERT	ELEVATION	PIPE SIZE	PIPE TYPE
SAN-1	936.92	SE	930.66	6"	PVC
		SW	930.51	6"	PVC
		NW	930.58	6"	PVC
SAN-2	927.79	SE	922.65	8"	PVC
		NE	922.55	8"	PVC
		SW	913.99	8"	PVC
SAN-3	920.49	NE	913.79	8"	PVC
		NE	913.79	8"	PVC

**WATER VALVES**


VALVE No.	SIZE	RIM ELEVATION	INVERT	TOP NUT ELEVATION	PIPE INVERT
WV-1	10"	938.75	TN	932.45	930.70

**BENCHMARKS**

BENCH MARK	ELEVATION	DESCRIPTION
BM-1	938.42	ARROW ON HYDRANT IN FRONT OF SITE
BM-2	935.18	RR SPIKE IN UTILITY POLE NORTHWEST CORNER OF SITE

**CURVE TABLE**

CURVE	LENGTH	RADIUS	DELTA	CHORD	CHORD BEARING
C-1	120.51'	286.55'	24°05'43"	119.62'	N78°24'32"E
( )	120.51'	286.55'	24°05'43"	119.62'	N79°34'58"E
C-2	90.85'	63.96'	81°22'52"	83.40'	S73°24'58"E
( )	90.80'	63.96'	81°20'08"	83.36'	S72°10'24"E





## **APPENDIX 2**

### **SOILS INFORMATION**

#### **USDA NRCS WEB SOIL SURVEY**


Hydrologic Soil Group—Milwaukee and Waukesha Counties, Wisconsin





## MAP LEGEND

### Area of Interest (AOI)









 Area of Interest (AOI)

### Soils

#### Soil Rating Polygons





 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Lines

 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Points






 A  
 A/D  
 B  
 B/D

 C  
 C/D  
 D  
 Not rated or not available


### Water Features

 Streams and Canals

### Transportation

 Rails  
 Interstate Highways  
 US Routes  
 Major Roads  
 Local Roads

### Background

 Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:15,800.

**Warning:** Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Milwaukee and Waukesha Counties, Wisconsin  
 Survey Area Data: Version 13, Oct 6, 2017

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 7, 2014—Sep 22, 2014

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
HmB	Hochheim loam, 2 to 6 percent slopes	D	0.0	0.4%
HmB2	Hochheim loam, 2 to 6 percent slopes, eroded	D	0.9	8.0%
HmC2	Hochheim loam, 6 to 12 percent slopes, eroded	D	9.0	84.2%
ScB	St. Charles silt loam, 2 to 6 percent slopes	B	0.8	7.4%
<b>Totals for Area of Interest</b>			<b>10.7</b>	<b>100.0%</b>

## Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

## Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Higher

# **APPENDIX 3**


## **PRELIMINARY PLANS**

# **APPENDIX 4**

## **PRE-DEVELOPMENT HYDROLOGIC CALCULATIONS**

EXISTING WATERSHED MAP  
PRE-DEVELOPMENT HYDROCAD OUTPUT

File: I:\2018\185469\DWG\185469\_SWMP.dwg Layout: EX1.0 User: chuhita Plotted: Apr 06, 2018 - 10:12am Xref's:



**LEGEND (PROPOSED)**

- PROPERTY LINE
- SETBACK LINE
- EASEMENT LINE
- BUILDING LINE
- BUILDING OVERHANG LINE
- EDGE OF CONCRETE
- STANDARD CURB AND GUTTER
- REJECT CURB AND GUTTER
- PROPOSED CONCRETE PAVEMENT
- PROPOSED HEAVY DUTY CONCRETE PAVEMENT
- PROPOSED ASPHALT PAVEMENT
- PROPOSED HEAVY DUTY ASPHALT PAVEMENT
- LIGHT POLE
- BOLLARD

**WATERSHED CHARACTERISTICS**

WATERSHED A  
 49,353 SF (66.4% IMPERVIOUS)  
 6 MINUTE TIME OF CONCENTRATION (MINIMUM)

WATERSHED OS  
 5663 SF (25.0% IMPERVIOUS)  
 6 MINUTE TIME OF CONCENTRATION (MINIMUM)



CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
 KENOSHA | APPLETON | WAUSAU

**MADISON REGIONAL OFFICE**  
 161 HORIZON DRIVE, SUITE 101  
 VERONA, WISCONSIN 53593  
 P. 608.848.5060

CLIENT:  
**SUMMIT CREDIT UNION**

CLIENT ADDRESS:  
**4800 American Parkway  
 MADISON, WI 53718**

PROJECT:  
**SUMMIT CREDIT UNION - WAUKESHA BRANCH**

PROJECT LOCATION:  
**2208 E MORELAND BOULEVARD  
 WAUKESHA COUNTY**

PLAN MODIFICATIONS:

#	Date:	Description:
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		



Design/Drawn: CLH  
 Approved: WHD

SHEET TITLE:  
**EXISTING DRAINAGE AREA MAP**


SHEET NUMBER:  
**EX1.0**

JSD PROJECT NO: 18-8469


**EAST MORELAND BOULEVARD  
 (USH 18)**




THESE PLANS AND DESIGNS ARE COPYRIGHT PROTECTED AND MAY NOT BE USED IN WHOLE OR IN PART WITHOUT THE WRITTEN CONSENT OF JSD PROFESSIONAL SERVICES, INC.





Off-site



Pre-Development Site



Pre-Development



**Predevelopment**

Prepared by Microsoft

Printed 4/6/2018

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Page 2

**Area Listing (all nodes)**

Area (acres)	CN	Description (subcatchment-numbers)
0.849	98	Impervious, HSG D (A, OS)
0.381	78	Pervious, HSG D (A)
0.033	78	Pervious, HSG D (OS)
<b>1.263</b>	<b>91</b>	<b>TOTAL AREA</b>



**Predevelopment**

Prepared by Microsoft

Printed 4/6/2018

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Page 3

**Soil Listing (all nodes)**

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
1.263	HSG D	A, OS
0.000	Other	
<b>1.263</b>		<b>TOTAL AREA</b>

**Predevelopment**

Prepared by Microsoft

Printed 4/6/2018

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Page 4

**Ground Covers (all nodes)**

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	0.000	0.849	0.000	0.849	Impervious	A, OS
0.000	0.000	0.000	0.381	0.000	0.381	Pervious	A
0.000	0.000	0.000	0.033	0.000	0.033	Pervious	OS
<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>1.263</b>	<b>0.000</b>	<b>1.263</b>	<b>TOTAL AREA</b>	

## Predevelopment

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Pre-Development

MSE 24-hr 3 2-year Rainfall=2.70"

Printed 4/6/2018

Page 5

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

### Link 1L: Pre-Development

Inflow=3.98 cfs 0.184 af  
Primary=3.98 cfs 0.184 af

### Subcatchment A: Pre-Development Site

Runoff Area=49,353 sf 66.36% Impervious Runoff Depth>1.73"  
Tc=6.0 min CN=91 Runoff=3.54 cfs 0.163 af

### Subcatchment OS: Off-site

Runoff Area=5,663 sf 75.00% Impervious Runoff Depth>1.90"  
Tc=6.0 min CN=93 Runoff=0.44 cfs 0.021 af

**Total Runoff Area = 1.263 ac Runoff Volume = 0.184 af Average Runoff Depth = 1.74"**  
**32.75% Pervious = 0.414 ac 67.25% Impervious = 0.849 ac**

## Predevelopment

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Pre-Development

MSE 24-hr 3 2-year Rainfall=2.70"

Printed 4/6/2018

Page 6

### Summary for Link 1L: Pre-Development

Inflow Area = 1.263 ac, 67.25% Impervious, Inflow Depth > 1.74" for 2-year event  
Inflow = 3.98 cfs @ 12.13 hrs, Volume= 0.184 af  
Primary = 3.98 cfs @ 12.13 hrs, Volume= 0.184 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

### Summary for Subcatchment A: Pre-Development Site

Runoff = 3.54 cfs @ 12.13 hrs, Volume= 0.163 af, Depth> 1.73"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 2-year Rainfall=2.70"

Area (sf)	CN	Description
* 32,752	98	Impervious, HSG D
* 16,601	78	Pervious, HSG D
49,353	91	Weighted Average
16,601		33.64% Pervious Area
32,752		66.36% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Minimum TC

### Summary for Subcatchment OS: Off-site

Runoff = 0.44 cfs @ 12.13 hrs, Volume= 0.021 af, Depth> 1.90"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 2-year Rainfall=2.70"

Area (sf)	CN	Description
* 4,247	98	Impervious, HSG D
* 1,416	78	Pervious, HSG D
5,663	93	Weighted Average
1,416		25.00% Pervious Area
4,247		75.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Minimum TC

**Predevelopment**

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Pre-Development

MSE 24-hr 3 10-year Rainfall=3.81"

Printed 4/6/2018

Page 7

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Link 1L: Pre-Development**

Inflow=6.11 cfs 0.290 af  
Primary=6.11 cfs 0.290 af

**Subcatchment A: Pre-Development Site**

Runoff Area=49,353 sf 66.36% Impervious Runoff Depth>2.74"  
Tc=6.0 min CN=91 Runoff=5.45 cfs 0.259 af

**Subcatchment OS: Off-site**

Runoff Area=5,663 sf 75.00% Impervious Runoff Depth>2.94"  
Tc=6.0 min CN=93 Runoff=0.66 cfs 0.032 af

**Total Runoff Area = 1.263 ac Runoff Volume = 0.290 af Average Runoff Depth = 2.76"**  
**32.75% Pervious = 0.414 ac 67.25% Impervious = 0.849 ac**

# Predevelopment

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Pre-Development  
MSE 24-hr 3 10-year Rainfall=3.81"

Printed 4/6/2018

Page 8

## Summary for Link 1L: Pre-Development

Inflow Area = 1.263 ac, 67.25% Impervious, Inflow Depth > 2.76" for 10-year event  
 Inflow = 6.11 cfs @ 12.13 hrs, Volume= 0.290 af  
 Primary = 6.11 cfs @ 12.13 hrs, Volume= 0.290 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

## Summary for Subcatchment A: Pre-Development Site

Runoff = 5.45 cfs @ 12.13 hrs, Volume= 0.259 af, Depth> 2.74"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 10-year Rainfall=3.81"

Area (sf)	CN	Description
* 32,752	98	Impervious, HSG D
* 16,601	78	Pervious, HSG D
49,353	91	Weighted Average
16,601		33.64% Pervious Area
32,752		66.36% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Minimum TC

## Summary for Subcatchment OS: Off-site

Runoff = 0.66 cfs @ 12.13 hrs, Volume= 0.032 af, Depth> 2.94"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 10-year Rainfall=3.81"

Area (sf)	CN	Description
* 4,247	98	Impervious, HSG D
* 1,416	78	Pervious, HSG D
5,663	93	Weighted Average
1,416		25.00% Pervious Area
4,247		75.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Minimum TC

## Predevelopment

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Pre-Development

MSE 24-hr 3 100-year Rainfall=6.18"

Printed 4/6/2018

Page 9

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

### Link 1L: Pre-Development

Inflow=10.61 cfs 0.526 af  
Primary=10.61 cfs 0.526 af

### Subcatchment A: Pre-Development Site

Runoff Area=49,353 sf 66.36% Impervious Runoff Depth>4.97"  
Tc=6.0 min CN=91 Runoff=9.50 cfs 0.469 af

### Subcatchment OS: Off-site

Runoff Area=5,663 sf 75.00% Impervious Runoff Depth>5.19"  
Tc=6.0 min CN=93 Runoff=1.11 cfs 0.056 af

**Total Runoff Area = 1.263 ac Runoff Volume = 0.526 af Average Runoff Depth = 4.99"**  
**32.75% Pervious = 0.414 ac 67.25% Impervious = 0.849 ac**

# Predevelopment

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Pre-Development  
MSE 24-hr 3 100-year Rainfall=6.18"

Printed 4/6/2018

Page 10

## Summary for Link 1L: Pre-Development

Inflow Area = 1.263 ac, 67.25% Impervious, Inflow Depth > 4.99" for 100-year event  
 Inflow = 10.61 cfs @ 12.13 hrs, Volume= 0.526 af  
 Primary = 10.61 cfs @ 12.13 hrs, Volume= 0.526 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

## Summary for Subcatchment A: Pre-Development Site

Runoff = 9.50 cfs @ 12.13 hrs, Volume= 0.469 af, Depth> 4.97"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 100-year Rainfall=6.18"

Area (sf)	CN	Description
* 32,752	98	Impervious, HSG D
* 16,601	78	Pervious, HSG D
49,353	91	Weighted Average
16,601		33.64% Pervious Area
32,752		66.36% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Minimum TC

## Summary for Subcatchment OS: Off-site

Runoff = 1.11 cfs @ 12.13 hrs, Volume= 0.056 af, Depth> 5.19"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 100-year Rainfall=6.18"

Area (sf)	CN	Description
* 4,247	98	Impervious, HSG D
* 1,416	78	Pervious, HSG D
5,663	93	Weighted Average
1,416		25.00% Pervious Area
4,247		75.00% Impervious Area


Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Minimum TC



**APPENDIX 5**  
**POST-DEVELOPMENT HYDROLOGIC CALCULATIONS**

PROPOSED WATERSHED MAP  
POST-DEVELOPMENT HYDROCAD OUTPUT

File: I:\2018\188469\DWG\188469 SWMP.dwg Layout: EX2.0 User: chuhta Plotted: Apr 06, 2018 - 10:17am Xref's:



**LEGEND (PROPOSED)**

	PROPERTY LINE
	SETBACK LINE
	EASEMENT LINE
	BUILDING LINE
	BUILDING OVERHANG LINE
	EDGE OF CONCRETE
	STANDARD CURB AND GUTTER
	REJECT CURB AND GUTTER
	PROPOSED CONCRETE PAVEMENT
	PROPOSED HEAVY DUTY CONCRETE PAVEMENT
	PROPOSED ASPHALT PAVEMENT
	PROPOSED HEAVY DUTY ASPHALT PAVEMENT
	LIGHT POLE
	BOLLARD

**WATERSHED CHARACTERISTICS**

WATERSHED C	34,499 SF (57.0% IMPERVIOUS)	6 MINUTE TIME OF CONCENTRATION (MINIMUM)
WATERSHED UT	14,854 SF (57.0% IMPERVIOUS)	6 MINUTE TIME OF CONCENTRATION (MINIMUM)
WATERSHED OS	5663 SF (25.0% IMPERVIOUS)	6 MINUTE TIME OF CONCENTRATION (MINIMUM)

**EAST MORELAND BOULEVARD  
(USH 18)**



CREATE THE VISION TELL THE STORY

MADISON | MILWAUKEE  
KENOSHA | APPLETON | WAUSAU

**MADISON REGIONAL OFFICE**  
161 HORIZON DRIVE, SUITE 101  
VERONA, WISCONSIN 53593  
P. 608.848.5060

CLIENT:  
**SUMMIT CREDIT UNION**

CLIENT ADDRESS:  
**4800 American Parkway  
MADISON, WI 53718**

PROJECT:  
**SUMMIT CREDIT UNION - WAUKESHA BRANCH**

PROJECT LOCATION:  
**2208 E MORELAND BOULEVARD  
WAUKESHA COUNTY**

**PLAN MODIFICATIONS:**


#	Date:	Description:
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		

Design/Drawn: CLH  
Approved: WHD





SHEET TITLE:  
**PROPOSED DRAINAGE AREA MAP**

SHEET NUMBER:  
**EX2.0**

JSD PROJECT NO: 18-8469



THESE PLANS AND DESIGNS ARE COPYRIGHT PROTECTED AND MAY NOT BE USED IN WHOLE OR IN PART WITHOUT THE WRITTEN CONSENT OF JSD PROFESSIONAL SERVICES, INC.



**Post-Development**

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Printed 4/6/2018

Page 2

**Area Listing (all nodes)**

Area (acres)	CN	Description (subcatchment-numbers)
1.439	98	Impervious, HSG D (B, C, OS1, OS2, UT)
1.022	78	Pervious, HSG D (B, C, UT)
0.065	78	Pervious, HSG D (OS1, OS2)
<b>2.526</b>	<b>89</b>	<b>TOTAL AREA</b>

**Post-Development**

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Printed 4/6/2018

Page 3

**Soil Listing (all nodes)**

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
2.526	HSG D	B, C, OS1, OS2, UT
0.000	Other	
<b>2.526</b>		<b>TOTAL AREA</b>

**Post-Development**

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Printed 4/6/2018

Page 4

**Ground Covers (all nodes)**

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	0.000	1.439	0.000	1.439	Impervious	B, C, OS1, OS2, UT
0.000	0.000	0.000	1.022	0.000	1.022	Pervious	B, C, UT
0.000	0.000	0.000	0.065	0.000	0.065	Pervious	OS1, OS2
<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>2.526</b>	<b>0.000</b>	<b>2.526</b>	<b>TOTAL AREA</b>	

## Post-Development

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Post-Development

MSE 24-hr 3 2-year Rainfall=2.70"

Printed 4/6/2018

Page 5

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

### Link 2L: Uncontrolled

Inflow=3.84 cfs 0.176 af  
Primary=3.84 cfs 0.176 af

### Link 3L: Post-Development

Inflow=3.16 cfs 0.154 af  
Primary=3.16 cfs 0.154 af

### Pond 6P: WQ Chamber

Peak Elev=927.42' Storage=0.031 af Inflow=2.72 cfs 0.124 af  
12.0" Round Culvert n=0.011 L=8.0' S=0.0100 '/' Outflow=2.45 cfs 0.121 af

### Subcatchment B: UnControlled Site

Runoff Area=49,353 sf 62.45% Impervious Runoff Depth>1.65"  
Tc=6.0 min CN=90 Runoff=3.40 cfs 0.155 af

### Subcatchment C: Untreated Site

Runoff Area=34,499 sf 57.01% Impervious Runoff Depth>1.57"  
Tc=6.0 min CN=89 Runoff=2.28 cfs 0.103 af

### Subcatchment OS1: Off-site

Runoff Area=5,663 sf 75.00% Impervious Runoff Depth>1.90"  
Tc=6.0 min CN=93 Runoff=0.44 cfs 0.021 af

### Subcatchment OS2: Off-site

Runoff Area=5,663 sf 75.00% Impervious Runoff Depth>1.90"  
Tc=6.0 min CN=93 Runoff=0.44 cfs 0.021 af

### Subcatchment UT: Untreated Site Bypass

Runoff Area=0.341 ac 24.93% Impervious Runoff Depth>1.15"  
Tc=6.0 min CN=83 Runoff=0.74 cfs 0.033 af

**Total Runoff Area = 2.526 ac Runoff Volume = 0.333 af Average Runoff Depth = 1.58"**  
**43.03% Pervious = 1.087 ac 56.97% Impervious = 1.439 ac**

## Post-Development

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Post-Development

MSE 24-hr 3 2-year Rainfall=2.70"

Printed 4/6/2018

Page 6

### Summary for Link 2L: Uncontrolled

Inflow Area = 1.263 ac, 63.74% Impervious, Inflow Depth > 1.67" for 2-year event  
Inflow = 3.84 cfs @ 12.13 hrs, Volume= 0.176 af  
Primary = 3.84 cfs @ 12.13 hrs, Volume= 0.176 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

### Summary for Link 3L: Post-Development

Inflow Area = 1.263 ac, 50.20% Impervious, Inflow Depth > 1.46" for 2-year event  
Inflow = 3.16 cfs @ 12.15 hrs, Volume= 0.154 af  
Primary = 3.16 cfs @ 12.15 hrs, Volume= 0.154 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

### Summary for Pond 6P: WQ Chamber

Inflow Area = 0.922 ac, 59.55% Impervious, Inflow Depth > 1.61" for 2-year event  
Inflow = 2.72 cfs @ 12.13 hrs, Volume= 0.124 af  
Outflow = 2.45 cfs @ 12.16 hrs, Volume= 0.121 af, Atten= 10%, Lag= 1.9 min  
Primary = 2.45 cfs @ 12.16 hrs, Volume= 0.121 af

Routing by Dyn-Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Starting Elev= 926.00' Surf.Area= 0.009 ac Storage= 0.019 af

Peak Elev= 927.42' @ 12.16 hrs Surf.Area= 0.008 ac Storage= 0.031 af (0.012 af above start)

Plug-Flow detention time= 66.7 min calculated for 0.102 af (82% of inflow)

Center-of-Mass det. time= 8.2 min ( 782.6 - 774.4 )

Volume	Invert	Avail.Storage	Storage Description
#1	923.25'	0.042 af	<b>72.0" Round Pipe Storage</b> L= 65.0'

Device	Routing	Invert	Outlet Devices
#1	Primary	926.25'	<b>12.0" Round Culvert</b> L= 8.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 926.25' / 926.17' S= 0.0100 '/ Cc= 0.900 n= 0.011, Flow Area= 0.79 sf

**Primary OutFlow** Max=2.39 cfs @ 12.16 hrs HW=927.39' TW=0.00' (Dynamic Tailwater)

←1=Culvert (Inlet Controls 2.39 cfs @ 3.05 fps)

### Summary for Subcatchment B: UnControlled Site

Runoff = 3.40 cfs @ 12.13 hrs, Volume= 0.155 af, Depth> 1.65"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 2-year Rainfall=2.70"



**Post-Development**

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Post-Development

MSE 24-hr 3 2-year Rainfall=2.70"

Printed 4/6/2018

Page 7

	Area (sf)	CN	Description
*	30,820	98	Impervious, HSG D
*	18,533	78	Pervious, HSG D
	49,353	90	Weighted Average
	18,533		37.55% Pervious Area
	30,820		62.45% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>

**Summary for Subcatchment C: Untreated Site**

Runoff = 2.28 cfs @ 12.13 hrs, Volume= 0.103 af, Depth&gt; 1.57"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 2-year Rainfall=2.70"

	Area (sf)	CN	Description
*	19,669	98	Impervious, HSG D
*	14,830	78	Pervious, HSG D
	34,499	89	Weighted Average
	14,830		42.99% Pervious Area
	19,669		57.01% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>

**Summary for Subcatchment OS1: Off-site**

Runoff = 0.44 cfs @ 12.13 hrs, Volume= 0.021 af, Depth&gt; 1.90"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 2-year Rainfall=2.70"

	Area (sf)	CN	Description
*	4,247	98	Impervious, HSG D
*	1,416	78	Pervious, HSG D
	5,663	93	Weighted Average
	1,416		25.00% Pervious Area
	4,247		75.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>

**Post-Development**

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Post-Development

MSE 24-hr 3 2-year Rainfall=2.70"

Printed 4/6/2018

Page 8

**Summary for Subcatchment OS2: Off-site**

Runoff = 0.44 cfs @ 12.13 hrs, Volume= 0.021 af, Depth&gt; 1.90"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 2-year Rainfall=2.70"

	Area (sf)	CN	Description
*	4,247	98	Impervious, HSG D
*	1,416	78	Pervsious, HSG D
	5,663	93	Weighted Average
	1,416		25.00% Pervious Area
	4,247		75.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>

**Summary for Subcatchment UT: Untreated Site Bypass**

Runoff = 0.74 cfs @ 12.14 hrs, Volume= 0.033 af, Depth&gt; 1.15"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 2-year Rainfall=2.70"

	Area (ac)	CN	Description
*	0.256	78	Pervious, HSG D
*	0.085	98	Impervious, HSG D
	0.341	83	Weighted Average
	0.256		75.07% Pervious Area
	0.085		24.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>

## Post-Development

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Post-Development

MSE 24-hr 3 10-year Rainfall=3.81"

Printed 4/6/2018

Page 9

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

### Link 2L: Uncontrolled

Inflow=5.97 cfs 0.281 af  
Primary=5.97 cfs 0.281 af

### Link 3L: Post-Development

Inflow=4.83 cfs 0.255 af  
Primary=4.83 cfs 0.255 af

### Pond 6P: WQ Chamber

Peak Elev=928.21' Storage=0.037 af Inflow=4.27 cfs 0.200 af  
12.0" Round Culvert n=0.011 L=8.0' S=0.0100 '/' Outflow=3.62 cfs 0.197 af

### Subcatchment B: UnControlled Site

Runoff Area=49,353 sf 62.45% Impervious Runoff Depth>2.64"  
Tc=6.0 min CN=90 Runoff=5.32 cfs 0.250 af

### Subcatchment C: Untreated Site

Runoff Area=34,499 sf 57.01% Impervious Runoff Depth>2.55"  
Tc=6.0 min CN=89 Runoff=3.62 cfs 0.168 af

### Subcatchment OS1: Off-site

Runoff Area=5,663 sf 75.00% Impervious Runoff Depth>2.94"  
Tc=6.0 min CN=93 Runoff=0.66 cfs 0.032 af

### Subcatchment OS2: Off-site

Runoff Area=5,663 sf 75.00% Impervious Runoff Depth>2.94"  
Tc=6.0 min CN=93 Runoff=0.66 cfs 0.032 af

### Subcatchment UT: Untreated Site Bypass

Runoff Area=0.341 ac 24.93% Impervious Runoff Depth>2.03"  
Tc=6.0 min CN=83 Runoff=1.29 cfs 0.058 af

**Total Runoff Area = 2.526 ac Runoff Volume = 0.539 af Average Runoff Depth = 2.56"**  
**43.03% Pervious = 1.087 ac 56.97% Impervious = 1.439 ac**

## Post-Development

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Post-Development

MSE 24-hr 3 10-year Rainfall=3.81"

Printed 4/6/2018

Page 10

### Summary for Link 2L: Uncontrolled

Inflow Area = 1.263 ac, 63.74% Impervious, Inflow Depth > 2.67" for 10-year event  
Inflow = 5.97 cfs @ 12.13 hrs, Volume= 0.281 af  
Primary = 5.97 cfs @ 12.13 hrs, Volume= 0.281 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

### Summary for Link 3L: Post-Development

Inflow Area = 1.263 ac, 50.20% Impervious, Inflow Depth > 2.42" for 10-year event  
Inflow = 4.83 cfs @ 12.15 hrs, Volume= 0.255 af  
Primary = 4.83 cfs @ 12.15 hrs, Volume= 0.255 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

### Summary for Pond 6P: WQ Chamber

Inflow Area = 0.922 ac, 59.55% Impervious, Inflow Depth > 2.60" for 10-year event  
Inflow = 4.27 cfs @ 12.13 hrs, Volume= 0.200 af  
Outflow = 3.62 cfs @ 12.17 hrs, Volume= 0.197 af, Atten= 15%, Lag= 2.4 min  
Primary = 3.62 cfs @ 12.17 hrs, Volume= 0.197 af

Routing by Dyn-Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Starting Elev= 926.00' Surf.Area= 0.009 ac Storage= 0.019 af

Peak Elev= 928.21' @ 12.17 hrs Surf.Area= 0.007 ac Storage= 0.037 af (0.018 af above start)

Plug-Flow detention time= 51.8 min calculated for 0.178 af (89% of inflow)

Center-of-Mass det. time= 7.3 min ( 773.7 - 766.4 )

Volume	Invert	Avail.Storage	Storage Description
#1	923.25'	0.042 af	<b>72.0" Round Pipe Storage</b> L= 65.0'

Device	Routing	Invert	Outlet Devices
#1	Primary	926.25'	<b>12.0" Round Culvert</b> L= 8.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 926.25' / 926.17' S= 0.0100 '/' Cc= 0.900 n= 0.011, Flow Area= 0.79 sf

**Primary OutFlow** Max=3.54 cfs @ 12.17 hrs HW=928.15' TW=0.00' (Dynamic Tailwater)

↑**1=Culvert** (Inlet Controls 3.54 cfs @ 4.50 fps)

### Summary for Subcatchment B: UnControlled Site

Runoff = 5.32 cfs @ 12.13 hrs, Volume= 0.250 af, Depth> 2.64"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 10-year Rainfall=3.81"

**Post-Development**

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Post-Development

MSE 24-hr 3 10-year Rainfall=3.81"

Printed 4/6/2018

Page 11

	Area (sf)	CN	Description
*	30,820	98	Impervious, HSG D
*	18,533	78	Pervious, HSG D
	49,353	90	Weighted Average
	18,533		37.55% Pervious Area
	30,820		62.45% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>

**Summary for Subcatchment C: Untreated Site**

Runoff = 3.62 cfs @ 12.13 hrs, Volume= 0.168 af, Depth&gt; 2.55"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 10-year Rainfall=3.81"

	Area (sf)	CN	Description
*	19,669	98	Impervious, HSG D
*	14,830	78	Pervious, HSG D
	34,499	89	Weighted Average
	14,830		42.99% Pervious Area
	19,669		57.01% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>

**Summary for Subcatchment OS1: Off-site**

Runoff = 0.66 cfs @ 12.13 hrs, Volume= 0.032 af, Depth&gt; 2.94"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 10-year Rainfall=3.81"

	Area (sf)	CN	Description
*	4,247	98	Impervious, HSG D
*	1,416	78	Pervious, HSG D
	5,663	93	Weighted Average
	1,416		25.00% Pervious Area
	4,247		75.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>

## Post-Development

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Post-Development

MSE 24-hr 3 10-year Rainfall=3.81"

Printed 4/6/2018

Page 12

### Summary for Subcatchment OS2: Off-site

Runoff = 0.66 cfs @ 12.13 hrs, Volume= 0.032 af, Depth> 2.94"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 10-year Rainfall=3.81"

	Area (sf)	CN	Description
*	4,247	98	Impervious, HSG D
*	1,416	78	Pervsious, HSG D
	5,663	93	Weighted Average
	1,416		25.00% Pervious Area
	4,247		75.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Minimum TC

### Summary for Subcatchment UT: Untreated Site Bypass

Runoff = 1.29 cfs @ 12.13 hrs, Volume= 0.058 af, Depth> 2.03"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 10-year Rainfall=3.81"

	Area (ac)	CN	Description
*	0.256	78	Pervious, HSG D
*	0.085	98	Impervious, HSG D
	0.341	83	Weighted Average
	0.256		75.07% Pervious Area
	0.085		24.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Minimum TC

**Post-Development**

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Post-Development

MSE 24-hr 3 100-year Rainfall=6.18"

Printed 4/6/2018

Page 13

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Link 2L: Uncontrolled**

Inflow=10.49 cfs 0.515 af  
Primary=10.49 cfs 0.515 af

**Link 3L: Post-Development**

Inflow=10.71 cfs 0.483 af  
Primary=10.71 cfs 0.483 af

**Pond 6P: WQ Chamber**

Peak Elev=934.26' Storage=0.042 af Inflow=7.58 cfs 0.370 af  
12.0" Round Culvert n=0.011 L=8.0' S=0.0100 '/' Outflow=8.22 cfs 0.366 af

**Subcatchment B: UnControlled Site**

Runoff Area=49,353 sf 62.45% Impervious Runoff Depth>4.86"  
Tc=6.0 min CN=90 Runoff=9.38 cfs 0.459 af

**Subcatchment C: Untreated Site**

Runoff Area=34,499 sf 57.01% Impervious Runoff Depth>4.75"  
Tc=6.0 min CN=89 Runoff=6.46 cfs 0.313 af

**Subcatchment OS1: Off-site**

Runoff Area=5,663 sf 75.00% Impervious Runoff Depth>5.19"  
Tc=6.0 min CN=93 Runoff=1.11 cfs 0.056 af

**Subcatchment OS2: Off-site**

Runoff Area=5,663 sf 75.00% Impervious Runoff Depth>5.19"  
Tc=6.0 min CN=93 Runoff=1.11 cfs 0.056 af

**Subcatchment UT: Untreated Site Bypass**

Runoff Area=0.341 ac 24.93% Impervious Runoff Depth>4.10"  
Tc=6.0 min CN=83 Runoff=2.51 cfs 0.117 af

**Total Runoff Area = 2.526 ac Runoff Volume = 1.001 af Average Runoff Depth = 4.76"**  
**43.03% Pervious = 1.087 ac 56.97% Impervious = 1.439 ac**

## Post-Development

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Post-Development

MSE 24-hr 3 100-year Rainfall=6.18"

Printed 4/6/2018

Page 14

### Summary for Link 2L: Uncontrolled

Inflow Area = 1.263 ac, 63.74% Impervious, Inflow Depth > 4.89" for 100-year event  
Inflow = 10.49 cfs @ 12.13 hrs, Volume= 0.515 af  
Primary = 10.49 cfs @ 12.13 hrs, Volume= 0.515 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

### Summary for Link 3L: Post-Development

Inflow Area = 1.263 ac, 50.20% Impervious, Inflow Depth > 4.59" for 100-year event  
Inflow = 10.71 cfs @ 12.14 hrs, Volume= 0.483 af  
Primary = 10.71 cfs @ 12.14 hrs, Volume= 0.483 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

### Summary for Pond 6P: WQ Chamber

Inflow Area = 0.922 ac, 59.55% Impervious, Inflow Depth > 4.81" for 100-year event  
Inflow = 7.58 cfs @ 12.13 hrs, Volume= 0.370 af  
Outflow = 8.22 cfs @ 12.14 hrs, Volume= 0.366 af, Atten= 0%, Lag= 0.8 min  
Primary = 8.22 cfs @ 12.14 hrs, Volume= 0.366 af

Routing by Dyn-Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Starting Elev= 926.00' Surf.Area= 0.009 ac Storage= 0.019 af

Peak Elev= 934.26' @ 12.14 hrs Surf.Area= 0.000 ac Storage= 0.042 af (0.023 af above start)

Plug-Flow detention time= 37.7 min calculated for 0.347 af (94% of inflow)

Center-of-Mass det. time= 6.0 min ( 761.9 - 755.8 )

Volume	Invert	Avail.Storage	Storage Description
#1	923.25'	0.042 af	<b>72.0" Round Pipe Storage</b> L= 65.0'

Device	Routing	Invert	Outlet Devices
#1	Primary	926.25'	<b>12.0" Round Culvert</b> L= 8.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 926.25' / 926.17' S= 0.0100 '/' Cc= 0.900 n= 0.011, Flow Area= 0.79 sf

**Primary OutFlow** Max=7.85 cfs @ 12.14 hrs HW=933.67' TW=0.00' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 7.85 cfs @ 10.00 fps)

### Summary for Subcatchment B: UnControlled Site

Runoff = 9.38 cfs @ 12.13 hrs, Volume= 0.459 af, Depth> 4.86"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 100-year Rainfall=6.18"



**Post-Development**

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Post-Development  
MSE 24-hr 3 100-year Rainfall=6.18"

Printed 4/6/2018

Page 15

	Area (sf)	CN	Description
*	30,820	98	Impervious, HSG D
*	18,533	78	Pervious, HSG D
	49,353	90	Weighted Average
	18,533		37.55% Pervious Area
	30,820		62.45% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>

**Summary for Subcatchment C: Untreated Site**

Runoff = 6.46 cfs @ 12.13 hrs, Volume= 0.313 af, Depth> 4.75"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 100-year Rainfall=6.18"

	Area (sf)	CN	Description
*	19,669	98	Impervious, HSG D
*	14,830	78	Pervious, HSG D
	34,499	89	Weighted Average
	14,830		42.99% Pervious Area
	19,669		57.01% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>

**Summary for Subcatchment OS1: Off-site**

Runoff = 1.11 cfs @ 12.13 hrs, Volume= 0.056 af, Depth> 5.19"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 100-year Rainfall=6.18"

	Area (sf)	CN	Description
*	4,247	98	Impervious, HSG D
*	1,416	78	Pervious, HSG D
	5,663	93	Weighted Average
	1,416		25.00% Pervious Area
	4,247		75.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>

**Post-Development**

Prepared by Microsoft

HydroCAD® 10.00-20 s/n 02918 © 2017 HydroCAD Software Solutions LLC

Post-Development

MSE 24-hr 3 100-year Rainfall=6.18"

Printed 4/6/2018

Page 16

**Summary for Subcatchment OS2: Off-site**

Runoff = 1.11 cfs @ 12.13 hrs, Volume= 0.056 af, Depth> 5.19"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 100-year Rainfall=6.18"

	Area (sf)	CN	Description
*	4,247	98	Impervious, HSG D
*	1,416	78	Pervsious, HSG D
	5,663	93	Weighted Average
	1,416		25.00% Pervious Area
	4,247		75.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>

**Summary for Subcatchment UT: Untreated Site Bypass**

Runoff = 2.51 cfs @ 12.13 hrs, Volume= 0.117 af, Depth> 4.10"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
MSE 24-hr 3 100-year Rainfall=6.18"

	Area (ac)	CN	Description
*	0.256	78	Pervious, HSG D
*	0.085	98	Impervious, HSG D
	0.341	83	Weighted Average
	0.256		75.07% Pervious Area
	0.085		24.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					<b>Direct Entry, Minimum TC</b>


# **APPENDIX 6**

## **SEDIMENT CALCULATIONS**

WINSLAMM DIAGRAM

WINSLAMM INPUT

WINSLAMM OUTPUT



TSS Calculations - InputData.txt

Data file name: I:\2018\188469\Civil\SWMP\Modeling\Slamm\TSS Calculations.mdb  
 WinSLAMM Version 10.3.4  
 Rain file name: C:\WinSLAMM Files\Rain Files\wisReg - Madison WI 1981.RAN  
 Particulate Solids Concentration file name: C:\WinSLAMM Files\v10.1 WI\_AVG01.pscx  
 Runoff Coefficient file name: C:\WinSLAMM Files\WI\_SL06 Dec06.rsvx  
 Residential Street Delivery file name: C:\WinSLAMM Files\WI\_Res and Other Urban Dec06.std  
 Institutional Street Delivery file name: C:\WinSLAMM Files\WI\_Com Inst Indust Dec06.std  
 Commercial Street Delivery file name: C:\WinSLAMM Files\WI\_Com Inst Indust Dec06.std  
 Industrial Street Delivery file name: C:\WinSLAMM Files\WI\_Com Inst Indust Dec06.std  
 Other Urban Street Delivery file name: C:\WinSLAMM Files\WI\_Res and Other Urban Dec06.std  
 Freeway Street Delivery file name: C:\WinSLAMM Files\Freeway Dec06.std  
 Apply Street Delivery Files to Adjust the After Event Load Street Dirt Mass Balance: False  
 Pollutant Relative Concentration file name: C:\WinSLAMM Files\WI\_GEO03.ppd  
 Source Area PSD and Peak to Average Flow Ratio File: C:\WinSLAMM Files\NURP Source Area PSD Files.csv  
 Cost Data file name:  
 Seed for random number generator: -42  
 Study period starting date: 01/01/81 Study period ending date: 12/31/81  
 Start of Winter Season: 12/02 End of Winter Season: 03/12  
 Date: 04-06-2018 Time: 10:44:20  
 Site information:

LU# 1 - Commercial: Primary Total area (ac): 0.340  
 13 - Paved Parking 1: 0.082 ac. Connected Source Area PSD File:  
 C:\WinSLAMM Files\NURP.cpz  
 25 - Driveways 1: 0.126 ac. Connected Source Area PSD File: C:\WinSLAMM Files\NURP.cpz  
 26 - Driveways 2: 0.018 ac. Connected Source Area PSD File: C:\WinSLAMM Files\NURP.cpz  
 31 - Sidewalks 1: 0.007 ac. Connected Source Area PSD File: C:\WinSLAMM Files\NURP.cpz  
 32 - Sidewalks 2: 0.003 ac. Connected Source Area PSD File: C:\WinSLAMM Files\NURP.cpz  
 51 - Small Landscaped Areas 1: 0.093 ac. Normal Clayey Low Density  
 Source Area PSD File: C:\WinSLAMM Files\NURP.cpz  
 52 - Small Landscaped Areas 2: 0.011 ac. Normal Clayey Low Density  
 Source Area PSD File: C:\WinSLAMM Files\NURP.cpz

LU# 2 - Commercial: Offsite Total area (ac): 0.341  
 13 - Paved Parking 1: 0.008 ac. Connected Source Area PSD File:  
 C:\WinSLAMM Files\NURP.cpz  
 25 - Driveways 1: 0.044 ac. Connected Source Area PSD File: C:\WinSLAMM Files\NURP.cpz  
 26 - Driveways 2: 0.022 ac. Connected Source Area PSD File: C:\WinSLAMM Files\NURP.cpz  
 31 - Sidewalks 1: 0.008 ac. Connected Source Area PSD File: C:\WinSLAMM Files\NURP.cpz  
 32 - Sidewalks 2: 0.003 ac. Connected Source Area PSD File: C:\WinSLAMM Files\NURP.cpz  
 51 - Small Landscaped Areas 1: 0.250 ac. Normal Clayey Low Density  
 Source Area PSD File: C:\WinSLAMM Files\NURP.cpz  
 52 - Small Landscaped Areas 2: 0.006 ac. Normal Clayey Low Density  
 Source Area PSD File: C:\WinSLAMM Files\NURP.cpz

LU# 3 - Commercial: Secondary Total area (ac): 0.317  
 Page 1

TSS Calculations - InputData.txt

1 - Roofs 1: 0.078 ac. Flat Connected Source Area PSD File:  
C:\winSLAMM Files\NURP.cpz  
13 - Paved Parking 1: 0.067 ac. Connected Source Area PSD File:  
C:\winSLAMM Files\NURP.cpz  
25 - Driveways 1: 0.107 ac. Connected Source Area PSD File: C:\winSLAMM  
Files\NURP.cpz  
31 - Sidewalks 1: 0.010 ac. Connected Source Area PSD File: C:\winSLAMM  
Files\NURP.cpz  
51 - Small Landscaped Areas 1: 0.055 ac. Normal Clayey Low Density  
Source Area PSD File: C:\winSLAMM Files\NURP.cpz

LU# 4 - Commercial: Tertiary Total area (ac): 0.135  
13 - Paved Parking 1: 0.108 ac. Connected Source Area PSD File:  
C:\winSLAMM Files\NURP.cpz  
31 - Sidewalks 1: 0.010 ac. Connected Source Area PSD File: C:\winSLAMM  
Files\NURP.cpz  
51 - Small Landscaped Areas 1: 0.017 ac. Normal Clayey Low Density  
Source Area PSD File: C:\winSLAMM Files\NURP.cpz

Control Practice 1: Catchbasin Cleaning CP# 1 (DS) - DS Catchbasins # 1

1. Fraction of area served by catchbasins = 1.00
  2. Number of catchbasins = 1
  3. Average sump depth below catchbasin outlet invert (feet) = 3
  4. Depth of sediment in catchbasin sump at beginning of study period (ft)
- = 0
5. Typical outlet pipe diameter (ft) = 1
  6. Typical outlet pipe Mannings n = 0.012
  7. Typical outlet pipe slope (ft/ft) = 0.01
  8. Typical catchbasin sump surface area (square feet) = 390
  9. Total catchbasin depth (feet) = 8
  10. Inflow hydrograph peak to average flow ratio = 3.8
  11. Leakage rate through sump bottom (in/hr) = 0
  12. Catchbasin Critical Particle Size File Name: Not needed - calculated  
by program

TSS Calculations - Output Summary.txt

SLAMM for windows Version 10.3.4  
 (c) Copyright Robert Pitt and John Voorhees 2012  
 All Rights Reserved

Data file name: I:\2018\188469\Civil\SWMP\Modeling\Slamm\TSS Calculations.mdb  
 Data file description:  
 Rain file name: C:\winSLAMM Files\Rain Files\wisReg - Madison WI 1981.RAN  
 Particulate Solids Concentration file name: C:\winSLAMM Files\v10.1 WI\_AVG01.pscx  
 Runoff Coefficient file name: C:\winSLAMM Files\WI\_SL06 Dec06.rsvx  
 Residential Street Delivery file name: C:\winSLAMM Files\WI\_Res and Other Urban Dec06.std  
 Institutional Street Delivery file name: C:\winSLAMM Files\WI\_Com Inst Indust Dec06.std  
 Commercial Street Delivery file name: C:\winSLAMM Files\WI\_Com Inst Indust Dec06.std  
 Industrial Street Delivery file name: C:\winSLAMM Files\WI\_Com Inst Indust Dec06.std  
 Other Urban Street Delivery file name: C:\winSLAMM Files\WI\_Res and Other Urban Dec06.std  
 Freeway Street Delivery file name: C:\winSLAMM Files\Freeway Dec06.std  
 Pollutant Relative Concentration file name: C:\winSLAMM Files\WI\_GEO03.ppdx  
 Start of Winter Season: 12/02 End of Winter Season: 03/12  
 Model Run Start Date: 01/01/81 Model Run End Date: 12/31/81  
 Date of run: 04-06-2018 Time of run: 10:43:12  
 Total Area Modeled (acres): 1.133  
 Years in Model Run: 1.00

Particulate	Percent	Runoff	Percent	Particulate
Solids	Particulate	Volume	Runoff	Solids
Yield	Solids	(cu ft)	Volume	Conc.
(lbs)	Reduction		Reduction	(mg/L)
Total of all Land Uses without Controls:		56938	-	132.3
470.1	-			
Outfall Total with Controls:		56937	0.00%	78.65
279.6	40.52%			
Annualized Total After Outfall Controls:		57093		
280.3				

---

---

# **APPENDIX 7**

## **STORM SEWER SIZING CALCULATIONS**

### **STORM SEWER SYSTEM CALCULATIONS**



STORM SEWER SIZING CALCULATIONS - 10 YEAR STORM

PIPE	Pipe Run		Manhole Size (in.)	Length (ft.)	Pipe Diameter (inches)	Slope (%)	Pipe Material	Mannings (n)	Pipe Area (sq. ft.)	Hydraulic Radius (ft.)	DA	Drainage Areas			Runoff Coef. C	Upstream End (Y/N)	Area x C		Time of Conc.		Rainfall Intensity (in/hr)	Design Storm Event	Total Runoff (cfs)	Design Capacity (cfs)	Percent Full (%)	Velocity Full (ft/sec)	Downstream I.E. (ft.)	Upstream I.E. (ft.)	Upstream T/P Elev. (ft.)	Pipe Cover (ft.)	Upstream Rim Elev. (ft.)	Upstream HGL Cover (ft)	Comments
	From	To										Imp. (acres)	Perv. (acres)	Total (acres)			Increment	Total	To Structure (min.)	Pipe (min.)													
P-1	STO INL-1	STO INL-2	2x3	23	10	0.25	PVC	0.010	0.55	0.21	P-1	0.155	0.166	0.321	0.59	Y	0.19	0.19	6.0	0.15	6.68	10	1.26	1.43	88.5%	2.62	927.88	927.94	928.85	1.92	930.77		
P-2	STO INL-2	STO MH 1	2x3	20	12	0.40	PVC	0.010	0.79	0.25	INL 2	0.092	0.024	0.116	0.80	N	0.09	0.28	6.1	0.09	6.68	10	1.89	2.94	64.3%	3.74	927.70	927.78	928.86	1.19	930.05		
P-3	STO MH 1	WQ Chamber	36	137	12	0.98	PVC	0.010	0.79	0.25					N	0.00	0.28	6.2	0.39	6.68	10	1.89	4.61	41.0%	5.87	926.25	927.60	928.68	3.27	931.95			
P-4	STO INL-3	WQ Chamber	2x3	19	6	5.00	PVC	0.010	0.20	0.13	INL 3	0.079	0.011	0.090	0.86	Y	0.08	0.08	6.0	0.04	6.68	10	0.52	1.64	31.9%	8.33	928.75	929.70	930.28	3.27	933.55		
P-5	STO INL-4	WQ Chamber	2x3	15	6	5.00	PVC	0.010	0.20	0.13	INL 4	0.098	0.024	0.122	0.81	Y	0.10	0.10	6.0	0.03	6.68	10	0.66	1.64	40.4%	8.33	928.75	929.50	930.08	3.96	934.04		
P-8	RD	STO INL-6	-	37	6	5.00	PVC	0.010	0.20	0.13	RD	0.000	0.090	0.090	0.25	Y	0.02	0.02	6.0	0.07	6.68	10	0.15	1.64	9.2%	8.33	931.05	932.90	933.48	3.72	937.20		
P-7	STO INL-6	STO INL-5	2x3	10	6	5.00	PVC	0.010	0.20	0.13					N	0.00	0.02	6.0	0.02	6.68	10	0.15	1.64	9.2%	8.33	930.45	930.95	931.53	2.49	934.02			
P-6	STO INL-5	WQ Chamber	2x3	32	6	5.00	PVC	0.010	0.20	0.13	INL 5	0.153	0.029	0.182	0.84	N	0.15	0.18	6.0	0.06	6.68	10	1.17	1.64	71.7%	8.33	928.75	930.35	930.93	3.50	934.43		
P-9	WQ Chamber	STO MH 2	-	8	12	1.00	PVC	0.010	0.79	0.25	HYDROCAD MODEL															926.17	926.25	927.33	7.27	934.60			

# **APPENDIX 7**

## **USLE INFORMATION**



# Soil Loss & Sediment Discharge Calculation Tool

for use on Construction Sites in the State of Wisconsin

WDNR Official Version 1.0 (05-15-2015)



YEAR 1

Developer: Summit Credit Union

Project: Summit Credit Union - Waukesha Branch

Date: 4/6/2018

County: Waukesha

Version 1.0

Activity	Begin Date	End Date	Period % R	Annual R Factor	Sub Soil Texture	Soil Erodibility K Factor	Slope (%)	Slope Length (feet)	LS Factor	Land Cover C Factor	Soil loss A (tons/acre)	Sediment Control Practice	Sediment Discharge (tons/acre)
Bare Ground	4/29/2019	5/10/2019	3.6%	130	Clay	0.32	40.0%	32	8.20	1.00	12.2	Silt Fence	4.3
Mulch or Erosion Mat	5/10/2019	10/15/2019	81.8%	130	Clay	0.32	40.0%	95	14.13	0.20	96.2	Sediment Basin	0.0
End	10/15/2019	----	----	----	-----	----			----	----	----		0.0
		----	----	----	-----	----			----	----	----		0.0
		----	----	----	-----	----			----	----	----		0.0
		----	----	----	-----	----			----	----	----		0.0
		----	----	----	-----	----			----	----	----		0.0
<b>TOTAL</b>											<b>108.4</b>	<b>TOTAL</b>	<b>4.3</b>

SLOPE > 20% USE PRESCRIPTIVE COMPLIANCE

**Notes:**

See Help Page for further descriptions of variables and items in drop-down boxes.  
 The last land disturbing activity on each sheet must be 'End'. This is either 12 months from the start of construction or final stabilization.  
 For periods of construction that exceed 12 months, please demonstrate that 5 tons/acre/year is not exceeded in any given 12 month period.

NOTE: THIS TOOL ONLY ADDRESSED SOIL EROSION DUE TO SHEET FLOW. MEASURES TO CONTROL CHANNEL EROSION MAY ALSO BE REQUIRED TO MEET SEDIMENT DISCHARGE REQUIREMENTS.

**Recommended Permanent Seeding Dates:**

4/1-5/15 and 8/7-8/29 Turf, introduced grasses and legumes  
 Thaw-6/30 Native Grasses, forbs, and legumes

Designed By:	CLH
Date	4/6/2018

## **APPENDIX 9**

### **MAINTAINENCE AGREEMENT**

**AGREEMENT FOR MAINTENANCE OF STORMWATER MANAGEMENT MEASURES**

**RECITALS:**

- A. Summit Credit Union is(are) the owner(s) of property in the City of Waukesha County of Waukesha, State of Wisconsin, more particularly described on Exhibit A attached hereto ("Property").
- B. The County requires Owner to record this Agreement regarding maintenance of stormwater management measures to be located on the Property. Owner agrees to maintain the stormwater management measures and to grant to the County the rights set forth below.

NOW, THEREFORE, in consideration of the agreement herein and other good and valuable consideration, the receipt and sufficiency of which are hereby acknowledged, the owner agrees as follows:

- 1. Maintenance. Owner and its successors and assigns shall be responsible to repair and maintain the stormwater management measures located on the Property in good condition and in working order and such that the measures comply with approved plans on file with Waukesha County. Said maintenance shall be at the Owner's sole cost and expense. Owner will conduct such

maintenance or repair work in accordance with all applicable laws, codes, regulations, and similar requirements. Specific maintenance task are more particularly described on Exhibit A.

- 2. Easement to County. If Owner fails to maintain the stormwater management measures as required in Section 1, then County shall have the right, after providing Owner with written notice of the maintenance issue ("Maintenance Notice") and thirty (30) days to comply with the County's maintenance request, to enter the Property in order to conduct the maintenance specified in the Maintenance Notice. County will conduct such maintenance work in accordance with all applicable laws, codes, regulations, and similar requirements and will not unreasonably interfere with Owner's use of the Property. All costs and expenses incurred by the County in conducting such maintenance may be charged to the owner of the Property by placing the amount on the tax roll for the Property as a special assessment in accordance with Section 66.0703, Wis. Stats. and applicable portions of the Waukesha County Ordinances.

- 3. Term/Termination. The term of this Agreement shall commence on the date that this Agreement is recorded with the Register of Deeds Office for Waukesha County, Wisconsin, and except as otherwise herein specifically provided, shall continue in perpetuity. Notwithstanding the foregoing, this Agreement may be terminated by recording with the Register of Deeds Office for Waukesha County, Wisconsin, a written instrument of termination signed by the County and all of the then-owners of the Property.

4. Miscellaneous.

- (a) Notices. Any notice, request or demand required or permitted under this Agreement shall be in writing and shall be deemed given when personally served or three (3) days after the same has been deposited with the United States Post Office, registered or certified mail, return receipt requested, postage prepaid and addressed as follows:

If to Owner: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

This space is reserved for recording data

Return to:  
Waukesha County Register of Deeds  
515 W Moreland Blvd Rm AC110  
Waukesha, Wisconsin 53188

Parcel Number(s):

WAKC113015001

If to County: Waukesha County Land & Water Resources  
515 W Moreland Blvd Rm AC110  
Waukesha, Wisconsin 53188

Any party may change its address for the receipt of notice by written notice to the other.

- (b) Governing Law. This Agreement shall be governed and construed in accordance with the laws of the State of Wisconsin.
- (c) Amendments or Further Agreements to be in Writing. This Agreement may not be modified in whole or in part unless such agreement is in writing and signed by all parties bound hereby.
- (d) Covenants Running with the Land. All of the easements, restrictions, covenants and agreements set forth in this Agreement are intended to be and shall be construed as covenants running with the land, binding upon, inuring to the benefit of, and enforceable by the parties hereto and their respective successors and assigns.
- (e) Partial Invalidity. If any provisions, or portions thereof, of this Agreement or the application thereof to any person or circumstance shall, to any extent, be invalid or unenforceable, the remainder of this Agreement, or the application of such provision, or portion thereof, to any other persons or circumstances shall not be affected thereby and each provision of this Agreement shall be valid and enforceable to the fullest extent permitted by law.

X \_\_\_\_\_  
Land Records Staff Signature

\_\_\_\_\_  
Print or type name

**State of WI**, County of \_\_\_\_\_; Subscribed and sworn before me on \_\_\_\_\_ by the above named person(s).

\_\_\_\_\_  
Notary Public

Print or type name: \_\_\_\_\_

My Commission Expires: \_\_\_\_\_

---

X \_\_\_\_\_  
Owner Signature

\_\_\_\_\_  
Print or type name

**State of WI**, County of \_\_\_\_\_; Subscribed and sworn before me on \_\_\_\_\_ by the above named person(s).

\_\_\_\_\_  
Notary Public

Print or type name: \_\_\_\_\_

My Commission Expires: \_\_\_\_\_

**DRAFTED BY:** \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

## **EXHIBIT A**

Lot 1 of CSM #10663

## **EXHIBIT B**

### Maintenance Provisions:

#### Storm Sewer System

The owner shall maintain all components of the storm sewer system located onsite. Installation and maintenance shall be in accordance with the manufacturer's guidelines. At a minimum the storm sewer system shall be inspected annually and cleaned as needed to maintain functionality and design capacity. The sumps located in the storm sewer system shall be inspected a minimum of three (3) times per year. Sediment should be removed from the sumps when sediment depth is greater than 1.5'. Owner shall maintain records of inspections, cleaning and replacement of the system or components of the system all in accordance with City of Waukesha Ordinances.

#### Underground Water Quality System

The owner shall install and maintain an underground storage chamber system as distributed by StormTech or approved equivalent. Said system is installed for detention and infiltration purposes to infiltrate roof water runoff. Installation and maintenance shall be in accordance with the manufacturer's guidelines. Inspect the StormTech system immediately following construction completion. Inspection of the underground storage structure shall be done a minimum of two (2) times per year or as needed until an understanding of the site characteristics is developed. More specifically, the StormTech rows shall be visually inspected via the inspection port and is to be JetVac cleaned any time sediment has accumulated to an average depth exceeding three (3) inches. Owner shall maintain records of inspections and cleaning of the rows in accordance with the City of Waukesha Ordinances.

Detailed information regarding installation and maintenance can be found on the Internet at [www.stormtech.com](http://www.stormtech.com) or by calling StormTech at 888-892-2694.