ONSITE CIVIL ENGINEERING INFRASTUCTURE PLANS


901 NORTHVIEW ROAD

WAUKESHA, WISCONSIN

PLANS PREPARED FOR

PREMIER DESIGN + BUILD GROUP

1000 W. IRVING PARK ROAD, STE 200 **ITASCA**, **IL** 60143



ABBREVIATIONS BASE LINE POINT OF VERTICAL INTERSECTION LONG CHORD OF CURVE **RADIUS CURB AND GUTTER** RIGHT-OF-WAY CATCH BASIN SANITARY SEWER CENTERLINE STORM SEWER **DEGREE OF CURVE** TANGENCY OF CURVE **EDGE OF PAVEMENT** TOP OF BANK FINISHED FLOOR TOP OF CURB FINISHED GRADE TOP OF FOUNDATION FLOW LINE TOP OF PIPE **FLOODPLAIN**

TOP OF SIDEWALK

INTERSECTION ANGLE

TOP OF WALK

WATER MAIN

BENCHMARKS BM 1: "OPEN" ON HYDRANT FLANGE ELEVATION= 131.83 Waukesha County Airport BM 2: "OPEN" ON HYDRANT FLANGE **ELEVATION= 134.6** Waukesha County **BM 3: NW UPPER HYDRANT FLANGE BOLT** Expo Center **ELEVATION= 134.56** BM 4: NORTH EDGE OF CONC. LIGHT BASE Aldoro Dr **ELEVATION=141.19** VERTICAL DATUM: CITY OF WAUKESHA DATUM=NGVD DATUM -780.55 HORIZONTAL DATUM: SOUTH LINE OF CSM NO. 2913 ASSUMED TO BEAR NORTH 00°00'00" EAST

PROJECT TEAM CONTACTS CIVIL ENGINEER: SURVEYOR: ADAM ARTZ, P.E. PINNACLE ENGINEERING GROUP DON CHAPUT, R.L.S 15850 BLUEMOUND ROAD, SUITE 210 **CHAPUT LAND SURVEYS** BROOKFIELD, WI 53005 234 W. FLORDIA STREET (262) 754-8888 MILWAUKEE, WI 53204 (414) 224-8068 PINNACLE ENGINEERING GROUP LANDSCAPING: 15850 BLUEMOUND ROAD, SUITE 210 DAVE KMETZ BROOKFIELD, WI 53005 REESMANS SERVICE CORPORATION (262) 754-8888 28815 BUSHNELL ROAD BURLINGTON, WI 53105 **APPLICANT:** (262) 342-1425 ALAN ZOCHER PREMIER DESIGN + BUILD GROUP 1000 W. IRVING PARK ROAD, STE 200 ITASCA, IL 60143 **ARCHITECT:** WERNER BRISKE **PARTNERS IN DESIGN**

600 FIFTY SECOND STREET STE 220

KENOSHA, WI 53140

(262) 652-2800

INDEX OF SHEETS COVER SHEET C-1 C-2 **EXISTING CONDITIONS DEMOLITION PLAN** SITE DIMENSIONAL AND PAVING PLAN **GRADING PLAN** UTILITY PLAN SITE STABILIZATION PLAN **CONSTRUCTION DETAILS** C-8 - C-10

GENERAL NOTES

- FOR THE PROPER EXECUTION OF WORK. ALL WORKS CONTAINED WITHIN THE PLANS AND SPECIFICATIONS SHALL BE COMPLETED IN ACCORDANCE WITH ALL REQUIREMENTS FROM LOCAL, STATE, FEDERAL OR OTHER GOVERNING AGENCY'S LAWS, REGULATIONS, JURISDICTIONAL ORDINANCES/CODES/RULES/ETC., AND THE OWNER'S DIRECTION
- THE CONTRACTOR IS RESPONSIBLE TO REVIEW AND UNDERSTAND ALL COMPONENTS OF THE PLANS AND SPECIFICATIONS INCLUDING FIELD VERIFYING SOIL CONDITIONS, PRIOR TO SUBMISSION OF A BID PROPOSA
- THE CONTRACTOR SHALL PROMPTLY REPORT ANY ERRORS OR AMBIGUITIES LEARNED AS PART OF THEIR REVIEW OF PLANS
- QUESTIONS/CLARIFICATIONS WILL BE INTERPRETED BY ENGINEER/OWNER PRIOR TO THE AWARD OF CONTRACT, ENGINEER/OWNER WILL SUBMIT OFFICIAL RESPONSES IN WRITING. INTERPRETATIONS PRESENTED IN OFFICIAL RESPONSES SHALL BE BINDING ON ALL
- ACCOUNT FOR CONDITIONS THAT AFFECT OR MAY AFFECT CONSTRUCTION INCLUDING BUT NOT LIMITED TO LIMITATIONS OF WORK ACCESS, SPACE LIMITATIONS, OVERHEAD OBSTRUCTIONS, TRAFFIC PATTERNS, LOCAL REQUIREMENTS, ADJACENT
- COMMENCEMENT OF CONSTRUCTION SHALL EXPLICITLY CONFIRM THAT THE CONTRACTOR HAS REVIEWED THE PLANS AND SPECIFICATIONS IN ENTIRETY AND CERTIFIES THAT THEIR SUBMITTED BID PROPOSAL CONTAINS PROVISIONS TO COMPLETE THE PROJECT, WITH THE EXCEPTION OF UNFORESEEN FIELD CONDITIONS; ALL APPLICABLE PERMITS HAVE BEEN OBTAINED; AND CONTRACTOR UNDERSTANDS ALL OF THE REQUIREMENTS OF THE PROJECT.
- SHOULD ANY DISCREPANCIES OR CONFLICTS IN THE PLANS OR SPECIFICATIONS BE DISCOVERED AFTER THE AWARD OF CONTRACT ENGINEER SHALL BE NOTIFIED IN WRITING IMMEDIATELY AND CONSTRUCTION OF ITEMS AFFECTED BY THI DISCREPANCIES/CONFLICTS SHALL NOT COMMENCE, OR CONTINUE, UNTIL A WRITTEN RESPONSE FROM ENGINEER/OWNER IS DISTRIBUTED. IN THE EVENT OF A CONFLICT BETWEEN REFERENCED CODES, STANDARDS, SPECIFICATIONS AND PLANS, THE ONE ESTABLISHING THE MOST STRINGENT REQUIREMENTS SHALL BE FOLLOWED
- THE CONTRACTOR SHALL, AT ITS OWN EXPENSE, OBTAIN ALL NECESSARY PERMITS AND LICENSES TO COMPLETE THE PROJECT. OBTAINING PERMITS, OR DELAYS, IS NOT CAUSE FOR DELAY OF THE CONTRACT OR SCHEDULE. CONTRACTOR SHALL COMPLY WITH
- 10. THE CONTRACTOR SHALL NOTIFY ALL INTERESTED GOVERNING AGENCIES, UTILITY COMPANIES AFFECTED BY THIS CONSTRUCTION PROJECT, AND DIGGER'S HOTLINE IN ADVANCE OF CONSTRUCTION TO COMPLY WITH ALL JURISDICTIONAL ORDINANCES/CODES/RULES/ETC., PERMIT STIPULATIONS, AND OTHER APPLICABLE STANDARDS.
- 1. SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE TO INITIATE, INSTITUTE, ENFORCE, MAINTAIN, AND SUPERVISE ALL SAFETY PRECAUTIONS AND JOB SITE SAFETY PROGRAMS IN CONNECTION WITH THE
- 12. CONTRACTOR SHALL KEEP THE JOBSITE CLEAN AND ORDERLY AT ALL TIMES. ALL LOCATIONS OF THE SITE SHALL BE KEPT IN A
- 13. THE CONTRACTOR SHALL INDEMNIFY THE OWNER, ENGINEER, AND THEIR AGENTS FROM ALL LIABILITY INVOLVED WITH THE CONSTRUCTION, INSTALLATION, AND TESTING OF THE WORK ON THIS PROJECT.
- 14. PRIOR TO CONSTRUCTION A PRE-CONSTRUCTION MEETING MUST BE HELD AT THE CITY OFFICES. THE PRE-CONSTRUCTION MEETING SHALL BE SCHEDULED AND MODERATED BY THE DESIGN ENGINEER OF RECORD.

FOR REVIEW



Milwaukee Area (414) 259-1181 Hearing Impaired TDD (800) 542-2289 www.DiggersHotline.com

EXPIRATION DATE: JULY 31, 2016

PINNACLE ENGINEERING GROUP, LLC

ENGINEER'S LIMITATION

PINNACLE ENGINEERING GROUP, LLC AND THEIR CONSULTANTS DO NOT WARRANT OR GUARANTEE THE ACCURACY AND COMPLETENESS OF THE DELIVERABLES HEREIN BEYOND A REASONABLE DILIGENCE. IF ANY MISTAKES, OMISSIONS, OR DISCREPANCIES ARE FOUND TO EXIST WITHIN THE DELIVERABLES, THE ENGINEER SHALL BE PROMPTLY NOTIFIED PRIOR TO BID SO THAT HE MAY HAVE THE OPPORTUNIT TO TAKE WHATEVER STEPS NECESSARY TO RESOLVE THEM. FAILURE TO PROMPTLY NOTIFY THE ENGINEER OF SUCH CONDITIONS SHALL ABSOLVE THE ENGINEER FROM ANY RESPONSIBILITY FOR THE CONSEQUENCES OF SUCH FAILURE, ACTIONS TAKEN WITHOUT THE KNOWLEDGE AND CONSENT TO THE ENGINEER, OR IN CONTRADICTION TO THE ENGINEER'S DELIVERABLES OR RECOMMENDATIONS, SHALL BECOME THE RESPONSIBILITY NOT OF THE ENGINEER BUT OF THE PARTIES RESPONSIBLE FOR TAKING SUCH ACTION.

FURTHERMORE, PINNACLE ENGINEERING GROUP, LLC IS NOT RESPONSIBLE FOR CONSTRUCTION SAFETY OR THE MEANS AND METHODS OF



EASEMENT LINE

FRAME

INVERT

MANHOLE

FLOODWAY

HIGH WATER LEVEL

LENGTH OF CURVE

NORMAL WATER LEVEL


POINT OF CURVATURE


PLAN I DESIGN I DELIVER www.pinnacle-engr.com 15850 W. BLUEMOUND ROAD **PINNACLE** ENGINEERING GROUP


901 NORTHVIEW ROAD WAUKESHA, WI


COVER SHEET


REVISIONS












WAUKESHA, WI

15850 W. BLUEMOUND ROAD

PINNACLE ENGINEERING GROUP

UTILITY PLAN



LEGEND — · · · — NORMAL WATER LEVEL (NWL) SANITARY SEWER MANHOLE DIRECTION OF SURFACE FLOW STORM SEWER MANHOLE STORM STORM CATCH BASIN (ROUND CASTING) STORM SEWER CATCH BASIN (RECTANGULAR CASTING) ->>>>> DIVERSION SWALE PRECAST FLARED END SECTION OVERFLOW RELIEF ROUTING **INLET PROTECTION** CONSTRUCTION ENTRANCE PROPOSED SPOT ELEVATION HYDROSEED (PER MANUFACTURER SPECIFICATIONS) EROSION CONTROL BLANKET (NORTH AMERICAN GREEN S75 OR EQUAL) - · · - HIGH WATER LEVEL (HWI)

CONSTRUCTION SITE SEQUENCING

- INSTALL PERIMETER SILT FENCE, INLET PROTECTION AND TEMPORARY CONSTRUCTION
- 2. STRIP AND STOCKPILE TOPSOIL, INSTALL SILT FENCE AROUND PERIMETER OF STOCKPILE. 3. CONDUCT ROUGH GRADING EFFORTS AND INSTALL CHECK DAMS AND SEDIMENT TRAPS/BASINS AS NEEDED.
- . INSTALL UTILITY PIPING AND STRUCTURES, IMMEDIATELY INSTALL INLET PROTECTION.
- COMPLETE FINAL GRADING, INSTALLATION OF GRAVEL BASE COURSES, PLACEMENT OF CURBS, PAVEMENTS, WALKS, ETC.
- PLACE TOPSOIL AND IMMEDIATELY STABILIZE DISTURBED AREAS WITH EROSION CONTROLS.
- EROSION CONTROL MEASURES SHALL BE REMOVED ONLY AFTER SITE CONSTRUCTION IS COMPLETE WITH ALL SOIL SURFACES HAVING AN ESTABLISHED VEGETATIVE COVER.
- CONTRACTOR MAY MODIFY SEQUENCING AFTER ITEM 1 AS NEEDED TO COMPLETE CONSTRUCTION IF EROSION CONTROLS ARE MAINTAINED IN ACCORDANCE WITH THE CONSTRUCTION SITE EROSION CONTROL REQUIREMENTS.

GENERAL EROSION AND SEDIMENT CONTROL NOTES


- ALL CONSTRUCTION SHALL ADHERE TO THE REQUIREMENTS SET FORTH IN EPA'S NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) STORMWATER GENERAL PERMIT ("WPDES" PERMIT NO. WI-S067831-4) FOR CONSTRUCTION SITE LAND DISTURBANCE ACTIVITIES. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL TECHNICAL STANDARDS AND PROVISIONS IN EFFECT AT THE TIME OF CONSTRUCTION. THESE PROCEDURES AND STANDARDS SHALL BE REFERRED TO AS BEST MANAGEMENT PRACTICES (BMP'S). IT IS THE RESPONSIBILITY OF ALL CONTRACTORS ASSOCIATED WITH THE PROJECT TO OBTAIN A COPY OF, AND UNDERSTAND, THE BMP'S PRIOR TO THE START OF CONSTRUCTION ACTIVITIES.
- THE EROSION CONTROL MEASURES INDICATED ON THE PLANS ARE THE MINIMUM REQUIREMENTS. ADDITIONAL CONTROL MEASURES AS DIRECTED BY OWNER/ENGINEER
- MODIFICATIONS TO THE APPROVED SWPPP IN ORDER TO MEET UNFORESEEN FIELD CONDITIONS ARE ALLOWED IF MODIFICATIONS CONFORM TO BMP'S. ALL MODIFICATIONS MUST BE APPROVED BY OWNER/ENGINEER/GOVERNING AGENCY PRIOR TO DEVIATION OF THE APPROVED PLAN.
- INSTALL PERIMETER EROSION CONTROL MEASURES (SUCH AS CONSTRUCTION ENTRANCES, SILT FENCE AND EXISTING INLET PROTECTION) PRIOR TO ANY SITE WORK, INCLUDING GRADING OR DISTURBANCE OF EXISTING SURFACE COVER, AS SHOWN ON PLAN IN ORDER TO PROTECT ADJACENT PROPERTIES/STORM SEWER SYSTEMS FROM
- WITH THE PROPER AUTHORITIES. PROVIDE NECESSARY FEES AND OBTAIN ALL REQUIRED APPROVALS OR PERMITS. ADDITIONAL CONSTRUCTION ENTRANCES OTHER THAN AS SHOWN ON THE PLANS MUST BE APPROVED BY THE APPLICABLE GOVERNING
- PAVED SURFACES ADJACENT TO CONSTRUCTION ENTRANCES SHALL BE SWEPT AND/OR SCRAPED TO REMOVE ACCUMULATED SOIL, DIRT AND/OR DUST IMMEDIATELY AND AS
- ALL EXISTING STORM SEWER FACILITIES THAT WILL COLLECT RUNOFF FROM DISTURBED AREAS SHALL BE PROTECTED TO TO PREVENT SEDIMENT DEPOSITION AT THE INLET OF ALL INSTALLED STORM SEWER AND SILT FENCE SHALL BE IMMEDIATELY FITTED AT ALL INSTALLED CULVERT INLETS. ALL INLETS, STRUCTURES, PIPES, AND SWALES SHALL BE KEPT CLEAN AND FREE OF SEDIMENTATION AND DEBRIS.
- EROSION CONTROL FOR UTILITY CONSTRUCTION (STORM SEWER, WATER MAIN, ETC.) OUTSIDE OF THE PERIMETER CONTROLS SHALL INCORPORATE THE FOLLOWING:
 - PLACE EXCAVATED TRENCH MATERIAL ON THE HIGH SIDE OF THE TRENCH.
 - BACKFILL, COMPACT AND STABILIZE THE TRENCH IMMEDIATELY AFTER PIPE
 - DISCHARGE TRENCH WATER INTO A SEDIMENTATION BASIN OR FILTERING TANK IN ACCORDANCE WITH BMP'S PRIOR TO RELEASE INTO STORM SEWER OR
- AT A MINIMUM, SEDIMENT BASINS AND NECESSARY TEMPORARY DRAINAGE PROVISIONS SHALL BE CONSTRUCTED AND OPERATIONAL BEFORE BEGINNING OF SIGNIFICANT MASS GRADING OPERATIONS TO PREVENT OFFSITE DISCHARGE OF UNTREATED RUNOFF.

- 10. ALL WATERCOURSES AND WETLANDS SHALL BE PROTECTED WITH SILT FENCE TO PREVENT ANY DIRECT DISCHARGE FROM DISTURBED SOILS.
- 11. ALL TEMPORARY AND PERMANENT EROSION CONTROL MEASURES MUST BE MAINTAINED AND REPAIRED AS NEEDED. THE GENERAL CONTRACTOR WILL BE RESPONSIBLE FOR INSPECTION AND REPAIR DURING CONSTRUCTION. THE OWNER WILL BE RESPONSIBLE IF EROSION CONTROL IS REQUIRED AFTER THE CONTRACTOR HAS COMPLETED THE PROJECT.
- 12. TOPSOIL STOCKPILES SHALL HAVE A BERM OR TRENCH AROUND THE CIRCUMFERENCE AND PERIMETER SILT FENCE TO CONTROL SILT. IF TOPSOIL STOCKPILE REMAINS UNDISTURBED FOR MORE THAN SEVEN (7) DAYS, TEMPORARY SEEDING AND STABILIZATION IS REQUIRED.
- 13. EROSION CONTROL MEASURES TEMPORARILY REMOVED FOR UNAVOIDABLE CONSTRUCTION ACTIVITIES SHALL BE IN WORKING ORDER IMMEDIATELY FOLLOWING COMPLETION OF SUCH ACTIVITIES OR PRIOR TO THE COMPLETION OF EACH WORK DAY, WHICH EVER OCCURS FIRST.
- 14. MAINTAIN SOIL EROSION CONTROL DEVICES THROUGH THE DURATION OF THIS PROJECT. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN THIRTY (30) DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED. DISTURBANCES
- 15. PUMPS MAY BE USED AS BYPASS DEVICES. IN NO CASE SHALL PUMPED WATER BE DIVERTED OUTSIDE THE PROJECT LIMITS. PUMP DISCHARGE SHALL BE DIRECTED INTO AN APPROVED FILTER BAG OR APPROVED SETTLING DEVICE.
- 16. GRADING EFFORTS SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE EROSION. EROSION AND SEDIMENT CONTROL MEASURES SHALL CONSIDER THE TIME OF YEAR, SITE CONDITIONS, AND THE USE OF TEMPORARY OR PERMANENT MEASURES. ALL DISTURBED AREAS THAT WILL NOT BE WORKED FOR A PERIOD OF FOURTEEN (14) DAYS REQUIRE TEMPORARY SEEDING FOR EROSION CONTROL. SEEDING FOR EROSION CONTROL SHALL BE IN ACCORDANCE WITH TECHNICAL STANDARDS.
- 17. ALL DISTURBED SLOPES EXCEEDING 4:1, SHALL BE STABILIZED WITH NORTH CHANNELS SHALL BE STABILIZED WITH NORTH AMERICAN GREEN C125BN (OR APPROVED EQUAL) OR APPLICATION OF AN APPROVED POLYMER SOIL STABILIZATION TREATMENT OR A COMBINATION THEREOF, AS REQUIRED. EROSION MATTING AND/OR NETTING USED ONSITE SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S
- 18. DURING PERIODS OF EXTENDED DRY WEATHER, THE CONTRACTOR SHALL KEEP A OTHERWISE BECOME AIRBORNE.THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING WIND EROSION (DUST) DURING CONSTRUCTION AT HIS/HER EXPENSE.
- 19. DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION SHALL BE VISUALLY INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM ON A DAILY BASIS.
- INSPECT DISTURBED AREAS OF THE CONSTRUCTION SITE THAT HAVE NOT BEEN FINALLY STABILIZED AND EROSION AND SEDIMENT CONTROLS WITHIN 24 HOURS OF ALL 0.5-INCH, OR MORE, PRECIPITATION EVENTS WITH A MINIMUM INSPECTION INTERVAL OF ONCE EVERY SEVEN (7) CALENDAR DAYS IN THE ABSENCE OF A QUALIFYING RAIN OR SNOWFALL EVENT. REPORTING SHALL BE IN ACCORDANCE WITH OF THE GENERAL PERMIT. CONTRACTOR SHALL IMMEDIATELY ARRANGE TO HAVE ANY DEFICIENT ITEMS REVEALED DURING INSPECTIONS REPAIRED/REPLACED.
- 21. SEE ADDITIONAL DETAILS AND NOTES ON SITE STABILIZATION AND CONSTRUCTION
- 22. CONTRACTOR SHALL SURFACE ROUGH THE HILLSIDE SLOPES WITH HEAVY EQUIPMENT

GRAPHICAL SCALE (FEET)

REVISIONS






1. ALL TRACKING PAD MATERIALS AND INSTALLATION SHALL BE IN CONFORMANCE WITH WI DNR TECHNICAL STANDARD 1057.

- 3. THE AGGREGATE FOR TRACKING PADS SHALL BE 3 TO 6 INCH CLEAR OR WASHED STONE. ALL MATERIALS TO BE RETAINED ON
- 4. THE AGGREGATE SHALL BE PLACED IN A LAYER AT LEAST 12-INCHES THICK. ON SITES WHERE SATURATED CONDITIONS ARE EXPECTED DURING THE LIFE OF THE PAD, THE PAD SHALL BE UNDERLAIN WITH GEOTEXTILE FABRIC WHICH MEETS MATERIAL
- SPECIFICATION 592 GEOTEXTILE, TABLE 1 OR 2, CLASS I, II OR IV, TO PREVENT MIGRATION OF UNDERLYING SOILS INTO THE 5. THE TRACKING PAD SHALL BE THE FULL WIDTH OF THE EGRESS POINT. MINIMUM WIDTH IS 14 FEET FOR ONE-WAY TRAFFIC AND 20 FEET FOR TWO-WAY TRAFFIC, WITH AN ADDITIONAL INCREASE OF 4 FEET FOR TRAILER TRAFFIC. THE TRACKING PAD
- SHALL BE A MINIMUM 50-FEET LONG.
- 6. ANY SEDIMENT TRACKED ONTO A PUBLIC OR PRIVATE ROAD SHOULD BE REMOVED BY STREET CLEANING, NOT FLUSHING, AT

CONSTRUCTION ENTRANCE

- 7. TRACKING PADS SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24-HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 0.5-INCHES OF RAIN OR MORE DURING A 24-HOUR PERIOD.
- 8. THE TRACKING PAD PERFORMANCE SHALL BE MAINTAINED BY SCRAPING OR TOP-DRESSING WITH ADDITIONAL AGGREGATE.



GEOTEXTILE

DIRECTION

EXPRESS



TYPE "B" & "C" INSTALLATION NOTES

INCHES OF THE GRATE.

FROM ENTERING THE INLET.

TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3

THE CONTRACTOR SHALL DEMONSTRATE A METHOD OF

MAINTENANCE, USING A SEWN FLAP, HAND HOLDS OR OTHER METHODS TO PREVENT ACCUMULATED SEDIMENT

^^^^

44444444

WOOD 2"x4" STAKES -

AND CROSS BRACING

SHALL COMPLETELY

SURROUND INLET TO

INTO THE INLET

GEOTEXTILE FABRIC SHALL

BE SECURED TO THE STAKES

AND CROSS BRACING. FABRIC

PREVENT SEDIMENT LADEN

INLET PROTECTION - TYPE "A"

RUNOFF FROM ENTERING

AND CROSS BRACING

- GRATED INLET

GEOTEXTILE

2' ABOVE

GROUND

FABRIC SHALL BE BURIED

IN TRENCH TO PREVENT

UNDERMINING OF THE

INLET PROTECTION

SILT FENCE

WOOD 2"x4" EXTENDS 10" BEYOND GRATE WIDTH ON BOTH SIDES, LENGTH VARIES,

SECURE TO GRATE WITH WIRE OR

1. GEOTEXTILE FABRIC SHALL MEET THE REQUIREMENTS OF MATERIAL SPECIFICATION

WHEN REMOVING OR MAINTAINING INLET PROTECTION, CARE SHALL BE TAKEN SO

INLET. ANY MATERIAL FALLING INTO THE INLET SHALL BE REMOVED IMMEDIATELY.

(1) FINISHED SIZE, INCLUDING FLAP POCKET WHERE REQUIRED, SHALL EXTEND A MINIMUM

(2) FOR INLET PROTECTION, TYPE "C" (WITH CURB BOX), AN ADDITIONAL 18 INCHES OF

SHALL NOT BLOCK THE ENTIRE HEIGHT OF THE CURB BOX OPENING.


(3) FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2x4.

OF 10 INCHES AROUND THE PERIMETER TO FACILITATE MAINTENANCE OR REMOVAL,

FABRIC IS WRAPPED AROUND THE WOOD AND SECURED WITH STAPLES. THE WOOD

592 GEOTEXTILE TABLE 1 OR 2, CLASS I, WITH AN EOS OF AT LEAST 30 FOR NONWOVEN

THAT THE SEDIMENT TRAPPED ON THE GEOTEXTILE FABRIC DOES NOT FALL INTO THE



SURFACE

GEOTEXTILE FABRIC,

RUNOFF WATER

FLOW ____

BURIED FABRIC

MIN. 6" DEPTH

DIRECTION OF 4.0' 2.0'

TYPE FF

GEOTEXTILE

1. DIVERSION MAY REQUIRE AREAS OF BERM AND OTHER AREAS OF CHANNEL TO PROVIDE SUFFICIENT PERIMETER

SURFACE

- 2. DIVERSION BERM VERSUS CHANNEL PRACTICES SHALL BE SELECTED SUCH TO PREVENT PONDING (E.G. POSITIVE DRAINAGE SHALL BE MAINTAINED). 3. FOR DIVERSIONS THAT ARE TO SERVE LONGER THAN 30 DAYS, THE SIDE SLOPES INCLUDING THE RIDGE, AND THE
- DOWN SLOPE SIDE OF THE DIVERSION SHALL BE STABILIZED AS SOON AS THEY CONSTRUCTED BY EQUIPMENT TRACKING AND TEMPORARY SEEDING. FOR DIVERSIONS SERVING LESS THAN 30 DAYS, THE DOWN SLOPE SIDE OF THE DIVERSION SHALL BE STABILIZED AS SOON AS CONSTRUCTED BY EQUIPMENT TRACKING AND TEMPORARY
- 4. DIVERSIONS SHALL BE PROTECTED FROM DAMAGE BY CONSTRUCTION ACTIVITIES. AT ALL POINTS WHERE DIVERSION BERMS OR CHANNELS WILL BE CROSSED BY CONSTRUCTION EQUIPMENT, THE DIVERSION SHALL BE SHAPED APPROPRIATELY AND/OR TEMPORARY CULVERTS OF ADEQUATE CAPACITY MAYBE ADDED AT CROSSINGS.
- 5. AT MINIMUM, INSTALL ONE DITCH CHECK (SEE DETAIL) FOR EVERY 2 VERTICAL FEET OF DROP.
- 6. DIVERSIONS SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 0.5 INCHES OF RAIN OR MORE DURING A 24 HOUR PERIOD. MAINTENANCE SHALL BE COMPLETED AS SOON AS POSSIBLE WITH CONSIDERATION TO SITE CONDITIONS. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES HALF THE HEIGHT OF THE DIVERSION BERM.

DIVERSION BERM / CHANNEL

CONSISTING OF ANGULAR WELL GRADED STONE OUTLET SEDIMENT TRAP BOTTOM ELEV= SECTION A-A' TOP OF EMBANKMENT SECTION B-B' 1. SEDIMENT TRAP SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH WDNR TECHNICAL STANDARD 1063. 2. SIDE SLOPES SHALL BE STABILIZED AS SOON AS THEY ARE CONSTRUCTED. 3. IF OUTLET BECOMES CLOGGED IT SHALL BE CLEANED TO RESTORE FLOW CAPACITY. 4. THE DEPTH OF THE SEDIMENT TRAP FROM THE BOTTOM OF THE TRAP TO THE INVERT OF THE STONE OUTLET SHALL BE AT LEAST 3 FEET. 5. THE SEDIMENT TRAP SHALL HAVE LENGTH TO WIDTH RATIO OF AT LEAST 2:1. SIDE SLOPES SHALL BE NO STEEPER THAN 2:1. 6. MAINTENANCE SHALL BE COMPLETED AS SOON AS POSSIBLE WITH CONSIDERATION TO SITE CONDITIONS, ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 1 FOOT. 7. FILTER FABRIC SHALL MEET THE REQUIREMENTS OF WDNR TS 1056. SEDIMENT TRAP

LENGTH 3' - 4'

GROUND

GEOTEXTILE FABRIC ONLY

SILT FENCE SHALL BE STAPLED, USING AT

POSTS IN AT LEAST 3 PLACES

I WITH EQUIVALENT OPENING SIZE OF AT LEAST 30 FOR NONWOVEN AND 50 FOR WOVEN.

SHALL NOT BE EXCAVATED WIDER OR DEEPER THAN NECESSARY FOR PROPER INSTALLATION.

5. WOOD POSTS SHALL BE A MINIMUM SIZE OF 1.125-INCHES x 1.125-INCHES OF DRIED OAK OR HICKORY.

4. FOLD MATERIAL TO FIT TRENCH AND BACKFILL AND COMPACT TRENCH WITH EXCAVATED SOIL.

3. SILT FENCE SHALL BE ANCHORED BY SPREADING AT LEAST 8-INCHES OF FABRIC IN A

1. ALL SILT FENCE MATERIALS AND INSTALLATION SHALL BE IN CONFORMANCE WITH WI DNR TECHNICAL STANDARD 1056.

2. GEOTEXTILE FABRIC SHALL MEET THE REQUIREMENTS OF MATERIAL SPECIFICATION 592 GEOTEXTILE TABLE 1 OR 2, CLASS

4-INCH WIDE AND 6-INCH DEEP TRENCH OR 6-INCH DEEP V-TRENCH ON THE UPSLOPE SIDE OF THE FENCE. TRENCHES

7. POST SPACING SHALL BE SELECTED BASED ON GEOTEXTILE FABRIC (8-FEET FOR WOVEN AND 3-FEET FOR NON-WOVEN).

LEAST 0.5-INCH STAPLES, TO THE UPSLOPE SIDE OF THE

6. SILT FENCE TO EXTEND ABOVE THE TOP OF PIPE, WHERE APPLICABLE.

BACKFILL AND -

COMPACT TRENCH

WITH EXCAVATED SOIL

20" MIN. DEPTH IN


PLAN I DESIGN I DELIVER www.pinnacle-engr.com PINNACLE ENGINEERING GROUP

901 NORTHVIEW ROAD WAUKESHA, WI

REVISIONS

15850 W. BLUEMOUND ROAD (262) 754-8888

CONSTRUCTION DETAILS



BROOKFIELD, WI 53005 (262) 754-8888

