


**RIGHT SIDE ELEVATION** 1/4"=1'-0" **A**



**MISCELLANEOUS**  
A. SEE SHT A1.1 'WINDOW TYPES' FOR WINDOW ELEVATIONS.

**SEALERS (REFER TO SPECS):**  
A. SEALANT AT ALL WALL AND ROOF PENETRATIONS.  
B. SEALANT AT ALL WINDOW AND DOOR FRAMES AT HEAD AND JAMB. DO NOT SEAL SILL @ WINDOWS.  
C. APPLY NEOPRENE GASKET (CONT.) BETWEEN BUILDING & CANOPY.

**'CRITICAL' DIMENSIONS:**  
A. REQUIRED CLEAR OPENING WIDTH TO ENSURE COORDINATION WITH STANDARD SIGNAGE/ BUILDING ELEMENTS DIMENSIONS.

**NOTE:** NO EXTERIOR SIGNS ARE WITHIN THE SCOPE OF WORK COVERED BY THE BUILDING PERMIT APPLICATION. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE INSTALLATION OF ALL EXTERIOR SIGNS AND INSTALLATION OF REQUIRED BLOCKING AND ELECTRICAL CONNECTIONS FOR FINAL APPROVED SIGNS.

**NOT USED** N.T.S. **B**

NOTE: SIGNAGE UNDER SEPARATE PERMIT

V-XXX	QTY	ITEM DESCRIPTION	ELEC
V-04.3640	2	TB 3'-6" x 4'-0" LARGE SWINING BELL, PURPLE LOGO - FACE LIT	X
V-09.16W	3	TB 16" CHANNEL LETTER WHITE	X
V-02.33	1	33 SF MONUMENT SIGN WITH BREAKFAST	X

**NOT USED** N.T.S. **I**

**NOT USED** N.T.S. **G**

**GENERAL NOTES** **F**

**NOT USED** N.T.S. **E**

**SIGN SCHEDULE** N.T.S. **C**

SYMBOL	AREA	MANUFACTURER	COLOR	ALTERNATE MFR	ALTERNATE COLOR	CONTACT INFORMATION
1	CANOPY RAFTER/ BEAM PAINT	SHERWIN WILLIAMS	SW3022 'WOODSCAPES BLACK ALDER'			SHERWIN WILLIAMS: BRAD HARRINGTON, 216-228-54988 (PHONE), BRAD.E.HARRINGTON@SHERWIN.COM (EMAIL)
2	CANOPY COLUMN PAINT	SHERWIN WILLIAMS	SW 7062 ROCK BOTTOM			
3	PARAPET CAP (TOWER)	DUROLAST (25)	MEDIUM BRONZE (FACTORY FINISH)	SHERWIN WILLIAMS	SW 7069 'IRON ORE'	DURO-LAST; LEE COBB, 800-434-3876 (PHONE)
4	PARAPET CAP (FRONT)	DUROLAST	SHERWIN WILLIAMS SW6832 'IMPULSE PURPLE' EGGHELL (P-4)			
5	PARAPET CAP (SIDES)	DUROLAST (25)	REGAL WHITE (FACTORY FINISH)			
6	PARAPET CAP (COOLER)	DUROLAST (25)	GALVALUME PLUS (FACTORY FINISH)			
7	STOREFRONT WINDOWS	TBD	CLEAR ANODIZED			
8	PIPE BOLLARDS	STREET SMART	YELLOW - 1/4" THICK PLASTIC COVER (US.POSTMAN.COM) OR EQUAL			
9	PARAPET BACK ROOFING	DUROLAST	THE COLOR SHALL BE FACTORY COLORED 'TAN.' EQUAL ALTERNATE ALLOWED.			DURO-LAST; LEE COBB, 800-434-3876 (PHONE)
10	AWNING, PATIO ROOF, COOLER WALL	BERRIDGE	S-DECK PREWEATHERED GALVALUME			
11	FIBER CEMENT PANELS	NICHIHA - VINTAGEWOOD	CEDAR			NICHIHA; CHRIS TATE, 404-538-1261 (PHONE), ctate@nichiha.com (EMAIL)
12	BRICK	INTERSTATE BRICK - COLOR STANDARD	ARCTIC WHITE L-4			
13	BRICK	INTERSTATE BRICK - COLOR STANDARD	PLATINUM L-4			NICHIHA; CHRIS TATE, 404-538-1261 (PHONE), ctate@nichiha.com (EMAIL)
14	METAL PANELS	WESTERN STATES METAL ROOFING	18" A606-4 RUSTWALL PANELS			WESTERN METAL DECK; RUSTY FAILS - RUSTY@METALDECK.COM - WWW.METALDECK.COM
16	FIBER CEMENT BOARD TRIM	JAMES HARDIE	HARDIETRIM - 5/4" X 3 1/2" SMOOTH			
17	BRICK	INTERSTATE BRICK - COLOR STANDARD	MOCHA L-4			

**EXTERIOR FINISH SCHEDULE** **H**

- 1 BUILDING SIGN, BY VENDOR. SEE STRUCTURAL BLOCKING ELEVATIONS, SHEET S5.0 FOR MORE INFORMATION. SEE ELECTRICAL PLANS FOR POWER REQUIREMENTS.
- 2 DRIVE THRU WINDOW. SEE SHEET A1.0 AND A1.1.
- 3 DASHED LINE INDICATES ROOF BEYOND.
- 4 STOREFRONT, TYPICAL.
- 5 TUBE STEEL POST. SEE STRUCTURAL DWGS.
- 6 SWITCH GEAR. PAINT TO MATCH WALL.
- 7 CORRUGATED METAL ROOF.
- 8 GOOSENECK LAMP.
- 9 ASSUME D/T LANE SURFACE IS 6" BELOW THE FINISH FLOOR. REFER TO GRADING & SITE PLAN.
- 10 NOT USED.
- 11 TOWER WITH METAL PANEL FINISH.
- 12 PARAPET CORING. IF DURO-LAST EDGE TRIM IS USED. USE THE DURO-LAST PRE-FINISHED EDGE TRIM. SEE DETAIL 2/A6.0.
- 13 CO2 FILLER VALVE & COVER. SEE DETAIL 5/A6.2 SIM.
- 14 PAINT DOOR TO MATCH BRICK PANELS - SHERWIN WILLIAMS, SW 6098 PACER WHITE.
- 15 GAS SERVICE.
- 16 WALL SHALL BE FINISHED PRIOR TO INSTALLATION OF SWITCHGEAR.
- 17 SCUPPER, COLLECTOR, AND VERTICAL DOWNSPOUT 6" MIN. PAINT TO MATCH ADJACENT WALL.
- 18 CONCRETE CURB.
- 19 RTU BEYOND. PAINT TO MATCH MAIN BUILDING COLOR.
- 20 BREAK METAL COVER OVER WOOD STUDS TO MATCH STOREFRONT. SEE 3/A6.1
- 21 OVERFLOW SCUPPER
- 22 WOOD RAFTERS. SEE STRUCTURAL DWGS.
- 23 BOLLARD
- 24 DUROLAST SINGLE MEMBRANE ROOFING OR EQUAL.
- 25 IF THE DURO LAST PARAPET CAP TRIM IS USED IT SHALL NOT BE PAINTED.
- 26 WOOD HEADER BEAM. SEE STRUCTURAL DWGS.
- 27 NOT USED.
- 28 WALL PACK LIGHT FIXTURE.
- 29 STOREFRONT DOOR. REFER TO DOOR SCHEDULE.
- 30 HOSE BIBB LOCATION. REFER TO PLUMBING AND DETAIL 8/A6.2
- 31 GUTTER AND DOWNSPOUT. PAINT TO MATCH COLUMN
- 32 METAL AWNING - BY OTHERS
- 33 4" Ø BOLLARDS AT ALL DOWNSPOUTS.
- 34 NOT USED.
- 35 3 1/2" FIBER CEMENT BOARD TRIM - PAINT TO MATCH ADJACENT FIBER CEMENT BOARD PANEL.
- 36 KNOX BOX.

**KEY NOTES** **D**

CONTRACT DATE: 03.19.18  
BUILDING TYPE: EXPLORER MED40  
PLAN VERSION: APRIL, 2019  
SITE NUMBER: XXX-XXX  
STORE NUMBER: XX-XXXX

**TACO BELL**  
2707 N. GRANDVIEW BLVD.  
WAUKESHA, WI

**EXTERIOR ELEVATIONS (ALT)**

**A4.0**

PLOT DATE: