

Miscellaneous

No. 37 - The base bid is for removal and disposal off site of the existing dry laid lannon stone wall and construction of a Redi Rock retaining wall; see plan sheets for specifications and details. The existing 1939 keystone shall be carefully refurbished and reinstalled within the new Redi Rock retaining wall. It includes all labor, materials, tools, equipment, and any other incidentals for removal of the existing wall and construction of the new wall, and as described on the plan sheets. The contractor is responsible for visiting the project site and basing their bid accordingly. Any shrub or tree roots or stumps encountered during the removal of the old wall or the construction of the new wall shall be incidental to the bid item "Construct New Redi Rock Retaining Wall." The new retaining wall will be paid per square foot of wall face exposed.

No. 38 - Repair and renovation/refurbishment of the existing dry stack lannon stone wall. It includes all labor, materials, tools, equipment, and any other incidentals for reconstruction of the existing wall, and as described on the plan sheets. The contractor is responsible for visiting the project site and basing their bid accordingly. Any shrub or tree roots or stumps encountered during the removal of the old wall or the construction of the new wall shall be incidental to the bid item "Repair/Renovate Existing Retaining Wall." The repaired wall will be paid per square foot of wall face exposed.