

# SITE IMPROVEMENT PLANS FOR

# ROLLING MEADOWS TOWN HOMES

CITY OF WAUKESHA, WISCONSIN



SITE MAP



## VICINITY MAP

BASED ON GRID NORTH OF THE WSCONSIN COUNTY CORRDINATE SYSTEM, (NAD83 WISCORS 2018) AND REFERENCED TO THE EAST LINE OF THE SE  $\frac{1}{4}$  OF SEC. 30-6-10 MEASURED AS S00°16'58"E.

VERTICAL DATUM IS CITY OF WAUKESHA REFERENCED TO THE NE CORNER OF SEC. 30-6-10 MEASURED AS 792.26' (NAVD88 GEOID 12A WISCORS 2019) CITY COVERSION FACTOR -780.56.

PRELIMINARY

ALL IMPROVEMENTS AND CONSTRUCTION SHOWN ONTHE PLANS SHALL CONFORM TO THE CITY OF WAUKESHA DEVELOPMENT HANDBOOK & INFRASTRUCTURE SPECIFICATIONS: WHERE THE PLANS DO NOT COMPLY, IT SHALL BE THE SOLE RESPONSIBILITY AND EXPENSE OF THE DEVELOPER TO MAKE REVISIONS TO THE PLANS AND/OR CONSTRUCTED INFRASTRUCTION TO COMPLY.

OWNER/DEVELOPER: JOHN MAREK INC. W284 N5039 ROOSEVELTS QUAY PEWAUKEE, WI 53072

AGENT/ENGINEER: JRM CONSULTING, LLC 3904 OAKMONT TRAIL WAUKESHA, WI 53188



### SITE IMPROVEMENT PLANS FOR ROLLING MEADOWS TOWN HOMES

### SHEET INDEX

- TITLE SHEET, SHEET INDEX, VICINITY AND SITE MAP
- **CONSTRUCTION DETAILS CONSTRUCTION DETAILS**
- SANITARY SEWER AND WATER PLAN & PROFILE
- SANITARY SEWER AND WATER PLAN & PROFILE

GRADING PLAN

- EROSION CONTROL PLAN
- LANDSCAPE PLAN



TO OBTAIN LOCATION OF 114-259-1181 MILWAUKEE METRO) (TDD: 800-542-2289) www.diggershotline.com

WIS. STATUTE 182.0175 (1974) REQUIRES MIN. OF 3 WORK DAYS NOTICE BEFORE YOU EXCAVATE.

### CAUTION NOTICE TO CONTRACTOR

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF VARIOUS UTILITY COMPANIES AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

INITIALS DATE	0 NTS
DESIGNED JRM 10/16/23	SCALE
DRAWN JBR 10/16/23 CHECKED JRM 10/16/23	PROJECT NO. 22-044

NO.	REVISIONS	BY	DATE	
1	New PEC and new wetland lines	jrm	08-11-23	
2	Revised per City water dept. email dated 12-	jrm	12-07-23	
3	Added surveyed trees over 5" dia.	jrm	01-08-24	
	SHEET NO.			
	VICINITY MAP SITE MAP	1	OF	- 11

### **EROSION CONTROL NOTES:**


- 1. DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE WISCONSIN DEPARTMENT OF NATURAL RESOURCES TECHNICAL STANDARDS.
- 2. CONSTRUCT SILT FENCE IN ACCORDANCE WITH WDNR TECHNICAL STANDARD 1056
- 3. CONTRACTOR SHALL CHECK ALL EROSION CONTROL MEASURES EVERY SEVEN DAYS OR AFTER EACH 0.5 INCH RAINFALL WHICHEVER IS SOONER AND PROVIDE ANY MAINTENANCE REQUIRED FOR CONFORMANCE WITH THIS PLAN.
- 4. A MINIMUM OF 4 INCHES OF TOPSOIL SHALL BE PLACED ON AREAS TO BE VEGETATED, INCLUDING RESTORATION OF AREAS DISTURBED DURING UTILITY INSTALLATION.
- 5. SEEDING SHALL BEGIN WITHIN 7 DAYS AFTER FINAL GRADING IS COMPLETED.
- 6. SEEDING SHALL CONFORM TO THE REQUIREMENTS OF SECTION 630 OF THE WISDOT STANDARD SPECIFICATIONS. A NO. 40 MIXTURE SHALL BE APPLIED AT A RATE OF 2 POUNDS PER 1000 S.F.
- PLACE EROSION MATTING ON ALL SLOPES OF 4:1 OR GREATER IN ACCORDANCE WITH WISDOT STANDARD SPECIFICATIONS. EROSION MAT PRODUCTS MUST BE SELECTED FROM THE WISDOT PRODUCT ACCEPTABILITY LIST.
- 8. INSTALL EROSION WATTLES AT THE BASE OF THE SLOPE BEHIND THE BACK OF CURB AT THE ENTRANCE TO THE SITE.
- 9. TOPSOIL PILES ARE TO BE SEEDED WITHIN 14 DAYS OF LAYUP.
- 10. ANY DISTURBED AREAS LEFT OPEN FOR MORE THAN 30 DAYS WILL REQUIRE TEMPORARY STABILIZATION. REFER TO WDNR STANDARD 1059, SECTION 3 "CONDITIONS WHERE PRACTICE APPLIES".
- 11. TEMPORARY SEEDING: ANNUAL RYEGRASS AT 25 lbs/ACRE; LATE SEASON TEMPORARY SEEDING (SEPT. 15 TO OCT. 15): WINTER WHEAT AT 2 BUSHELS/ACRE; DORMANT SEEDING (AFTER NOV. 1): NO. 10 MIXTURE AT 4 lbs/1000 S.F. CHANNELS ARE TO BE STABILIZED WITH CLASS 3, TYPE A EROSION MAT.
- 12. BIWEEKLY PROGRESS SITE MEETINGS TO BE HELD ON THE SITE. ATTENDEES WILL BE OWNER, CONTRACTOR, ENGINEER AND A REPRESENTATIVE FROM CITY OF WAUKESHA ENGINEERING DEPARTMENT.


### **CONSTRUCTION SEQUENCE:**

- 1. CONSTRUCT STONE TRACKING PAD AT THE PROPOSED ENTRANCE.
- 2. CLEAR AND GRUB SITE.
- 3. INSTALL SILT FENCE AT THE LOCATIONS NOTED ON THE PLANS. THIS MUST BE DONE BEFORE ANY GRADING ACTIVITIES TAKE PLACE.
- CONSTRUCT SEDIMENT TRAP AND SEDIMENT BASIN. THIS WORK IS TO BE DONE PRIOR TO ANY OTHER GRADING ACTIVITIES. SIDE SLOPES ARE TO BE STABILIZED IMMEDIATELY AFTER CONSTRUCTION.
- GRADE THE SWALE BEHIND UNITS 10 11 AND 14 -15 TO DIRECT RUNOFF INTO DETENTION POND. STABILIZE THE SWALE IN ACCORDANCE WITH THE EROSION CONTROL PLAN IMMEDIATELY AFTER CONSTRUCTION.
- 6. IF DEWATERING IS NECESSARY DURING POND CONSTRUCTION A TEMPORARY SETTLING BASIN IS TO BE CONSTRUCTED IN ACCORDANCE WITH THE DETAIL ON SHEET 3. THE BASIN MUST BE PLACED WITHIN THE PERIMETER SILT FENCE ON LEVEL GROUND.
- 7. TOPSOIL ON THE REMAINDER OF THE SITE IS TO BE STRIPPED AND STOCKPILED. THE STOCKPILE IS TO BE PROTECTED WITH SILT FENCE WITHIN 7 DAYS AND SEEDED WITHIN 14 DAYS OF LAYUP.
- 8. ROUGH GRADING MAY TAKE PLACE AFTER TOPSOIL STRIPPING.
- GRADE ROADWAY AND BUILDING PADS. INSTALL STORM SEWER AND UTILITIES. ALL INLETS ARE TO BE PROTECTED IMMEDIATELY AFTER INSTALLATION IN ACCORDANCE WITH THESE DETAILS.
- 10. AFTER BASIN HAS BEEN GRADED, THE STORM SEWER OUTFALL IS TO BE CONNECTED TO THE BASIN STANDPIPE WITH A 12" DIAMETER PIPE. THIS CONNECTION IS TO REMAIN IN PLACE UNTIL VEGETATION HAS BEEN ESTABLISHED IN THE BASIN.
- 11. FINISH GRADE CONSTRUCTED WETLAND AND SEED WITH NATIVE WISCONSIN SEED MIXTURE. CONTRACTOR TO CONSULT WITH A CERTIFIED LANDSCAPE ARCHITECT.
- 12. PERMANENT SEEDING TO BE COMPLETED BY OCTOBER 15TH OF THE YEAR GRADING WORK IS COMPLETED OR BY JUNE 1ST OF THE FOLLOWING YEAR.
- 13. REMOVE ALL TEMPORARY BMP'S SUCH AS SILT FENCES AND SEDIMENT TRAPS AS SOON AS ALL DISTURBED AREAS HAVE BEEN STABILIZED. DO NOT REMOVE BMP'S UNTIL DISTURBED AREAS HAVE BEEN STABILIZED. CONTRACTOR IS TO ENSURE THAT SEDIMENT IS REMOVED FROM PERMANENT BASINS USED AS SEDIMENT TRAPS DURING CONSTRUCTION


### This drawing based on Wisconsir Department of Transportation Standard Detail Drawing 8 E 9-6.

SILT FENCE / 1






(WHEN ADDITIONAL SUPPORT REQUIRED)




TRENCH DETAIL


### **GENERAL NOTES:**

- 1. HORIZONTAL BRACE REQUIRED WITH 2" x 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- 2. TRENCH SHALL BE A MINIMUM OF 4" WIDE AND 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL AND COMPACT TRENCH WITH EXCAVATED SOIL.
- 3. WOOD POSTS SHALL BE A MINIMUM SIZE OF 1-1/8" x 1-1/8" OF OAK OR HICKORY
- 4. SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- 5. CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180^ B) HOOK THE END OF EACH SILT FENCE LENGTH.
- 6. SILT FENCE SHALL BE INSTALLED USING CURRENT WISDOT STANDARDS AT THE TIME OF CONSTRUCTION.







JOINING TWO LENGTHS OF SILT FENCE




COMPACTED CLAY COLLAR (2)



SEDIMENT TRAP #2 OUTLET 3





BASIN #1 OUTLET DETAIL




PLACE WISDOT TYPE R GEOTEXTILE FABRIC UNDER STONE IF SATURATED CONDITIONS ARE EXPECTED.

STONE TRACKING PAD (5)







AND SMOOTHED.

- 2. PLACE FILTER CLOTH ON BOTTOM AND SIDES OF PREPARED FOUNDATION. ALL JOINTS TO OVERLAP A MINIMUM OF ONE FOOT
- 3. EXERCISE CARE IN RIPRAP PLACEMENT TO AVOID DAMAGE TO FILTER FABRIC.
- 4. PLACE RIPRAP ON ZERO GRADE, TOP OF RIPRAP TO BE LEVEL WITH PROPOSED OUTLET NO OVERFALL AT ENDS.
- 5. RIPRAP SHALL BE MEDIUM RIPRAP IN ACCORDANCE WITH SECTION 606 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
- 6. IMMEDIATELY AFTER CONSTRUCTION, STABILIZE ALL DISTURBED AREAS WITH VEGETATION.
- 7. LINE CHANNEL TO TOP OF BANKS FOR A DISTANCE OF 12' DOWNSTREAM. NO RESTRICTION OF CHANNEL CROSS SECTION SHOULD EXIST.

FLARED END SECTION (F.E.S.) AND RIPRAP DETAIL 2/

**PRELIMINARY** 

3904 OAKMONT TRAIL WAUKESHA, WI 53188 262-206-8047

INITIALS DATE DESIGNED JRM 10/16/23 JAB 10/16/23 CHECKED JRM 10/16/23 NTS


> PROJECT NO. 22-044


SHEET NO.

OF

FILENAME. C. I CAD Projects | Tanglawand Waykasha | SHEETS | 2-3-1 Datail Shoots dwa


PINT NATE: 1/11/2021 5.16 11





# PRE-CAST INLET DETAIL 2 NEENAH R-3501-PR 3

\* CONTRACTOR SHALL SET INLET AT ASPHALT BINDER GRADE AND ADJUST WHEN SURFACE COURSE IS PLACED.



IF DEWATERING IS NECESSARY, A PUMP WILL BE PLACED WHERE NEEDED. AT THE POINT OF DISCHARGE THE WATER BEING PUMPED OUT WILL FLOW INTO A TEMPORARY SETTLING BASIN AS SHOWN ON THE PLANS. SIZING OF THE TEMPORARY SETTLING BASIN SHALL BE DETERMINED IN THE FIELD BY THE CONTRACTOR.

SIZE TO BE DETERMINED IN FIELD AS INDICATED BELOW:

STORAGE VOLUME (C.F.) = 16 x GPM (PUMP RATE)


EXAMPLE:
CONTRACTOR INDICATES PUMP CAPABLE OF 50 GPM
HEIGHT OF BALES = 1.5 FT


 $SV(C.F.) = 16 \times 50 \text{ GPM} = 800 \text{ C.F.}$  $\frac{800 \text{ C.F.}}{1.5 \text{ FT.}} = 533 \text{ S.F.}$ 


SOLUTION:

USE A 20' x 27' BASIN

**DEWATERING PLAN** 









INSTALLATION NOTES:
FINISHED SIZE, INCLUDING FLAP POCKETS WHERE REQUIRED,
SHALL EXTEND A MINIMUM OF 10" AROUND THE PERIMETER TO
FACILITATE MAINTENANCE OR REMOVAL.
THE CONTRACTOR SHALL DEMONSTRATE A METHOD OF
MAINTENANCE, USING A SEWN FLAP, HAND HOLDS OR OTHER METHOD
TO PREVENT ACCUMULATED SEDIMENT FROM ENTERING THE INLET.
INLET PROTECTION SHALL BE INSPECTED AT A MINIMUM WEEKLY AND
WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT
PRODUCES 0.5 INCHES DURING A 24 HOUR PERIOD. SEDIMENT
DEPOSITS SHALL BE REMOVED WHEN ACCUMULATION TOTALS
BETWEEN 1/3 AND 1/2 THE DESIGN DEPTH OF THE DEVICE OR WHEN THE
DEVICE IS NOT FUNCTIONING AS DESIGNED.
DURING REMOVAL OF INLET PROTECTION ENSURE SEDIMENT DOES
NOT FALL INTO THE INLET. ANY MATERIAL WHICH FALLS INTO THE


INLET PROTECTION, TYPE B 4

INLET SHALL BE REMOVED.





### MOUNTABLE CURB CROSS SECTION





**PRELIMINARY** 

Sevisions per City water dept. email 12-06-2023 | Sevis water dept. email 12-06-2023 | Sevis water dept. email 12-06-2023 | Sevis water dept. emai

ROLLING MEADOWS TOWN
DETAIL SHEET

INITIALS DATE

DESIGNED JRM 10/16/23

DRAWN JAB 10/16/23

CHECKED JRM 10/16/23

NTS


SCALE
PROJECT NO.
22-044

SHEET NO.


3 OF 1


FILENAME: C. \CAD Projects \ Tanalowood Waukasha \ SHEETS \ 2-3-1 Datail Shoots dwa

PINT NATE: 1/10/2021 6:51 DM




# SANITARY SEWER LIFT STATION 1










### LIFT STATION CONTROL PANEL



**PRELIMINARY** 



LING MEADOWS TOWN P

INITIALS DATE

DESIGNED JRM 10/16/23

DRAWN JAB 10/16/23


CHECKED JRM 10/16/23

NTS

PROJECT NO. **22-044** 

SHEET NO.

OF 1 1




3904 OAKMONT TRAIL WAUKESHA, WI 53188 262-206-8047

INITIALS DATE DESIGNED JRM 10/16/23

JAB 10/16/23 CHECKED JRM 10/16/23

PROJECT NO. **22-044** SHEET NO. OF



CIVIL EXCHERENCE SERVICE

Shows we that the second of the

9 - 2

# SANITARY SEWER AND WATER PLAN

INITIALS DATE

DESIGNED JRM 10/16/23

DRAWN JAB 10/16/23


O 40'


SCALE
PROJECT NO.


22-044 SHEET NO.

SHEET NO.

6 OF










### NOTES:

- 1. SEWER CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CITY OF WAUKESHA STANDARD SPECIFICATIONS AND STATE OF WISCONSIN STANDARDS FOR SEWER AND WATER CONSTRUCTION.
- 2. WATER MAIN CONSTRUCTION MUST COMPLY WITH THE "SPECIFICATIONS FOR WATER MAIN & SERVICE LATERAL MATERIALS AND THE INSTALLATION OF WATER MAIN & APPURTENANCES FOR WAUKESHA WATER UTILITY, CITY OF WAUKESHA" DATED NOVEMBER 21, 2019.
- 3. TRACER WIRE REQUIRED FOR ALL STORM SEWER, SANITARY SEWER AND WATER SERVICE PER DSPS REQUIREMENTS. 18 GAUGE MINIMUM AND LOCATED WITHIN 6" OF PIPE. STORM SEWER WIRE SHALL BE BROWN, WATER SHALL BE BLUE AND SANITARY SHALL BE GREEN IN COLOR.
- 4. SANITARY LATERALS ARE 6" MIN. WITH A SLOPE OF 1% TYPICAL.
- 5. WATER LATERALS ARE 1 1/2" MIN. AND INCLUDES SHUTOFF VALVES.
- 6. INSTALL THE PROP. 8" WATER MAIN WITHIN TWENTY FEET (20') OF THE CONNECTION, FILL AND PRESSURE TEST THE NEW WATER MAIN. AFTER THE PRESSURE TEST PASSES, MAKE THE CONNECTION AT STATION 1+30 AND FLUSH FOR BACTERIOLOGICAL SAMPLE AFTER WATER MAIN HAS CHLORINATED FOR TWENTY-FOUR HOURS.
- 7. HYDRANT VALVES NOT ALLOWED IN SIDEWALK.
- 8. ALL APPLICATIONS AND FEES FOR SANITARY SEWER MUST BE COMPLETED AND PAID PRIOR TO BE CONNECTION TO SEWER SYSTEMS.
- 9. ANY UTILITY WORK IN THE RIGHT-OF-WAY AND ALL SANITARY SEWER CONNECTIONS TO BE INSPECTED BY CITY. NOTIFY CITY 72 HOURS IN ADVANCE OF CONNECTING TO SEWER.







**PRELIMINARY** 

CONSULTING, LIC

TAME EXCUSSIONS

1 Modified grading per new wetland line jrm 05–15–23

2 Revisions per City water dept. email of 12–06–23. jrm 12–07–2023

2 Revisions per City water dept. email of 12–06–23. jrm 12–07–2023

OLLING MEADOWS TOWN HOMES SANITARY SEWER AND WATER PLAN

INITIALS DATE

DESIGNED JRM 10/16/23


DRAWN JAB 10/16/23

CHECKED JRM 10/16/23

SCALE
PROJECT NO.

PROJECT NO.
22-044
SHEET NO.

7 OF 11






WAUKESHA, WI 53188 262-206-8047

INITIALS DATE DESIGNED JRM 10/16/23

SCALE PROJECT NO. 22-044

SHEET NO.




3904 OAKMONT TRAIL WAUKESHA, WI 53188 262-206-8047

INITIALS DATE DESIGNED JRM 10/16/23 JAB 10/16/23 CHECKED JRM 10/16/23

PROJECT NO. 22-044

SHEET NO. OF





262-206-8047							
BY DATE	jrm 05-15-23		12-07-23	jrm 01-08-24			
ВУ	jrm		. jrm	jrm			
REVISIONS	Modified grading per new wetland line	and modified grading to keep trees on P/L	Revisions per City water dept. email of $12-6-23$ . jrm   $12-07-23$	3 Added surveyed trees over 5" dia.			
NO.	_		7	$\sim$			

ROLLING MEADOWS TOWN HOME
EROSION CONTROL PLAN

INITIALS DATE

DESIGNED JRM 10/16/23

DRAWN JAB 10/16/23

O 40'
SCALE

PROJECT NO. 22-044

SHEET NO.

OF





12-07-23 01-05-24

ROLLING

INITIALS DATE DESIGNED JRM 10/16/23 DRAWN JAB 10/16/23 CHECKED JRM 10/16/23

> SCALE PROJECT NO.

22-044 SHEET NO.

OF