

LANDMARKS COMMISSION APPLICATION

Monthly meeting is scheduled the first Wednesday of every month.

Application Deadline is 4:30 p.m. on the Monday of the week before the Landmarks

Commission meeting (ten days before the meeting date).

| Date Received: | Paid: | Rec'd. By |
|---|--|---|
| I am applying for a: Certificate of Appropriateness (COA) - \$15 application Paint and Repair Grant (no fee) | | |
| A. General Information: Applicant Name: Zachay Pape Phone-Home: 703-994-6910 Phone-Work: E-mail: Zachay Pape & gmail com Mailing Address: N59w2u702 Quail Run Lane | | |
| PLEASE READ AND SIGN: The information in this application supply any relevant documentation that is required for the proper remissing or incomplete information may delay the review process. By its agents to enter upon my property for the purpose of reviewing this a Signed: | eview of this applic signing this I also a application. | cation and I understand that any authorize the City of Waukesha o |
| 2 | ELOW to INDICATION TO THE PROPERTY OF THE PROP | TE WHETHER YOUR FAMILY <u>e Level</u> (Up to:) ,050 ,350 ,650 ,950 elines |
| C. Architectural Information on Property (if unknown you Historic Name of Building: Henry Market Nickels Haddress of Historic Property 513 McCall 51, Construction Date/Era: 1885 Architectural Style: Gabled Ell Historic Background (Brief): | louse | |

We recommend reading the Landmarks Commission Design Policies and/or discussing your plans with staff before submitting your application. The Design Policies are available here: https://www.waukesha-wi.gov/government/departments/landmarks.php

D. Nature of Intended Repair(s)/Proposed Work:

Briefly and accurately describe type and location of proposed work on the primary building, carriage house, and any other outbuildings (i.e.: garage). Attach extra sheets and supplemental material as requested in the criteria checklist found in Section E. Be sure to reference the attached Exhibit A, which summarizes the guidelines from the Secretary of Interior's Standards for Historic Preservation Projects. Your narrative must address any of the following elements related to your project:

| Roof: Repair or replacement? Replacement Soffits, Fascia, Downspouts Eaves, Gutters Shingle type/style/color | Chimney(s): Repair or replacement? Flashing Tuckpointing |
|---|---|
| Siding: Repair or replacement? Paint Colors, Materials Shingling and Ornamentation/Stickwork | Windows: Repair or replacement? |
| Other Exterior Repairs: Front Door Awnings Brickwork/Stonework Cresting Doors Replace Apt # 3 Door | Foundation: Extent of repair Tuckpointing Other |
| Porch: Repair or replacement? Front or Side, Rear Ornamentation Finials, Other | Landscaping Fences |
| about rehabbing the door and they | a large Crack spanning from top as well. Inquired with Thoughtful Craftsmar declined. Would replace with like Style. b have some picked out by LC meeting). |
| Flat roof portion above west side be repair but was determined that replace | ny window is leaving. Figured about ny entire root section is more economical. |
| | |
| | |

Landmarks Application Revised/2021

BCI Exteriors

Address: N57 W13566 Carmen Ave

PALMER ODONAVIN

Quote

Page 1 of 2

Mneomonee Falls WI 53051

Phone: 262-703-9800


262-703-9804

Website: www.bciexteriors.com

Quote Number: 20

Date: 4/20/2022

Sales Person: Mitch Bradetich



Job Name:

Specifications —

U.D. = 33-1/2" x 81-5/8"; R.O. = 34-1/4" x 82"

O.M. of Exterior Trim = 36" x 82-7/8"

Lead Time: Call for Lead Time: Installed Sale




Image is viewed from Exterior!

| Item Description | Qty | Price | Extended |
|--|-----|----------|------------|
| Installed Sale: Standard Installation | | | |
| 2' 8" x 6' 8" FCM601-FFLE Fiber-Classic Mahogany (Flat Lite Frame) Fiberglass Door w/Low E Glass - Left Hand Inswing | 1 | 2,900.71 | \$2,900.71 |
| 2-3/8" Backset - Double Bore (2-1/8" Dia. Bore w/Standard 5-1/2" Spacing) w/Faceplate Lockset Latch Prep w/Standard Strike Prep w/No Deadbolt Strike Prep | 1 | 16.81 | \$16.81 |
| Set of Standard - Oil Rubbed Bronze Hinges | 1 | 23.53 | \$23.53 |
| Primed Dura-Frame - 6-7/8" Jamb w/Dura-Frame Brickmould Exterior Trim (Applied) w/(1)Oil Rubbed Bronze Adjustable Security Strike Plate (for Lockset only) | 1 | 285.78 | \$285.78 |
| Bronze Compression Weatherstrip | 1 | 0.00 | \$0.00 |
| Tru-Defense Composite Adj. w/Dark Cap - Mill Finish Sill | 1 | 0.00 | \$0.00 |
| PREFINISH: Paint Door Panel Interior & Exterior 100 SNOW | 1 | 349.66 | \$349.66 |
| Item Total | | | \$3,576.49 |

Replace Intuior _> +\$250.00 Molding around door

#3826.49



Version #: 1.25-0 Version Date: 4/10/2022



BUILT ON BELIEF, COMMITMENT, AND INTEGRITY.



ROOFING . SIDING . GUTTERS . WINDOWS . DOORS . INSULATION

CONTRACT

April 20, 2022

Zachary Pape N59W24702 Quail Run. Sussex WI. 53089

Phone Number: 703-994-6910

Jobsite Address: 513 Mccall St. Waukesha WI, 53186

Thank you for the opportunity to quote the following work. We hereby propose to furnish and perform the labor necessary for the completion of ... Job Description: Sectional roof removal and replacement (Side of home flat roof)

SPECIFICATIONS

Full replacement of flat roofing area:

- 1. Remove existing roofing materials down to existing wood roof deck on flat roofing located on side, of building on top of window bump out. If any rotten wood is found it will be replaced at a time and material basis. Time being \$87.50 per man hour, and material at prevailing rates.
- 2. Remove existing storm windows, and set aside for reinstallation upon job completion. Remove aluminum brickmould trim around storm windows.
- 3. Install 1/4" DenSDeck roofing underlayment board mechanically fastened with screws and plates over the top of exiting roof deck.
- 4. Install fully adhered .060 E.P.D.M. to underlayment installed as well as up and/or over any adjacent surfaces.
- 5. Install fully adhered .060 E.P.D.M. on the DenSDeck material and up/onto any adjacent wall surfaces.
- 6. Install .060 uncured rubber or cover strip fully adhered in all detailed areas.
- 7. Install custom fabricated pre-finished .26-gauge steel perimeter flashings to all exposed roof edges. Color to be: white
- 8. Install .060 6" cover tape around entire perimeter of newly installed perimeter metal.
- 9. Install all proper caulk, sealants, and water cut-off in areas that are necessary.
- 10. Install new pre-finished aluminum flashing over brickmould of windows. Color to be; white
- 11. Reinstall Storm windows set aside after job completion.
- 12. Remove all job-related debris on a daily basis, and dumpster removal upon completion.

| *BCI is not liable for any leak caused from window areas since | e it's not being replaced. Initial: | * |
|--|-------------------------------------|---|
| | | |

(Includes taxes) Contact terms initial to proceed:

Total contract amount = \$1,999.00 Total amount due down = \$699.00 Total amount due upon completion = \$1,300.00