MRV ARCHITECTS, INC.

5105 Tollview Dr., Suite 209, Rolling Meadows, IL 60008 Ph. (224) 318-2140 – Email: mariov@mrvarch.com

June 14, 2018

City of Waukesha Plan Commission Community Development Department 201 Delafield Street, Room 200 Waukesha, WI 53188

Written Statement

The applicant, Albor Restaurant Group, intend to build Taco Bell franchise building with an accessory drive-thru on the current property at the above noted location. The brand will exist on the site as a freestanding building. As a part of the redevelopment, we are required to request a review of the Plan Commission for this property. We believe that the development and operation of the brand will enhance current property, while providing the typical Quick Services Restaurant service in a high-quality environment this brand is known to deliver.

The franchise group own and operate many drive-thru locations throughout the United States. The Albor Restaurant Group's upper management team consists of many multi-unit managers who have well over 15 years of Quick Service Restaurant experience each.

In general, this location qualifies for a new prototypical style for Taco Bell. They will be unveiling a new prototypical design for their respective building. This location has a full menu offering, and functions as a typical free-standing building. The total gross area of the proposed building comes out as 2,112 S.F.

We understand the sensitivity to create a building with an architecturally pleasing exterior appearance; but at the same time offering a comfortable and functional experience in the interior. The introduction of more modern elements to the building exterior work in conjunction with interior elements such as soft seating produces a very wholesome, and complete experience. Furthermore, the use of quality construction materials sets these buildings apart from other brands and as well as those within the same brand.

Items such as directional signs and a menu board are also essential to a well-functioning drive-thru facility and have been integrated into the overall site design. A drive-thru would be an added convenience for customers that are not intending on dining in. Both drive-thru lanes will be separated from the bypass traffic. To help ensure public safety, warning stripes are to be painted wherever pedestrians may come into contact with drive-thru traffic. The drive-thru speaker systems typically used are adjustable to comply with any village restrictions and can be accessed by a manager at any time as needed to control the volume. They can also be set for day and night sound levels to prevent any noise from carrying to the surrounding properties at the quieter hours of the night. For those that will be dining in, there are 18 parking stalls planned.

MRV ARCHITECTS, INC.

5105 Tollview Dr., Suite 209, Rolling Meadows, IL 60008 Ph. (224) 318-2140 – Email: mariov@mrvarch.com

The hours of operation are intended to be for 7 days a week. The store could open as early as 7:00am and dining room would close at 11:00 pm. The drive-thru operation would be 7:00 am to 3:00 am on weekday and 4:00am on the weekends.

There will not be any alcohol served at this location.

Overall, the addition of this building and drive-thru will prove beneficial to the community by providing a valuable service. Taco Bell will be able to accommodate the customers as needed while having little disruption to the surrounding area. The exterior and interior lighting, signage, materials and proposed plan will maintain the character of the design and surrounding area while creating a more enjoyable experience. We look forward to presenting this project to you and hearing your feedback.

Please feel free to contact me with any further questions regarding the request for review.

Sincerely,


Mario Valentini

Principal,

MRV Architects, Inc.

TACO BELL RESTAURANT

2707 N. GRANDVIEW BOULEVARD WAUKESHA, WISCONSIN



	1 50515	
EXISTING	LEGEND	PROPOSED
× W=E631.75	WALK GRADE	\times W=631.75
C=E630.62	CURB GRADE	× C=630.62
G=E630.06	GUTTER GRADE	G=630.39
P=E630.55	PAVEMENT GRADE	P=631.25
E632.26	GRADE	632.51
639	CONTOUR	639
	CONCRETE CURB	
========	CONC. CURB TO BE REMOVED	
	RETAINING WALL	
—— (—— (SANITARY SEWER	\longrightarrow
	STORM SEWER	———
W ₁₂ "	WATERMAIN	W ₂ "
_xxxx-	CHAIN LINK FENCE	2
	GUARD RAIL	
─ ─	DITCH FLOWLINE	
⊚	MANHOLE	•
	CATCH BASIN	
	INLET BASIN	
	DRY WELL	
\otimes	VALVE VAULT	
	VALVE BOX	•
- -	LIGHT POLE	+
Ø	WOOD POLE	
A	FIRE HYDRANT	~
	DIRECTION OF DRAINAGE	
	CONCRETE WALK/PAVEMENT	
AN .	SILT FENCE	——————————————————————————————————————
£ · 3 3"D	DECIDUOUS TREE	
- w	DDODEDTY LINE	
—— E ——	PROPERTY LINE UNDERGROUND ELECTRIC	
G	GAS MAIN	
—— т ——	UNDERGROUND TELEPHONE	
——— F ———	UNDERGROUND FIBER OPTIC	
——————————————————————————————————————	UNDERGROUND CABLE TV	
——— UH ———	OVERHEAD WIRES OVERLAND FLOW ROUTE	ightharpoons
		- /
	WOOD FENCE	

GENERAL DEVELOPMENT NOTES

All work shall be performed in a manner so as not to unreasonably impair or interfere with the use, occupancy or enjoyment of, or with any business conducted on, any adjacent property.
 At all times during the performance of any Work all areas other than the construction site proper and

the staging area shall be kept free from any loose dirt, debris, equipment or construction materials

. Upon completion of the Work, Constructing Party shall promptly restore the area to as good or better condition than existed before the use of the area commenced. Restoration shall include, without limitation, clearing the areas of all loose dirt, debris, equipment and construction materials, the repair or replacement of paving, striping and landscaping, and the repair or replacement of any and all damaged areas or improvements.

GENERAL NOTES AND SPECIFICATIONS

1. All material and construction shall comply with the requirements of the State of Wisconsin Department of Transportation "Standard Specifications for Highway and Structure Construction" latest edition, except as may be modified by the project plans and specifications.

2. All underground construction shall comply with the requirements of the "Standard Specifications for Sewer and Water

Construction in Wisconsin", latest edition, except as may be modified by the project plans and specifications.

3. Water mains shall be protected in accordance with the requirements of the Wisconsin Administrative Code and the City of Waukesha. Where a sewer crosses a water main, a minimum vertical separation of 18" shall be provided between the top of

the lower pipe and the bottom of the upper pipe. At crossings one full length of water pipe shall be centered on the sewer so that both joints will be as far away from the sewer as possible. Where this 18" vertical separation is not provided, the sewer shall be constructed to water main standards for a minimum of 10 feet on each side of the water main unless otherwise noted on the drawings. Minimum water main cover is 6.0 feet.

4. All sewer and water main trenches under or within five feet of existing or proposed curbs, sidewalk, or pavement shall be backfilled with compacted porous granular backfill complying with WISDOT and City of Waukesha requirements.

5. AT&T Wisconsin Telephone, WE Energies, Spectrum Business, and other utility company conduits are not necessarly shown on the drawings and must be located in the field prior to construction. Call Diggers Hotline (1-800-242-8511) at least 72 hours prior to the start of construction.

6. Any pavement, walks, landscaping, or other improvements on adjoining properties disturbed by contractor's operations shall be replaced in kind at no additional cost.

7. Valve vault, inlet basin and manhole covers and rings shall be set in workmanlike manner in mastic bed.

8. All elevations shown are based on City of Waukesha datum.
9. The City of Waukesha Engineering, Building, and Public Works Departments and Waukesha Water Utility shall be notified at least five working days prior to start of construction.

five working days prior to start of construction.

10. All structures shall be clean at time of final acceptance at no additional charge.

11. All work to meet all state and local codes and requirements.

12. Water and sewer locations are shown on the drawing from the best available information and must be located in the field by the contractor prior to construction. Any discrepancy that the contractor may find with the plan shall be immediately

reported to the Engineer for resolution prior to proceeding with construction.

13. Valve vault lids shall be stamped "Water", storm manhole covers shall be stamped "Storm", and sanitary manhole covers shall be stamped "Sanitary". All lids shall also be stamped "Waukesha".

14. Water service lines (3" and larger) to be cement—lined ductile iron, Class 52, conforming to ANSI specification A21.51 with push—on rubber gasket joints. All fittings to be cement—lined. Sterilization and pressure testing is included. All water service construction shall comply with the Wisconsin Administrative Code and the Waukesha Water Utility requirements.

15. Water service lines (2" and smaller) shall be copper water tube, type K, soft temper for underground service conforming to ASTM B—88 and B251 and also conforming to all Waukesha Water Utility requirements.

16. PVC sewer pipe shall be PVC SDR 26 pipe meeting the requirements of ASTM D3034 with flexible elastomeric joints per ASTM D3212, unless otherwise noted on the drawings.

17. Class I embedment, with a minimum depth of 6" below the pipe and 12" above the pipe complying with City of Waukesha requirements shall be provided for all sewer construction.
18. All floor drains shall be connected to the sanitary sewer system. All downspouts and footing drains shall discharge into the

19. "Band Seal" or similar flexible type couplings shall be used in the connection of sewer pipe of dissimilar materials.

20. Concrete thrust blocks to prevent movement of water main under pressure shall be placed at all tees, valves, and bends of

11 1/4 degrees and greater.
21. Reinforced concrete storm sewer pipe shall be ASTM C-76 with rubber gasket joints (ASTM C443), except as noted.
22. When connecting to an existing sewer main by means other than an existing wye, tee, or an existing manhole, one of the following methods shall be used: A. Circular saw-cut of sewer main by proper tools ("Sewer-Tap" machine or similar) and proper installation of hub-wye saddle or hub-tee saddle. B. Remove an entire section of pipe (breaking only the top of one

bell) and replace with a wye or tee branch section. C. With pipe cutter, neatly and accurately cut out desired length of pipe for insertion of proper fitting, using "Band—Seal" or similar couplings to hold it firmly in place.

23. The contractor(s) shall indemnify the owner, Northwestern Engineering Consultants, P. C. and the municipality, their agents, etc. from all liability involved with the construction, installation and testing of the work on this project.

24. Existing grades and improvements are shown from the best information available and must be verified in the field by the

etc. from all liability involved with the construction, installation and testing of the work on this project.

24. Existing grades and improvements are shown from the best information available and must be verified in the field by the contractor prior to the start of construction. Any discrepancy with the plan shall be reported to the engineer.

25. All existing buildings, foundations, utilities, landscaping and other improvements on adjacent properties shall be protected at all times during construction. The contractor is responsible to provide and install any materials, equipment, and/or manpower necessary to accomplish this.

26. All construction and traffic control within the street rights—of—way shall comply with all Wisconsin Department of Transportation, Waukesha County DPW and City of Waukesha requirements. The contractor is accountable for the safety of the motoring public and shall adhere to WISDOT standards for maintenance of traffic.

27. The contractor is responsible for maintaining a clean construction area and shall remove debris resulting from his operations. Open trenches or other construction hazards shall be protected with barricades at the end of each day's operations.
28. The contractor shall be responsible for compliance with all of the requirements of the Occupational Safety and Health Act including those requirements for open cut trenches and sheeting and bracing as required. At no time will the engineer or any of his employees be held liable, either directly or as third party participants to any litigation concerned with the construction

29. Subgrade preparation for all pavements and other improvements shown on the drawings shall include topsoil stripping and removal of any underlying unstable/deleterious material. Fill placement under all paved areas shall be compacted to 95% Modified Proctor density and shall comply with all the recommendations of the soils engineer.

30. All existing field drainage tile encountered or damaged during construction are to be restored to their original condition,

properly rerouted, and/or connected to the storm sewer system. The contractor shall keep a record of all locations of field drainage tile encountered.

drainage tile encountered.
31. D.l. sewer pipe shall be ductile iron pipe, Class 52 conforming to ANSI specification A21.51 with push—on rubber gasket joints.
32. Drainage from upstream properties shall not be blocked at any time in any manner by any of the proposed construction

work shown on these drawings.

33. All excess excavated material shall become the property of the contractor and shall be removed from the site and legally disposed of by him.

34. All work shall comply with the Wisconsin Department of Natural Resources Wisconsin Construction Site Best Management Practices Handbook. The contractor shall take whatever steps are necessary to control erosion on the site. Erosion control features shall be constructed concurrently with other work on the site. The contractor shall take sufficient precaution to prevent pollution of streams, lakes and reservoirs with fuels, oils, bitumens, calcium chloride or other harmful materials. He shall conduct and schedule his operations so as to avoid or minimize siltation of streams, lakes and reservoirs. Hauling will not be allowed when the work site is too wet to maintain acceptable conditions on adjacent streets. Adjacent streets and driveways shall be manually or mechanically swept periodically as may be required to maintain clean conditions. Downstream inlet basins shall be protected with temporary inlet protection devices under the rims to prevent sediment from entering the storm sewer system—see detail. sheet C—8.

35. The design engineer shall not be responsible for the means, methods, procedures, techniques, or sequences of construction not specified herein, nor for the safety on the job site, nor shall the design engineer be responsible for the contractor's failure to carry out the work in accordance with the contract documents.


36. The contractor is advised that the site contains areas of trees and brush. He shall make his own investigation and shall include the cost of tree and brush removal in his total price bid. Any trees whose trunk is located on both sides of any Taco Bell property line shall remain and be protected, unless written permission is obtained from the adjoining property owner to remove said trees. Verify the exact scope of the landscape material removal/preservation with the landscape drawings.

37. Any damage of perimeter street curbs and/or pavement caused by the contractor's activity shall be repaired by the

38. Tracer wire for utilities to be #10 AWG copper. Color shall be blue for water, green for sanitary, brown for storm, and purple for non-potable water.

SPECIAL NOTE:
THE CONTRACTOR SHALL AT ALL TIMES CONDUCT HIS WORK IN A MANNER AS TO MINIMIZE HAZARDS TO VEHICULAR AND PEDESTRIAN TRAFFIC. TRAFFIC CONTROLS AND WORK SITE PROTECTION SHALL BE IN ACCORDANCE WITH THE APPLICABLE REQUIREMENTS OF SECTION 643 TRAFFIC CONTROL OF THE WISDOT STANDARD SPECIFICATIONS FOR HIGHWAY AND STRUCTURE CONSTRUCTION, LATEST EDITION. ALL SIGNS, BARRICADES, FLAGGERS, ETC. REQUIRED FOR TRAFFIC CONTROL SHALL BE FURNISHED BY THE CONTRACTOR. ALL WORK IN THE N. GRANDVIEW BOULEVARD RIGHT OF WAY SHALL COMPLY WITH ALL WISDOT, WAUKESHA COUNTY DPW AND CITY OF WAUKESHA STANDARDS AND REQUIREMENTS.

ALL MATERIAL AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CITY OF WAUKESHA STANDARD CONSTRUCTION SPECIFICATIONS, 2018 EDITION.



INDEX OF DRAWINGS

- C-1 TITLE SHEET
- C-2 SITE PLAN
- C-3 GRADING AND DRAINAGE PLAN
- C-4 UTILITY PLAN
- C-5 STORM WATER POLLUTION PREVENTION PLAN
- C-6 DETAILS
- C-7 DEMOLITION PLAN
- C-8 WISDOT & WISDNR DETAILS
- C-9 WISDOT & WISDNR DETAILS

BENCHMARK

BM NO.1=131.37=ELEVATION OF EAST UPPER FLANGE BOLT ON NORTH SIDE OF FIRE HYDRANT LOCATED 2 FEET EAST AND 1 FOOT NORTH OF THE SOUTHWEST TACO BELL PROPERTY CORNER. (CITY OF WAUKESHA DATUM).

DEVELOPER

MR. NEIL BORKAN
NJB OPERATIONS, INC.
302 SAUNDERS ROAD, SUITE 100
RIVERWOODS, IL 60015
847-955-1000


ARCHITECT
MR. MARIO VALENTINI
MRV ARCHITECTS, INC.
5105 TOLLVIEW DRIVE, SUITE 197
ROLLING MEADOWS, IL 60008
224-318-2140



DESCRIPTION DESCRIPTION

PREPARED BY
NORTHWESTERN ENGINEERING
CONSULTANTS, P.C.

wisconsin engineering corp license number 3525-11 expires 01/31/20
675 N. NORTH COURT
PALATINE, ILLINOIS 60067
(847) 520-8410
JANUARY 17, 2019



TERI

ULT


PALATINI

CORP LICENA H U

PLAN
RESTAURANT
VIEW BOULEVA
WISCONSIN SITE TACO BELL I ' N. GRANDV WAUKESHA,


DRAWN BY: KRI CHECKED BY: DMH **DATE:** 1-17-19


1"=20 DRAWING NO.



DRAWN BY: KRL CHECKED BY: DMH DATE: 1-17-19 SCALE: 1"=20'

JOB NO. 18 - 16





SCALE: 1"=20'

STORM WATER POLLUTION PREVENTION PLAN GENERAL NOTES This Storm Water Pollution Prevention Plan has been prepared in compliance with the requirements of the City of Waukesha and the State of Wisconsin. The work to be done is stripping, stockpiling and grading of the project site shown in detail on the contract drawings. The following notes and requirements shall apply to work performed on this project: . Soil Erosion and sediment control features shall be constructed prior to the commencement

- . Hauling will not be allowed when the work site is too wet to maintain acceptable conditions 3. Adjacent streets will be manually or mechanically swept periodically as may be required.
- minimum at end of each working day or as directed by City Inspector. All streets are to be kept free from mud and debris. I. Each catch basin will be installed with a sump as indicated on the drawings. The rims will be set at final grade. A temporary 1 foot deep sump shall be excavated in a 10 foot
- diameter area around the structure to act as a silt trap. Both sumps will be inspected after each rain and cleaned as required. . Soil stockpile areas shall be designated and surrounded by a geotextile fabric silt fence to intercept sediment-laden runoff from the stockpile. The fence shall be continuously maintained and sediment shall be removed to restore planned capacity as required.
- 6. If the stockpiles will not be used for construction activity for a period of more than 14 days, thay shall be protected with temporary vegetative cover. No material from construction site shall be discharged to the storm sewer.
- 3. The contractor shall take whatever other steps are deemed necessary by the City Inspector to prevent erosion from taking place during the course of the construction project.). The contractor shall comply with all requirements of this plan and shall include the cost of such compliance in the total price bid for his contract. O.All temporary and permanent erosion control measures must be maintained and repaired as
- The general contractor will be responsible for inspection and repair during construction. The owner will be responsible if erosion control is required after the contractor has completed 1. All work shall comply with "Wisconsin Department of Natural Resources Stormwater Construction Technical Standards and Construction Practice Standards" and all City of Oconomowoc
- 2. Install storm drain inlet protection device under the rim of each new and existing impacted storm
- structure to prevent eroded material from entering the storm sewer system during the construction project. Storm drain inlet protection devices shall be checked weekly and within 24 hours after every rain that produces 0.5 inches of rain or more during a 24 hour period and replaced if covered with dirt or torn. The contractor shall use extreme care not to allow eroded material to enter the storm structure when removing or changing the storm drain inlet 3. Watering shall be used as required to control dust on the project. A water truck shall be
- kept on the site at all times during mass earthwork construction, if required by the City. 4. The name address and telephone number of the individual in responsible charge of erosion control measures during the construction project shall be given to the City Public Works Department prior to the start of construction. 5. Disturbed areas shall be protected with seeding according to the "Typical Soil Protection
- 16. All erosion control measures and inspections shall be documented on site in the site
- 7. A copy of the approved Storm Water Pollution Prevention Plan shall be maintained on the site
- 18. All wash water (concrete trucks, vehicle cleaning, equipment cleaning, etc.) shall be detained 9. Rubbish, trash, garbage, litter, or other such materials shall be deposited into sealed containers. Materials shall be prevented from leaving the premises through the action of wind
- or stormwater discharge into drainage ditches or waters of the State. 20. All Contractors and Subcontractors involved with storm water pollution prevention shall obtain a copy of the storm water pollution prevention plan and the State of Wisconsin National Pollution Discharge Elimination General Permit (NPDES Permit) and become familiar with their contents. . The Contractor shall implement best management practices as required by the SWPPF Additional best management practices shall be implemented as dictated by conditions at no
- requirements or manual of practice. As applicable Contractor shall implement additional controls as directed by permitting agency or owner.

 23. All temporary erosion and sediment control items are to be removed within thirty (30) days of the site's final stabilization by the contractor. 24. All construction activities within the boundaries of the project as well as all construction
- activities involved in making any connections to utilities outside the boundaries of the project shall comply with the requirements of this plan. This Storm Water Pollution Prevention Plan 25. Refer to the Landscape Plan for locations and specifications of sodding, seeding and other
 - CONSTRUCTION SEQUENCE
 INSTALL INLET PROTECTION FOR EXISTING DRAINAGE STRUCTURES (IF INSTALL SILT FENCE AT LOCATIONS AS INDICATED ON THE PLANS. INSTALL STONE TRACKING PAD (STABILIZED CONSTRUCTION ENTRANCE).
 PERFORM SITE DEMOLITION AS NOTED ON DEMOLITION PLAN (IF APPLICABLE). STRIP EXISTING TOPSOIL AND STOCKPILE/STABILIZE. CUT AND FILL SITE TO PLAN SUB-GRADE. BEGIN BUILDING CONSTRUCTION
 - CONSTRUCT UNDERGROUND IMPROVEMENTS, I.E. SANITARY SEWER AND CONSTRUCT PAVEMENT IMPROVEMENTS PER PLAN.
 COMPLETE CONSTRUCTION OF SITE WITH PERMANENT STABILIZATION.
 REMOVE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES.

TYPICAL SOIL PROTECTION CHART Dormant Seeding B-----A= Kentucky Bluegrass @ 90 lbs/ac. Mixed with Perennial Ryegrass @ 30 lbs/ac. B= Kentucky Bluegrass @ 135 lbs/ac. Mixed with Perennial Ryegrass @ 45 lbs/ac. C= Spring Oats @ 100lbs/ac

D= Wheat or Cereal Rye @150 lbs/ac.

F= Straw Mulch @ 2 tons/ac.

Irrigation should be provided as necessary to throughly establish growth.

INSPECTIONS AND MAINTENANCE
ALL EROSION CONTROL DEVICES AND MEASURES SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION AS REQUIRED UNTIL THE SITE OR SECTIONS OF THE SITE ARE STABILIZED. ALL EROSION CONTROL DEVICES AND MEASURES SHALL BE INSPECTED BY A REPRESENTATIVE OF THE GENERAL CONTRACTOR ONCE PER WEEK AND WITHIN 24 HOURS OF ANY STORM EVENT EXCEEDING 0.5" RAIN. WRITTEN INSPECTION REPORTS SHALL BE MAINTAINED ON SITE AND SHALL BE PRODUCED UPON REQUEST OF ANY LOCAL, STATE OR FEDERAL OFFICIAL. THE FOLLOWING SHALL BE THE MINIMUM MAINTENANCE REQUIREMENTS:

. ANY INLET OR PIPE PROTECTION OR PERIMETER EROSION BARRIER THAT SHOWS SIGNS OF DETERIORATION OR UNDERMINING SHALL BE REPLACED OR REPAIRED AS REQUIRED. 2. CATCH BASINS SHALL BE INSPECTED AND CLEANED PERIODICALLY.

3. ANY SEEDED AREAS THAT SHOW SIGNS OF GULLIES OR EROSION SHALL BE REGRADED, RESEEDED, WATERED AND FERTILIZED AS REQUIRED TO MAINTAIN A COVER THAT IS ADEQUATE TO PREVENT EROSION. . SEDIMENT SHALL BE REMOVED FROM PERIMETER EROSION BARRIER WHEN SILT REACHES ONE HALF THE

5. THE CONSTRUCTION ENTRANCE SHALL BE MAINTAINED TO PREVENT TRACKING OF MUD ONTO THE RIGHT OWAY OR PUBLIC PARKING LOTS. TOP DRESSING SHALL BE INSTALLED AS REQUIRED ON THE CONSTRUCTION

6. ANY MUD OR DEBRIS TRACKED ONTO A PUBLIC ROAD OR PARKING LOT SHALL BE REMOVED BY THE CONTRACTOR TO THE SATISFACTION OF THE JURISDICTIONAL BODY CONTROLLING THE ROAD OR PARKING LOT. THIS WORK SHALL BE PERFORMED AT NO ADDITIONAL COST TO THE OWNER.

DRAWN BY: KRI CHECKED BY: DMH **DATE:** 1-17-19

POLLUTIC BELL R RANDVI


0


元 0


SCALE: 1"=20'


DRAWING NO.


JOB NO. 18 - 16











PROJECT LOCATION MAP

MRV

ARCHITECTS, INC.

ROLLING MEADOWS, IL 60008

TEL: 224-318-2140 FAX: 224-735-3514

MRV ARCHITECTS, INC. 2017

ALL DRAWINGS, SPECIFICATIONS, PLANS AND CONCEPTS ARE INSTRUMENTS OF SERVICE AND THEREFORE ARE PROPERTY OF MRV ARCHITECTS, INC. THEY MAY NOT BE REUSED, COPIED OR REPRODUCED WITHOUT PERMISSION AND EXPRESS WRITTEN CONSENT FROM MRV ARCHITECTS, INC.

C:\Users\Mario\Documents\MRV_Architects\eSeal_E_Valentini-Mod

TACO BELL, EXPLORER

MEDIUM - 40

CONTRACT DATE: 03.19.18
BUILDING TYPE: EXPLORER MED40
PLAN VERSION: JANUARY, 2019
SITE NUMBER: XXX-XXX
STORE NUMBER: XX-XXXX

TACO BELL

2707 N. GRANDVIEW BLVD. WAUKESHA, WI

PROPOSED SITE PLAN

SP1.0

SITE PLAN 1" = 250'-0" **1**


Calculation Summary					
Label	Avg	Max	Min	Avg/Min	Max/Min
EXTENDED	3.20	9.1	0.0	N.A.	N.A.
PARKING LOT & DRIVE-THRU SURFACE	5.46	9.1	2.3	2.37	3.96

LIGHT LEVELS ARE MAINTAINED FOOT-CANDLES, INITIAL LEVELS ARE SLIGHTLY HIGHER

Luminair	Luminaire Schedule									
Symbol	Qty	Label	Arrangement	Lum. Lumens	LLF	Lum. Watts	Description			
─	2	А	SINGLE	40845	0.900	395	VPL-96L-395-4K7-3-UNV-A-DBT / SES-25-40-01-A-B3-DB			
—	1	В	SINGLE	39921	0.900	395	VPL-96L-395-4K7-4-UNV-A-DBT / SES-25-40-01-A-B3-DB			
	2	С	SINGLE	40848	0.900	395	VPL-96L-395-4K7-5QM-UNV-A-DBT / SES-25-40-01-A-B3-DB			

FIXTURES ARE 395W 4000K LED

POLES ARE 25'-0" FOR AN OVERALL FIXTURE HEIGHT OF 27'-6" A.F.G.





ARCHITECTS, INC.

ROLLING MEADOWS, IL 60008

TEL: 224-318-2140 FAX: 224-735-3514

MRV ARCHITECTS, INC. 2017

ALL DRAWINGS, SPECIFICATIONS, PLANS AND CONCEPTS ARE INSTRUMENTS OF SERVICE AND THEREFORE ARE PROPERTY OF MRV ARCHITECTS, INC. THEY MAY NOT BE REUSED, COPIED OR REPRODUCED WITHOUT PERMISSION AND EXPRESS WRITTEN CONSENT FROM MRV ARCHITECTS, INC.






BUILDING TYPE: EXPLORER MED40 PLAN VERSION: SITE NUMBER: STORE NUMBER: XX-XXXX

TACO BELL

2707 N. GRANDVIEW BLVD. WAUKESHA, WI

PHOTOMETRIC SITE PLAN



1 1x8 DOG-EARED ROUGH SAWN —CEDAR (KILN DRIED) - ATTACH TO

RAILS WITH GALV. DECK SCREWS

2"x2"x1/4" ANGLE FRAME, WELDED

--6" WELD COLLAR HINGE W/ GREASE ZERK - DETAIL "A"

- CONC. FILL TO DEPTH OF PIPE

CANE BOLT

WEST ELEVATION

ARCHITECTS, INC.

TEL: 847-373-5005 FAX: 224-735-3514

Lake Geneva, Wisconsin 53147

ASSOCIATES, LLC

ANDSCAPE ARCHITECTURE

HELLER &

P.O. Box 1359

ph 262.639.9733 david@wdavidheller.com

BUILDING TYPE: EXPLORER MED40
PLAN VERSION: MARCH, 2017
SITE NUMBER: XXX-XXX
STORE NUMBER: XXXXX

TACO BELL

2707 N. GRANDVIEW BLVD, WAUKESHA, WISCONSIN

SHEET TITLE

OVERALL LANDSCAPE PLAN



MASONRY TRASH ENCLOSURE

NORTH / SOUTH ELEVATIONS

- GRADE

CONCRETE FOOTING



- 1. Contractor responsible for contacting Diggers Hotline (811 or 800-242-8511) to have site marked prior to excavation or planting.
- 2. Contractor to verify all plant quantities shown on Plant & Material List and landscape planting symbols and report any discrepancies to Landscape Architect or General Contractor.
- 3. All plantings shall comply with standards as described in American Standard of Nursery Stock Z60.1 ANSI (latest version). Landscape Architect reserves the right to inspect, and potentially reject any plants that are inferior, compromised, undersized, diseased, improperly transported, installed incorrectly or damaged. No sub-standard "B Grade" or "Park Grade" plant material shall be accepted. Plant material shall originate from nursery(ies) with a similar climate as the planting site.
- 4. Any potential plant substitutions must be approved by Landscape Architect or Owner. All plants must be installed as per sizes indicated on Plant & Material Schedule, unless approved by Landscape Architect. Any changes to sizes shown on plan must be submitted in writing to the Landscape Architect prior to installation.
- 5. Topspoil in Parking Lot Islands (if applicable): All parking lot islands to be backfilled with topsoil to a minimum depth of 18" to insure long-term plant health. Topsoil should be placed within 3" of finish grade by General Contractor / Excavation Contractor during rough grading operations/activity. The landscape contractor shall be responsible for the fine grading of all disturbed areas, planting bed areas, and lawn areas. Crown all parking lot islands a minimum of 6" to provide proper drainage, unless otherwise specified.
- 6. Tree Planting: Plant all trees slightly higher than finished grade at the root flare. Remove excess soil from the top of the root ball, if needed. Remove and discard non-biodegradable ball wrapping and support wire. Removed biodegradable burlap and wire cage (if present) from the top $\frac{1}{3}$ of the rootball and carefully bend remaining wire down to the bottom of the hole. Once the tree has been placed into the hole and will no longer be moved, score the remaining $\frac{2}{3}$ of the burlap and remove the twine. Provide one slow release fertilizer packets (per 1" caliper) for each tree planted.
- 7. Tree Planting: Backfill tree planting holes 80% existing soils removed from excavation and 20% Soil Amendments (see Note 11). Avoid air pockets and do not tamp soil down. Discard any gravel, rocks, heavy clay, or concrete pieces. When hole is $\frac{2}{3}$ full, trees shall be watered thoroughly, and water left to soak in before proceeding to fill the remainder of the hole. Water again to full soak in the new planting. Each tree shall receive a 3" deep, 4-5' diameter (see planting details or planting plan) shredded hardwood bark mulch ring / saucer around all trees. Do not build up any mulch onto the trunk of any tree. Trees that are installed incorrectly will be replaced at the time and expense of the Landscape Contractor.
- 8. Shrub Planting: All shrubs to be planted in groupings as indicated on the Landscape Plan. Install with the planting of shrubs a $\frac{50}{50}$ mix of Soil Amendments with blended, pulverized topsoil. Install topsoil into all plant beds as needed to achieve proper grade and displace undesirable soils (see planting detail). Remove all excessive gravel, clay and stones from plant beds prior to planting. When hole(s) are $\frac{2}{3}$ full, shrubs shall be watered thoroughly, and water left to soak in before proceeding. Provide slow-release fertilizer packets at the rater of 1 per 24" height/diamter of shrub at planting.
- 9. Mulching: All tree rings to receive a 3" deep layer of high quality shredded hardwood bark mulch (not pigment dyed or enviro-mulch). All shrub planting and perennial planting bed areas (groupings) shall receive a 2-3" layer of shredded hardwood bark mulch, and groundcover areas a 1-2" layer of the same mulch. Do not mulch annual flower beds (if applicable). Do not allow mulch to contact plant stems and tree trunks.
- 10. Edging: All planting beds shall be edged with a 4" deep spade edge using a flat landscape spade or a mechanical edger. Bedlines are to be cut crisp, smooth as per plan. A clean definition between landscape beds and lawn is required. Pack mulch against lawn edge to hold in place.
- 11. Plant bed preparation/Soil Amendment composition: All perennial, groundcover and annual areas (if applicable) are required to receive a blend of organic soil (Soil Amendments) amendments prior to installation. Roto-till the following materials at the following ratio, into existing soil beds or installed topsoil beds to a depth of approximately 8"-10". Containerized and balled & burlapped plant material should be back-filled with amended soil:

Per 100 SF of bed area (Soil Amendment composition)

3/4 CY Peat Moss or Mushroom Compost

A uniform coverage through all turf areas

3/4 CY blended/pulverized Topsoil

 $\frac{1}{4}$ CY composted manure

In roto-tilled beds only, also include in above mixture:


2 lbs Starter Fertilizer

12. Installation preparation for all seeded areas: remove/kill off any existing unwanted vegetation prior to seeding. Prepare the topsoil (if adequate or provide as in item #6 above) and seed bed by removing all surface stones 1" or larger. Apply a starter fertilizer (20-10-5, or approved comparable) and specified seed uniformly at the specified rate, and provide mulch covering suitable to germinate and establish turf. Provide seed and fertilizer specifications to Landscape Architect and Owner prior to installation. Erosion control measures are to be used in swales and on slopes in excess of 1:3 and where applicable (see Civil Engineering Drawings). Methods of installation may vary are the discretion of the Landscape Contractor on his/her responsibility to establish and guarantee a smooth, uniform, quality turf. A minimum of 2" of blended, prepared and non-compacted topsoil is required for all lawn areas. If straw mulch is used as a mulch covering, a tackifier may be necessary to avoid wind dispersal of mulch covering. Marsh hay containing reed canary grass is NOT acceptable as a mulch


An acceptable quality seed installation is defined as having: No bare spots larger than one (1) square foot No more than 10% of the total area with bare areas larger than one (1) square foot


- 13. Warranty and Replacements: All plantings are to be watered thoroughly at the time of planting, through construction and upon completion of project as required. Trees, Evergreens, and Shrubs (deciduous and evergreen) shall be guaranteed (100% replacement) for a minimum of one (1) year from the date of project completion. Perennials, groundcovers, and ornamental grasses shall be guaranteed for a minimum of one (1) growing season. Perennials, groundcovers, and ornamental grasses planted after September 15th shall be guaranteed through May 31st of the following year. Only one replacement per plant will be required during the warranty period, except for losses or replacements due to failure to comply with specified requirements. Watering and general ongoing maintenance instructions are to be supplied by the Landscape Contractor to the Owner upon completion of the project.
- 14. The Landscape Contractor is responsible for the watering and maintenance of all landscape areas for a period of 45 days after the substantial completion of the landscape installation. This shall include all trees, shrubs, evergreens, perennials, ornamental grasses, turf grass, no-mow grass, and native prairie seed mix / stormwater seed mix. Work also includes weeding, edging, mulching (only if required), fertilizing, trimming, sweeping up grass clippings, pruning and deadheading.
- 15. Project Completion: Landscape Contractor is responsible to conduct a final review of the project, upon completion, with the Landscape Architect, Client or Owner / Client Representative, and the General Contractor to answer questions, provide written care instructions for new plantings and turf, and insure that all specifications have been met.


LANDSCAPE GENERAL NOTES



PLANTING & HARDSCAPE DETAILS









WATER IMMEDIATELY AFTER PLANTING W A THOROUGH AND DEEP, SLOW RELEASE





P.O. Box 1359 Lake Geneva, Wisconsin 53147 ph 262.639.9733 david@wdavidheller.com

FAX: 224-735-3514












Remove 36" Elm tree at the north end of lot


Remove 6" Maple trees along the west lot line








SPECIFICATION / NOTES





Reinder's Deluxe 50 Seed Mix (800-785-3301): 20% Kentucky Bluegrass (Sod Quality) 15% Newport Kentucky Bluegrass 15% Ken Blue Kentucky Bluegrass

15% Quebec Perennial Ryegrass 10% Fiesta III Perennial Ryegrass Seed at rate of 150-200# per acre

25% Creeping Red Fescue PLANT & MATERIAL LIST


CONTRACT DATE: BUILDING TYPE: EXPLORER MED40 MARCH, 2017 PLAN VERSION: SITE NUMBER: XXX-XXX STORE NUMBER: XXXXX

TACO BELL

2707 N. GRANDVIEW BLVD, WAUKESHA, WISCONSIN

SHEET TITLE

LANDSCAPE DETAILS, NOTES & **SCHEDULES**



FLOOR PLAN NOTES

D

WALL LEGEND

ALLOW THE G.C. FLEXIBLITY.)

HEIGHT U.O.N. FINISH AS SCHEDULED.

- KITCHEN WALLS AND DINING ROOM CLOSET:

ARCHITECTS, INC.

ROLLING MEADOWS, IL 60008

MRV ARCHITECTS, INC. 2017

ALL DRAWINGS, SPECIFICATIONS, PLANS AND CONCEPTS ARE INSTRUMENTS OF SERVICE AND THEREFORE ARE PROPERTY OF MRV ARCHITECTS, INC. THEY MAY NOT BE REUSED, COPIED OR REPRODUCED WITHOUT PERMISSION AND EXPRESS WRITTEN CONSENT FROM MRV ARCHITECTS, INC.

EXPLORER MEDIUM - 40

BUILDING TYPE: EXPLORER MED40

XXX-XXX


XX-XXXX


2707 N. GRANDVIEW BLVD.

WAUKESHA, WI

FLOOR PLAN

KEY NOTES





KEYNOTES

SYM.	QTY.	ITEM	SYM.	QTY.	
(D-581)	1	PINE PLANK SETTEE BOOTHS - 48"	(D-721)	2	24" X 42" ADA TABLE TOP - PLYWOOD
(D-582)	2	PINE PLANK SETTEE BOOTHS - 60"	(D-723)	4	24" X 42" TABLE TOP - PLYWOOD
(D-620)	31	RETRO CHAIR - 18"	(D-750)	TBD *	WINDOW SILL
(D-623)	6	BARREL BARSTOOL - 29"	(D-753)	TBD *	WAINSCOTING
(D-640)	1	SERVICE COUNTER & POS STATION	(D-755)	TBD *	CHAIRRAIL
(D-646)	1	CONDIMENT COUNTER - RECTANGLE	* CONS		O PROVIDE LINEAR FOOTAGE FOR SILLS, CHAIR RAILS
(D-647)	1	WASTE ENCLOSURE - SINGLE	AND 3H	NOUDS.	
(D-648)	1	WASTE ENCLOSURE - DOUBLE			
(D-655)	1	WB HUB TABLE - 72"			
(D-658)	1	WB HUB TABLE ADA - 48"			
(D-700)	4	22" X 22" X 28.5"H FREE STANDING TABLE BASE			
(D-703)	12	22" X 5.5" X 28.5"H FREE STANDING TABLE BASE			
(D-720)	4	24" X 19" TABLE TOP - PLYWOOD			

SEATING PACKAGE - BY SEATING VENDOR U.O.N. (TOTAL SEATS = 43 INT)

⟨x⟩	QTY.	ITEM	REMARKS					
G 20	2 1	SAUCE PACKET COMPILATION - ALCOVE ARTWORK 9'-5" X 4'-2" 17'-5" x 4'-2"	SEE A7.1 AND A8.0 FOR LOCATION					
(G21)		HOT SAUCE POP ART	OPT. ALCOVE ARTWORK					
(G22)	1	EMOJIIS, 28"X40"	SEE A8.0 FOR LOCATION					
(G23)	1	LINEAR SAUCES, 28"X40"	SEE A8.0 FOR LOCATION					
(G24)	1	CONCRETE, 28"X40"	SEE A8.0 FOR LOCATION					
(G25)	1	MASH UP 1, 28"X40"	SEE A8.0 FOR LOCATION					
(G26)	1	MASH UP 2, 28"X40"	SEE A8.0 FOR LOCATION					
ARTWORK SCHEDULE D								

			EQUIPMENT/SEATING PLAN 1/4"=1'-0"	A
DECOR 1. REFER TO SC SHEETS FOR SCOPE OF WORK RESPON 2. (H) - SYMBOL DENOTES A HIGH TABLE OR DINING CO 3. (HC)- SYMBOL DENOTES A HANDICAP ACCESSIBLE TABLE	UNTER WITH STOOLS.		1 HOOD FIRE SUPPRESSION SYSTEM (ANSUL R-102 OR EQUAL). 2 SEE SHEET A1.1 FOR SECURITY DOOR PACKAGE. 3 MAINTAIN 36" MIN CLEAR AISLE EGRESS PATHS TO EXIT DOORS. 4 30" x 48" CLEAR FLOOR SPACE FOR HANDICAP ACCESS.	
			5 ALERT LIGHT BOX FOR 3-COMP POWER SOAK. 6 PULL STATION @ 3'-8" A.F.F. 7 GAS LINE DOWN TO EQUIPMENT. 8 COORDINATE LOCATION OF HORIZ PVC SYRUP CHASE THRU WALL TO COU	UNTE
GENERAL NOT	ES C) 1	10) SWITCHGEAR / ELECTRIC PANELS.	
STORAGE TYPE	LINEAR FT.		11 ROOF LADDER, SEE DETAILS 4 & 7/A6.0. 12 8' LADDER.	
DRY STORAGE COLD STORAGE	53 25		13 SAFE. 14 SPLASH GUARD. SEE 9 / A6.3.	
FROZEN STORAGE	10			

C2

SHELVING QUANTITIES REQUIRED

ARCHITECTS, INC.

TEL: 224-318-2140 FAX: 224-735-3514

MRV ARCHITECTS, INC. 2017

ALL DRAWINGS SPECIFICATIONS PLANS AND

ROLLING MEADOWS, IL 60008

ALL DRAWINGS, SPECIFICATIONS, PLANS AND CONCEPTS ARE INSTRUMENTS OF SERVICE AND THEREFORE ARE PROPERTY OF MRV ARCHITECTS, INC. THEY MAY NOT BE REUSED, COPIED OR REPRODUCED WITHOUT PERMISSION AND EXPRESS WRITTEN CONSENT FROM MRV ARCHITECTS, INC.

C:\Users\Martid\Documents\MRV_Architectste\Sea_L_Valentini-Model.jpg



CONTRACT DATE: 03.19.18
BUILDING TYPE: EXPLORER MED40
PLAN VERSION: JANUARY, 2019
SITE NUMBER: XXX-XXX
STORE NUMBER: XX-XXXX


TACO BELL


2707 N. GRANDVIEW BLVD. WAUKESHA, WI

EQUIPMENT AND SEATING PLAN

A2.0

PLOT DATE:





EXTERIOR FINISH SCHEDULE

MRV

ARCHITECTS, INC.

ROLLING MEADOWS, IL 60008
TEL: 224-318-2140 FAX: 224-735-3514

MRV ARCHITECTS, INC. 2017

ALL DRAWINGS, SPECIFICATIONS, PLANS AND CONCEPTS ARE INSTRUMENTS OF SERVICE AND THEREFORE ARE PROPERTY OF MRV ARCHITECTS, INC. THEY MAY NOT BE REUSED, COPIED OR REPRODUCED WITHOUT PERMISSION AND EXPRESS WRITTEN CONSENT FROM MRV ARCHITECTS, INC.

C:\Users\MarioDocuments\MRV_Archlects\alpha\Seel_IL_\Valentin\Model.jpg



EXPLORER MEDIUM - 40

\(\lambda \)

CONTRACT DATE: 03.19.18

BUILDING TYPE: EXPLORER MED40

PLAN VERSION: JANUARY, 2019

SITE NUMBER: XXX-XXX

STORE NUMBER: XX-XXXX


TACO BELL

2707 N. GRANDVIEW BLVD. WAUKESHA, WI

EXTERIOR ELEVATIONS

A4.(

KEY NOTES





MRV ARCHITECTS, INC. 2017

ALL DRAWINGS, SPECIFICATIONS, PLANS AND CONCEPTS ARE INSTRUMENTS OF SERVICE AND THEREFORE ARE PROPERTY OF MRV ARCHITECTS, INC. THEY MAY NOT BE REUSED, COPIED OR REPRODUCED WITHOUT PERMISSION AND EXPRESS WRITTEN CONSENT FROM MRV ARCHITECTS, INC.

TEL: 224-318-2140 FAX: 224-735-3514

C:\Users\Mario\Documents\MRV_Architectris\Geal_SL_Valentin-Model.jpg

TACO
BELL

EXPLORER
MEDIUM - 40

LEFT SIDE ELEVATION 1/4"=1'-0"

CONTRACT DATE: 03.19.18
BUILDING TYPE: EXPLORER MED40
PLAN VERSION: JANUARY, 2019
SITE NUMBER: XXX-XXX
STORE NUMBER: XXX-XXXX


TACO BELL


2707 N. GRANDVIEW BLVD. WAUKESHA, WI

EXTERIOR ELEVATIONS

A4.1

PLOT DATE:





FRONT ELEVATION 1/4" = 1'-0" C

REAR ELEVATION 1/4" = 1'-0" B



MRV

ARCHITECTS, INC.

MRV ARCHITECTS, INC. 2017

ALL DRAWINGS, SPECIFICATIONS, PLANS AND CONCEPTS ARE INSTRUMENTS OF SERVICE AND THEREFORE ARE PROPERTY OF MRV ARCHITECTS, INC. THEY MAY NOT BE REUSED, COPIED OR REPRODUCED WITHOUT PERMISSION AND EXPRESS WRITTEN CONSENT FROM MRV ARCHITECTS, INC.

ROLLING MEADOWS, IL 60008

TEL: 224-318-2140 FAX: 224-735-3514



CONTRACT DATE: 03.19.18

BUILDING TYPE: EXPLORER MED40

PLAN VERSION: MARCH, 2017

SITE NUMBER: XXX-XXX

STORE NUMBER: XX-XXXX

TACO BELL

2707 N. GRANDVIEW BLVD. WAUKESHA, WI

RENDERED EXTERIOR ELEVATIONS

A4.0

PLOT DATE:



Cat.#

Job

Type



Approvals

SPECIFICATIONS

Intended Use:

The Beacon Viper luminaire is available in two sizes with a wide choice of different LED wattage configurations and optical distributions designed to replace HID lighting up to 1000W MH or HPS. Luminaires are suitable for wet locations.

Construction:

- Manufactured with die cast aluminum.
- Coated with a polyester finish that meets ASTM B117 corrosion test requirements and ASTM D522 cracking and loss of adhesion test requirements.
- External hardware is corrosion resistant.
- One piece optical cartridge system consisting of an LED engine, LED lamps, optics, gasket and stainless steel bezel.
- Cartridge is held together with internal brass standoffs soldered to the board so that it can be field replaced as a one piece optical system.
- Two-piece silicone and microcellular polyurethane foam gasket ensures a weather-proof seal around each individual optic.

Electrical:

- Luminaire accepts 100V through 277V, 50 Hz to 60 Hz (UNV), 347V, or 480V input.
- Power factor is ≥ .90 at full load.
- All electrical components are rated at 50,000 hours at full load and 25°C ambient conditions per MIL- 217F Notice 2.
- Dimming drivers are standard, but must contact factory to request wiring leads for purpose of external dimming controls.
- Component-to-component wiring within the luminaire may carry no more than 80% of rated load and is certified by UL for use at 600VAC at 90°C or higher.
- Plug disconnects are certified by UL for use at 600 VAC, 13A or higher. 13A rating applies to primary (AC) side only.
- Fixture electrical compartment shall contain all LED driver components and shall be provided with a push-button terminal block for AC power connections.
- Optional 7-pin ANSI C136.41-2013 twist-lock photo control receptacle available. Compatible with ANSI C136.41 external wireless control
- Surge protection 20kA.
- Lifeshield™ Circuit protects luminaire from excessive temperature. The device shall activate at a specific, factory-preset temperature, and progressively reduce power over a finite temperature range. Operation shall be smooth and undetectable to the eye. Thermal circuit is designed to "fail on", allowing the luminaire to revert to full power in the event of an interruption of its power supply, or faulty wiring connection to the drivers. The device shall be able to co-exist with other 0-10V control devices (occupancy sensors, external dimmers, etc.).

Controls/Options:

- Available with an optional passive infrared (PIR) motion sensor capable of detecting motion 360° around the luminaire. When no motion is detected for the specified time, the motion response system reduces the wattage to factory preset level, reducing the light level accordingly. When motion is detected by the PIR sensor, the luminaire returns to full wattage and full light output. Please contact Beacon Products if project requirements vary from standard configuration
- Available with Energeni for optional set dimming, timed dimming with simple delay, or timed dimming based on time of night (see www.beaconproducts.com/products/energeni)
- In addition, Viper can be specified with SiteSync™ wireless control system for reduction in energy and maintenance costs while optimizing light quality 24/7. For more details, see ordering information or visit: www.hubbelliighting.com/sitesync

Installation:

 Mounting options for horizontal arm, vertical tenon or traditional arm mounting available. Mounting hardware included.

Finish:

- IFS polyester powder-coat electrostatically applied and thermocured. IFS finish consists of a five stage pretreatment regimen with a polymer primer sealer and top coated with a thermoset super TGIC polyester powder coat finish.
- The finish meets the AAMA 2604 performance specification which includes passing a 3000 hour salt spray test for corrosion resistance and resists cracking or loss of adhesion per ASTM D522 and resists surface impacts of up to 160 inch-pounds.

Certifications/Ratings:


- Listed to UL 1598 and CSA22.2#250.0 for wet locations
- 3G rated for ANSI C136.31 high vibration applications with MAF mounting
- IDA approved

Warranty:


Five year limited warranty for more information visit: www.hubbelllighting.com/resources/warranty

PRODUCT IMAGE(S)





MOUNTING OPTIONS



CERTIFICATIONS/LISTINGS









- 5.50" -

VPL SERIES LED ENGINE CCT/CRI ROTATION **VOLTAGE COLOR OPTIONS** VPL Viper **64L-135** 135W LED array 3K7 3000K, 70 CRI **UNV** 120-277V **DBT** Dark Bronze Textured F Fusing Leave blank for no 80L-180 180W LED array 4K7 4000K, 70 CRI **120** 120V **BMT** Black Matte Textured **BSP** Bird Spikes L5 Optic rotation left 80L-235 235W LED array 208 208V PS Platinum Silver Smooth BC Backlight control (limited 5K7 5000K, 70 CRI R5 Optic rotation right to Type 4W only) 96L-220 220W LED array WHT White Textured 240 240V 96L-280 280W LED array **277** 277V CC Custom Color (RAL#) 96L-315 315W LED array **347** 347V **96L-395** 395W LED array 480 480V DISTRIBUTION FR Type 1/Front Row 2 Type 2 **3** Type 3 4 Type 4 4W Type 4 Wide 5QM Type 5QM 5QN Type 5QN 5R Type 5R (rectangular) 5W Type 5W (round wide) **CONTROL OPTIONS** MOUNTING **7PR** 7-Pin Receptacle only (shorting cap, photo control, or wireless control provided by others) A Rectangular Arm (formerly RA) 7PR-SC 7-Pin Receptacle w/Shorting Cap MAF Mast Arm Fitter (formerly SF2) 7PR-TL 7-Pin Receptacle w/Twist Lock photo control K Knuckle (formerly PK2) limit to 45° tilt SCP^{1,2,6} Programmable Occupancy Sensor w/ daylight control (120-277 volts only) WB Wall Bracket

PRECOMMISSIONED SITESYNC ORDERING INFORMATION: When ordering a fixture with the SiteSync lighting control option, additional information will be required to complete the order. The SiteSync Commissioning Form or alternate schedule information must be completed. This form includes Project location, Group information, and Operating schedules. For more detailed information please visit www.HubbellLighting.com/sitesync or contact Hubbell Lighting tech support at (800) 345-4928.

SiteSync fixtures with Motion control (SWPM) require the mounting height of the fixture for selection of the lens.

Examples: VP-L/80L-235/4K7/3/UNV/A/DBT/SWP/ VP-L/80L-235/4K7/3/UNV/A/DBT/SWPM-20F/

SiteSync with Motion Control

SiteSync only

- 1 Not available with other sensor, control, or photo control receptacle options
- Specify mounting height
- ³ Specify routine setting code (example GENI-04). See ENERGENI brochure and instructions for setting table and options. Not available with sensor or SiteSync options.
- ⁴ Specify group and zone at time of order. See www.hubbelllighting.com/sitesync for further details. Order at least one SiteSync interface Accessory SWUSB or SWTAB. Each option contains SiteSync License, GUI, and Bridge Node
- $^{\mbox{\tiny 5}}$ Only available with 1A, 2, 3, 4, 4W and 5R distributions
- Order at least one SCP-REMOTE per project location to program and control


- WSP^{1,2} WASP Occupancy Sensor w/ daylight control (347 or 480 volts only)
- **GENI-XX**³ ENERGENI
- SWP1,4 SiteSync Pre-Commission
- SWPM1,2,4 SiteSync Pre-Comm w/ Sensor

Accessories and Services (Ordered Separately)

Catalog Number	Description
SWUSB*	SiteSync loaded on USB flash drive (Windows based only)
SWTAB*	SiteSync Windows Tablet
SWBRG+	SiteSync Wireless Bridge Node

- *When ordering with SiteSync, one of the interface options must be chosen and ordered separately. Each option contains the SiteSync License, GUI and Bridge Node.
- + If needed, an additional Bridge Node can be ordered.









## PLEDS CURRENT SYSTEM WAITS STRIBUTION TYPE 120 MINES 1PW B U C 100 MINES	PERFORM	ANCE DATA				5K					4K					3K										
CLED'S WATS				(5000K nominal, 70 CRI)			(4000K nominal, 70 CRI)					· ·														
64 625 mA	# LED'S	CURRENT		DISTRIBUTION TYPE	LUMENS	LPW ¹	В	U	G	LUMENS	LPW ¹	В	U	G	LUMENS	LPW ¹	В	U	G							
Second S						1					+		_					_	2							
64 625 mA							_						_	_					_							
64 625 mA						1					 	_		_				_								
SON 18023 131 4 0 0 189590 135 4 0 0 16165 177 4 0 0 189590 135 4 0 0 16165 177 4 0 0 189590 135 4 0 0 16165 177 4 0 0 189590 135 4 0 0 15165 177 4 0 0 189590 135 4 0 0 15165 177 4 0 0 189590 135 4 0 0 15165 177 4 0 0 189590 135 4 0 0 15165 177 4 0 0 189590 135 4 0 0 15165 177 4 0 0 2 177 189590 177 2 0 0 2 177 2 0 0 2 177 2 0 0 2 177 2 0 0 2 177 2 0 0 2 177 2 0 0 2 177 2 0 0 2 177 2 0 0 2 177 2 0 0 2 177 2 0 0 1 177	64	625 mA	135W	135W						3				_				_		3						
SR						+						_	_	_			-	_	2							
SW							_		_				-	_				_								
2 21965 121 3 0 3 22645 125 3 0 3 19701 109 2 0 4 3 3 22645 125 3 0 3 19701 109 2 0 4 4 21502 3 0 3 22645 125 3 0 3 19701 109 2 0 4 2 0 4 22683 125 3 0 3 19701 109 2 0 4 4 2 2 2 0 4 19285 106 2 0 4 4 2 2 2 0 4 19285 106 2 0 4 2 2 2 2 2 2 2 2 2					16498	+	4	_	2			4	-				4	_	2							
Section Sect								_					_	-				_	2							
No column No c						+		-					_	-												
SOM 22005 121 4 0 2 22686 125 4 0 2 19736 109 4 0 2 50N 22979 177 4 0 1 23689 131 4 0 1 1 2010 114 4 0 0 0 5R 22197 172 4 0 4 22884 126 4 0 4 19909 110 4 0 4 50 0 3 18867 104 4 0 3 0 4 22884 126 4 0 4 19909 110 4 0 4 1909 10 4 0 3 1 1 1 1 1 1 1 1 1						+		_					_	-				_								
SON 22979 127 4 0 1 23689 131 4 0 1 20610 114 4 0 0 0 5	80	700 mA	180W			1	_		_		+	_	_						4							
SR 22197 122 4 0 4 22884 126 4 0 4 19909 110 4 0 4 58W 21035 116 5 0 3 21886 120 5 0 3 18867 104 4 0 3 2 2 2 2 2 2 2 2 2						1	+				+		_	_												
96 PTODMA 220W AW 25070 118 3 0 4 22638 132 2 0 2 22638 109 3 0 4 2 0 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2						+					 			_												
80 875 mA 235W 4 2369 102 3 0 3 3 27148 118 3 0 4 23619 102 3 0 3 3 6875 mA 2369 102 3 0 3 3 0 4 27148 118 3 0 4 23659 103 3 0 4 4 25777 112 2 0 4 26575 115 2 0 5 23120 100 2 0 4 2675 105 2 1 0 1 0 1 0 1 0 1 0 1 0 1 0 1 0 1 0 1				5W		116	5		3			5	_	3			4		3							
80 875 mA 235W 4W 25675 111 3 0 4 27194 118 3 0 4 23689 103 3 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0						+							_													
80 875 mA 235W 4W 256775 1112 2 0 0 4 26675 115 2 0 5 23120 100 2 0 1 4 4						+	_						-	_				_								
80 875 mA 235W 4W 25675 111 3 0 4 26469 115 3 0 1 20028 100 3 0 4 0 2 50M 256M 27543 119 5 0 1 22799 118 4 0 2 23661 103 4 0 2 50M 256M 27543 119 5 0 1 22400 123 5 0 1 24708 107 5 0 1 1 50 0 1 24708 107 5 0 1 1 24708 107 5 0 1 1 24708 107 5 0 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2			235W			+							_	+				_								
96 1000mA 260m 27548 119 5 0 1 28400 123 5 0 1 24708 107 5 0 1 1 1 1 1 1 1 1 1	80	875 mA		235W		25675					26469	115	3	_	-	23028		3	_	4						
SR 26611 115 5 0 5 27434 119 5 0 5 23868 104 4 0 4 0 4								+	_						_	_				_						
96 875 mA 280W 4W 30810 114 3 0 4 32577 118 3 0 4 28390 100 3 0 4 4 3983 112 2 0 2 2 2974 100 2 0 4 2 2074 100 2 0 4 4 30833 112 2 0 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2								_					_	<u> </u>				_								
96													_													
96						1	_					_	_	_												
96						1					 		_	_				_								
96			mA 220W			+							_	_												
SON 27575 127 5 0 1 28427 131 5 0 1 24732 114 5 0 1 0 1 0 1 0 0 1 0 0	96	700 mA		220W	220W	220W	220W	220W	220W	220W			+	_	_			-		_	_				_	4
96 1000mA 315W² 5R									+							-	_				_					
96								_					-					_								
96								_					_													
96 875 mA 280W 4W 30810 111 3 0 5 31889 115 2 0 5 27744 100 2 0 5 5 0						+		_			i 		_					_	2							
96 875 mA 280W 4W 30810 111 3 0 5 31889 115 2 0 5 27744 100 2 0 5 5						+	_	_					_			_										
96 875 mA 280W 4W 30810 111 3 0 5 31763 115 3 0 5 27634 100 3 0 4 50M 31657 114 5 0 3 32636 118 5 0 3 28393 103 4 0 2 50M 33058 119 5 0 1 34080 123 5 0 1 29650 101 5 0 1 5 0 5 50M 33058 119 5 0 1 34080 123 5 0 1 29650 101 5 0 1 5 0 5 50M 30262 109 5 0 4 31198 113 5 0 4 27142 98 5 0 3 3 664 118 5 0 3 28631 104 5 0 5 5 50 5 32921 119 5 0 1 5 28641 104 5 0 5 5 50 5 32921 119 5 0 1 5 28641 104 5 0 5 5 50 5 50 5 50 5 50 5 50 5						+					+		-													
96 1000mA 315W² 315W² 32802 104 3 0 5 0 1 34080 123 5 0 1 29650 101 5 0 1 5 0 5 5 0 5 32921 119 5 0 5 28641 104 5 0 5 5 0 5 32921 119 5 0 5 28641 104 5 0 5 5 0 5 32921 119 5 0 5 28641 104 5 0 5 5 0 5 32921 119 5 0 5 28641 104 5 0 5 5 0 5 32921 109 5 0 4 31198 113 5 0 4 27142 98 5 0 3 3 6 6 113 3 0 2 36769 117 3 0 2 31989 101 2 0 2 2 2 33725 107 3 0 4 34768 110 3 0 4 30248 96 3 0 4 4 33012 105 2 0 5 34033 108 2 0 5 32929 96 3 0 4 4 33012 105 2 0 5 34033 108 2 0 5 29609 94 2 0 5 5 50 3 33785 107 5 0 3 34830 110 5 0 3 30302 96 5 0 2 5 5 5 5 5 5 5 5 5	96	875 mA	280W			1	+		_		 		_	_				_	4							
96 1000mA 315W² 5R 31933 115 5 0 5 32921 119 5 0 5 28641 104 5 0 5 5 5 5 5 5 5 5						+					 			_			_		2							
96 1000mA 315W²																		_								
96								_					_					_	3							
96 1000mA 315W2 33782 107 3 0 5 34827 110 3 0 5 30299 96 3 0 4 4 33012 105 2 0 5 34033 108 2 0 5 29609 94 2 0 5 5QM 33785 107 5 0 3 34830 110 5 0 3 30302 96 5 0 2 5QM 35280 112 5 0 1 36371 115 5 0 1 31643 100 5 0 1 5R 34080 108 5 0 5 35134 111 5 0 5 30567 97 5 0 5 5W 32302 102 5 0 4 33301 106 5 0 4 28972 92 5 0 4 FR 39569 101 3 0 4 43125 110 3 0 3 37518 96 3 0 2 2 39569 101 3 0 4 40793 104 3 0 4 35490 91 3 0 4 3 39619 101 3 0 5 39763 101 3 0 5 34731 88 2 0 5 5QM 39623 101 5 0 3 40848 104 5 0 3 35538 90 5 0 3 5QN 41394 105 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5 5R 39969 102 5 0 5 41205 105 5 0 5 35					35666					36769	117	3	_		31989											
96													_													
96 1000mA 315W² 4W 32882 104 3 0 5 33899 107 3 0 5 29492 93 3 0 5 50M 33785 107 5 0 3 34830 110 5 0 3 30302 96 5 0 2 50M 35280 112 5 0 1 36371 115 5 0 1 31643 100 5 0 1 5 5 5 5 5 5 5 5 5																										
96 1225mA 350N 35280 112 5 0 1 36371 115 5 0 1 31643 100 5 0 1 5	96	1000mA	315W ²								i		_					_	5							
96 1225mA 3680 108 5 0 5 35134 111 5 0 5 30567 97 5 0 5 5													_	_					2							
96 1225mA 5W 32302 102 5 0 4 33301 106 5 0 4 28972 92 5 0 4 5 0 4 3125 110 3 0 3 37518 96 3 0 2 5 0 4 3125 110 3 0 4 35490 91 3 0 4 3 0 4 3125 110 3 0 4 35490 91 3 0 4 3 0 4 3125 110 3 0 5 35535 91 3 0 5 4 1 3125 110 3 0 5 35535 91 3 0 5 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1						1			_		+			-												
96 1225mA FR 39569 101 3 0 4 43125 110 3 0 3 37518 96 3 0 2 2 39569 101 3 0 4 40793 104 3 0 4 35490 91 3 0 4 3 39619 101 3 0 5 40845 104 3 0 5 35535 91 3 0 5 4 38723 98 3 0 5 39921 101 3 0 5 34731 88 2 0 5 4W 38570 98 3 0 5 39763 101 3 0 5 34594 88 3 0 5 50M 39623 101 5 0 3 40848 104 5 0 3 35538 90 5 0 3 50N 41394 105 5 0 1 42675 109 5 0 1 37127 95 5 0 1 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5											 		_						4							
96 1225mA 395W² 395W² 4W 38570 98 3 0 5 39921 101 3 0 5 34594 88 3 0 5 5 5QM 39623 101 5 0 3 40848 104 5 0 3 35538 90 5 0 1 5QN 41394 105 5 0 1 42675 109 5 0 1 37127 95 5 0 1 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5				FR	39569	101	3	0	4	43125	110	3	0	3	37518	96	3	0	2							
96 1225mA 395W² 4W 38570 98 3 0 5 39921 101 3 0 5 34731 88 2 0 5 5QM 39623 101 5 0 3 40848 104 5 0 3 35538 90 5 0 1 5QN 41394 105 5 0 1 42675 109 5 0 1 37127 95 5 0 1 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5						1							_	_				_	4							
96 1225mA 395W² 4W 38570 98 3 0 5 39763 101 3 0 5 34594 88 3 0 5 50M 39623 101 5 0 3 40848 104 5 0 3 35538 90 5 0 3 50M 41394 105 5 0 1 42675 109 5 0 1 37127 95 5 0 1 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5																										
5QM 39623 101 5 0 3 40848 104 5 0 3 35538 90 5 0 3 5QN 41394 105 5 0 1 42675 109 5 0 1 37127 95 5 0 1 5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5	96	1225mA	395W ²			1					•	3	-						5							
5R 39969 102 5 0 5 41205 105 5 0 5 35848 91 5 0 5						+						5	_	_		90		_	3							
									-					<u> </u>				_	5							
, , , , , , , , , , , , , , , , , , ,				5W	37877	97	5	0	4	39048	100	5	0	4	33986	87	5	0	4							

¹Lumen values are from photometric tests performed in accordance with IESNA LM-79-08. Data is considered to be representative of the configurations shown. Actual performance may differ as a result of end-user environment and application. ² 315W and 395W 3000K versions are not DLC QPL listed. Reference highlighted cells in table.







PHOTOMETRICS

Type FR - Front Row/Auto Optic


Type 2



Type 3





Type 4




Type 4W

Type 5W






Type 5QN



Type 5QM



Type 5R

ELECTRICAL DATA

	NUMBER OF	DRIVE CURRENT	INPUT VOLTAGE	SYSTEM POWER	CURRENT
# OF LEDS	DRIVERS	(mA)	(V)	(w)	(Amps)
			120		1.4
64	1	625 mA	277	135	0.6
			347 480		0.5 0.3
			120		1.8
80	2	700 mA	277	180	0.8
00	-	700 IIIA	347	100	0.6
			480		0.5
			120		2.4
80	2	875 mA	277	235	1.0
			347		0.8 0.6
			480 120		2.2
			277		1.0
96	2	700 mA	347	220	0.8
			480		0.6
			120		2.8
96	2	875 mA	277	200	1.2
90		6/5 IIIA	347	280	1.0
			480		0.7
			120		3.2
96	2	1000 mA	277	315	1.4
	_		347 480		1.1 0.8
			120		4.0
06	,	1225 mA	277	205	1.7
96	2	1225 mA	347	395	1.4
			480		1.0

PROJECTED LUMEN MAINTENANCE

AMBIENT TEMP.	0	25,000	50,000	¹TM-21-11 60,000	100,000	Calculated L70 (HOURS)
25°C / 77°C	1	0.98	0.97	0.97	0.96	>377,000

¹ Projected per IESNA TM-21-11

Data references the extrapolated performance projections for the 700mA base model in a 25°C ambient, based on 10,000 hours of LED testing per IESNA LM-80-08.

	AMBIENT TEMPERATURE						
0°C	32°F	1.03					
10°C	50°F	1.02					
20°C	68°F	1.00					
25°C	77°F	1.00					
30°C	86°F	0.97					
40°C	104°F	0.92					

Use these factors to determine relative lumen output for average ambient temperatures from 0-40 $^{\circ}$ C (32-104 $^{\circ}$ F).

DRILL PATTERN

