

1355 Josephine St. G
Waukesha, WI. 53186

Caleb Odegard
(262) 720-5694
missionsventures@yahoo.com

ESTIMATE

Missions Chimney-Roof

For Joe Yatzeck
214 W Laflin Ave.
Waukesha, WI.

Estimate Num 19555
Date May 31, 2019

Description	Quantity	Rate	Amount
Re tuck point entirety of the exposed above roof line chimney exterior masonry. 3 Story non walkable slope additional starter set up required. Historic Building restoration. Cut out all of the chimney mortar joints to uniformed depth. Antique style built chimney with several bump outs. Clean and chem prep the cut joints. Install new Type N Spec Mix mortar into the cut and prepped joints. Antique white color blend mortar. When mortar starts to set score mortar joints to insure watertight joints to prevent further chimney deterioration. Once mortar has set waterproof coat the exterior of the chimney brick and mortar to lock moisture out. Clean up and dispose of all left behind debris. Ensure that all joints are sealed and secure to prevent further deterioration and keep the chimney structurally sound. Remove the loose and damaged brick. Chimney Aprox. 2.5x3.5x6 with bumpouts.	1	\$4,350.00	\$4,350.00

Notes:

Previous caulking of the chimney is visible and not a solution to the structure of the chimney. The recommended repairs will keep the chimney structurally sound and stable as well as restore the natural look of the chimney.

Subtotal \$4,350.00

Total \$4,350.00

Balance Due \$4,350.00



ATTACHMENTS



Attachment #1



Attachment #2



Attachment #3



Attachment #4