

PLANT SCHEDULE					
SYMBOL	CODE	BOTANICAL / COMMON NAME	SIZE	CONTAINER	QTY
DECIDUOUS	TREES				
	AC	Acer x freemanii 'Celzam' / Celebration® Freeman Maple	2.5" Cal.	B&B	2
	GS	Gleditsia triacanthos inermis 'Shademaster' / Shademaster Honey Locust	2.5" Cal.	B&B	5
A CARACTER AND A CARACTER ANTER ANTE	GD	Gymnocladus dioica 'Espresso' / Kentucky Coffeetree	2.5" Cal.	B&B	4
	QB	Quercus bicolor / Swamp White Oak	2.5" Cal.	B&B	2
	QS	Quercus x schuettei / Swamp Bur Oak	2.5" Cal.	B&B	3
	ТА	Tilia americana 'Kromm' / Sweet Street™ American Linden	2.5" Cal.	B&B	5
- Cu - Cu - Cu - Cu - Cu - Cu - Cu - Cu	TG	Tilia cordata 'Greenspire' / Greenspire Littleleaf Linden	2.5" Cal.	B&B	1

1



D

Х

Х


THE UNDERGROUND UTILITY INFORMATION SHOWN ON THIS MAP IS BASED ON FIELD MARKINGS AND INFORMATION FURNISHED BY UTILITY COMPANIES AND THE LOCAL MUNICIPALITY. WHILE THIS INFORMATION IS BELIEVED TO BE RELIABLE, ITS ACCURACY AND COMPLETENESS CANNOT BE GUARANTEED.

EVERGREEN	TREES	1			1
	AC2	Abies concolor / White Fir	6` Ht.	B&B	5
	РВ	Pinus cembra 'Big Blue' / Big Blue Swiss Stone Pine	6` Ht.	B&B	7
And the second s	PS	Pinus strobus / White Pine	6` Ht.	B&B	6
ORNAMENTA		3			_
	AG	Amelanchier x grandiflora 'Autumn Brilliance' / Autumn Brilliance Apple Serviceberry	1.5" Cal (Multi-Stem)	B&B	2
DECIDUOUS	SHRUBS				
(\cdot)	AM	Aronia melanocarpa elata / Glossy Black Chokeberry	2` Ht.	Cont.	17
$\overbrace{\cdot}$	CS	Cornus sericea 'Alleman's Compact' / Dwarf Red Twig Dogwood	2` Ht.	Cont.	3
(\cdot)	CA	Corylus americana / American Hazelnut	3` Ht.	Cont.	7
$\overline{\bigcirc}$	SL	Diervilla lonicera 'Jewel' / Jewell Bush Honeysuckle	1.5` Ht.	Cont.	19
$\overline{(}$	FB	Fothergilla gardenii 'Beaver Creek' / Beaver Creek Dwarf Fothergilla	3 gal.	Cont.	15
$\overline{\bigcirc}$	HL	Hydrangea paniculata 'SMHPLQF' / Little Quick Fire® Panicle Hydrangea	1.5` Ht.	Cont.	3
E. Market Market	RG	Rhus aromatica 'Gro-Low' / Gro-Low Fragrant Sumac	3 gal.	Cont.	46
	SM	Syringa meyeri 'Palibin' / Dwarf Korean Lilac	2` Ht.	Cont.	7

3

2

EVERGREEN	SHRUB	S			
+	JP	Juniperus chinensis 'Kallays Compact' / Kallay Compact Pfitzer Juniper	3 gal.	Cont.	30
5	JF	Juniperus chinensis 'Sea Green' / Sea Green Juniper	2` Ht.	Cont.	3
+	JB	Juniperus sabina 'Blue Forest' / Blue Forest Juniper	3 gal.	Cont.	14
	тв	Thuja occidentalis 'Bail John' / Technito® Arborvitae	4` Ht.	B&B	6
ORNAMENT	AL GRAS	SES			
1997 - 19	СК	Calamagrostis x acutiflora 'Karl Foerster' / Karl Foerster Feather Reed Grass	1 gal.	Cont.	33
£ . 3	ST	Sporobolus heterolepis 'Tara' / Tara Prairie Dropseed	1 gal.	Cont.	10



LANDSCAPE GENERAL NOTES:

4

- 1. VERIFY EXISTING AND PROPOSED CONDITIONS, UTILITIES, PIPES, AND STRUCTURES, ETC. PRIOR TO BIDDING AND CONSTRUCTION.
- 2. INSPECT THE SITE PRIOR TO COMMENCING WORK. DOCUMENT IN WRITING AND PHOTOGRAPH EXISTING CONDITIONS WITHIN, AND IN AREAS ADJACENT TO THE LIMITS OF CONSTRUCTION. THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGES NOT DOCUMENTED IN THE PHOTOGRAPHS PRIOR TO COMMENCEMENT OF DEMOLITION ACTIVITIES.
- 3. COORDINATE THE INSTALLATION OF PLANT MATERIAL WITH INSTALLATION OF ADJACENT PAVEMENTS, DRAINAGE, CURB RELATED STRUCTURES WITH OTHER TRADES.
- 4. RESTORE AREAS OF THE SITE, OR ADJACENT AREAS, WHERE DISTURBED. DAMAGE CAUSED DURING LANDSCAPE INSTALLATION TO EXISTING CONDITIONS AND IMPROVEMENTS IS THE RESPONSIBILITY OF THE LANDSCAPE CONTRACTOR.
- 5. CONTRACTOR SHALL THOROUGHLY REVIEW ALL SPECIFICATIONS RELATED TO TREE PROTECTION, SOIL PREPARATION, TURF, GRASSES AND PLANTS. THESE SECTIONS PROVIDE ADDITIONAL INFORMATION ON MATERIALS AND SET STANDARDS FOR QUALITY AND INSTALLATION REQUIREMENTS.
- 6. PROVIDE 3" DOUBLE SHREDDED BARK MULCH FOR ALL PLANTED TREES, SHRUBS AND LANDSCAPE BEDS.




Landscape Plan

SHEET TITLE:

Х





SHEET

KEY	PL	.AN	

REV #	DESCRIPTION	DATE

REVISIONS

The Sigma Group <u>Phone</u>: 414.643.4200 Address:1300 W. Canal Street Milwaukee, WI 53233 Landscape Architect of Record - Rosheen Styczinski

MEP **RTM Engineering Consultants** Phone: 414.273.1432 Address: 316 N. Milwaukee Street, Suite 560 Milwaukee, WI 53202 Engineer of Record - Timothy Larsen, PE

Engineer of Record - Linda Johnson

Landscape Architect

P:262.945.7709 CIVIL TerraTec Engineering Phone: 262.377.9905 Address: W67N222 Evergreen Blvd., Suite 205 Cedarburg, WI 53012

Architect of Record - Jon P. Wallenkamp P:414.690.3197 Project Manager - Lee Anderson

Address: 10505 Corporate Drive, Suite 100 Pleasant Prairie, Wisconsin 53158

ARCHITECT Kueny Architects Phone: 262.857.8101

©2025 Kueny Architects L.L.C. - All Rights Reserved CONSULTANTS

10505 Corporate Drive, Pleasant Prairie, WI 53158 phone: 262.857.8101 web: www.kuenyarch.com

Issue Description OWNER:

0 Chapman Drive, Waukesha, WI 53189

Operations Center

Waukesha Water Utility

PROJECT ISSUE DATE:





PROJECT:

PLANTING QUALITY ASSURANCE

 PLANTS ARE TO BE INSPECTED UPON DELIVERY TO PROJECT SITE AND THE LANDSCAPE ARCHITECT OR OWNER'S PROJECT REPRESENTATIVE MAY REJECT ANY SPECIMENS NO LONGER MEETING THE SPECIFIED STANDARDS OR THAT HAVE BEEN DAMAGED IN TRANSIT.

2. ALL PLANT MATERIAL SHALL BE TRUE TO SPECIES AND VARIETY/HYBRID/CULTIVAR SPECIFIED, AND NURSERY GROWN IN ACCORDANCE WITH GOOD HORTICULTURAL PRACTICES, AND UNDER CLIMATIC CONDITIONS SIMILAR TO THOSE OF THE SITE LOCATION. SPECIMENS NURSERY-DUG TO BE REPLANTED SHALL HAVE BEEN FRESHLY DUG AND PROPERLY PREPARED FOR PLANTING.

3. TREES:

- 3.1. SHALL BE TRAINED IN DEVELOPMENT AND APPEARANCE AS TO BE SUPERIOR IN FORM. COMPACTNESS AND SYMMETRY. TREES WITH MULTIPLE LEADERS, UNLESS SPECIFIED
- OTHERWISE, AND SHRUBS WITH DAMAGED OR CUT MAINSTEM(S), WILL BE REJECTED.
- 3.2. WITH A DAMAGED, CUT OR CROOKED LEADER, ABRASION OF BARK, SUNSCALD, FROST CRACK DISFIGURING KNOTS, INSECTS (INCLUDING EGGS AND LARVAE) OR INSECT DAMAGE, CANKERS/CANKEROUS LESIONS OR FUNGAL MATS, MOLD, PREMATURELY-OPENED BUDS, OR CUTS OF LIMBS OVER ³/₄" DIAMETER THAT ARE NOT COMPLETELY CALLUSED WILL BE REJECTED. SHALL HAVE HEALTHY, WELL-DEVELOPED ROOT SYSTEMS, AND BE FREE FROM PHYSICAL 3.3.
- DAMAGE OR OTHER HINDRANCES TO HEALTHY GROWTH. 3.4. BALLED AND BURLAPPED PLANTS SHALL BE DUG WITH SOLID BALLS OF A DIAMETER NOT LESS THAN THAT RECOMMENDED BY THE AMERICAN STANDARDS FOR NURSERY STOCK, AND OF SUFFICIENT DEPTH TO INCLUDE BOTH FIBROUS AND FEEDING ROOTS. BALLS SHALL BE SECURELY WRAPPED WITH BURLAP, AND TIGHTLY BOUND WITH ROPE OR TWINE. NO PLANTS SHALL BE BOUND WITH ROPE OR WIRE IN SUCH A MANNER AS TO DAMAGE BARK OR BREAK BRANCHES. THE ROOT FLARE SHOULD BE WITHIN THE TOP 2" OF THE SOIL BALL. BALLED AND BURLAPPED PLANTS WILL NOT BE ACCEPTED IF THE BALL IS DRY, CRACKED, OR BROKEN BEFORE OR DURING PLANTING.

4. PLANTS SHALL CONFORM TO THE MEASUREMENTS SPECIFIED WITHIN THE PLANT SCHEDULE.

PLANTING PROJECT CONDITIONS:

- 1. VERIFY SERVICE AND UTILITY LOCATIONS, AND DIMENSIONS OF CONSTRUCTION CONTIGUOUS WITH NEW PLANTINGS BY FIELD MEASUREMENTS BEFORE PROCEEDING WITH PLANTING WORK.
- 2. INTERRUPTION OF EXISTING SERVICES OR UTILITIES; DO NOT INTERRUPT SERVICES OR UTILITIES
- UNLESS PERMITTED UNDER THE FOLLOWING CONDITIONS AND THEN ONLY AFTER ARRANGING TO PROVIDE TEMPORARY SERVICES OR UTILITIES ACCORDING TO REQUIREMENTS INDICATED:
- 2.1. NOTIFY OWNER'S PROJECT REPRESENTATIVE NO FEWER THAN TWO DAYS IN ADVANCE OF PROPOSED INTERRUPTION OF EACH SERVICE OR UTILITY.
- 2.2. DO NOT PROCEED WITH INTERRUPTION OF SERVICES OR UTILITIES WITHOUT
- REPRESENTATIVE'S WRITTEN PERMISSION. 3. PLANTING RESTRICTIONS: PLANTING SHALL OCCUR DURING THE FOLLOWING ACCEPTABLE INSTALLATION PERIODS:
- 3.1. DECIDUOUS TREES AND SHRUBS APRIL 15 TO OCTOBER 15.
- 3.2. NATIVE SEEDING AND TURFGRASS: APRIL 15 OCTOBER 15
- 4. WEATHER LIMITATIONS: PROCEED WITH PLANTING ONLY WHEN EXISTING AND FORECASTED WEATHER CONDITIONS PERMIT PLANTING TO BE PERFORMED WHEN BENEFICIAL AND OPTIMUM RESULTS MAY BE OBTAINED. APPLY PRODUCTS DURING FAVORABLE WEATHER CONDITIONS ACCORDING TO MANUFACTURER'S WRITTEN INSTRUCTIONS AND WARRANTY REQUIREMENTS.
- 5. CONTRACTOR SHALL PROTECT ALL EXISTING AND/OR NEWLY INSTALLED PLANTS, LAWNS, AND GRASS AREAS FROM DAMAGE AT ALL TIMES. DAMAGED PLANTS, LAWNS OR GRASS AREAS SHALL BE REPLACED OR TREATED AS REQUIRED TO CONFORM TO SPECIFICATIONS HEREIN FOR FRESH STOCK. WORK AREA SHALL BE KEPT CLEAN AND ORDERLY DURING THE INSTALLATION PERIOD. UNDER NO CONDITION SHALL DEBRIS FROM PLANTING ACTIVITIES RESULT IN A SAFETY HAZARD ON-SITE OR ADJACENT OFF-SITE PROPERTY. DAMAGE TO SITE IMPROVEMENTS OR ADJACENT LANDSCAPES INCURRED AS A RESULT OF PLANTING OR REPLACEMENT OPERATIONS SHALL BE REPAIRED BY THE CONTRACTOR THAT CAUSES THE DAMAGE AT NO COST TO THE OWNER.
- 6. EXAMINE AREAS TO RECEIVE PLANTS FOR COMPLIANCE WITH REQUIREMENTS AND CONDITIONS AFFECTING INSTALLATION AND PERFORMANCE. PROCEED WITH INSTALLATION ONLY AFTER UNSATISFACTORY CONDITIONS HAVE BEEN CORRECTED.
- 6.1. VERIFY THAT NO FOREIGN OR DELETERIOUS MATERIAL OR LIQUID SUCH AS PAINT, PAINT WASHOUT. CONCRETE SLURRY. CONCRETE LAYERS OR CHUNKS. CEMENT. PLASTER. OILS GASOLINE, DIESEL FUEL, PAINT THINNER, TURPENTINE, TAR, ROOFING COMPOUND, OR ACID
- HAS BEEN DEPOSITED IN SOIL WITHIN PLANTING AREAS. 6.2. DO NOT MIX OR PLACE SOILS IN FROZEN, WET, OR MUDDY CONDITIONS

PLANTING DELIVERY, STORAGE, & HANDLING:

- 1. BULK MATERIALS:
- 1.1. DO NOT DUMP OR STORE BULK MATERIALS NEAR STRUCTURES, UTILITIES, WALKWAYS AND PAVEMENTS, OR ON EXISTING TURF AREAS OR PLANTS.
- 2. DO NOT PRUNE TREES AND SHRUBS BEFORE DELIVERY. PROTECT BARK, BRANCHES, AND ROOT SYSTEMS FROM SUN SCALD, DRYING, WIND BURN, SWEATING, WHIPPING, AND OTHER HANDLING AND TYING DAMAGE. DO NOT BEND OR BIND-TIE TREES OR SHRUBS IN SUCH A MANNER AS TO DESTROY THEIR NATURAL SHAPE. PROVIDE PROTECTIVE COVERING OF PLANTS DURING SHIPPING AND DELIVERY. DO NOT DROP PLANTS DURING DELIVERY AND HANDLING.
- 3. HANDLE PLANTING STOCK BY ROOT BALL.
- 4. DELIVER PLANTS AFTER PREPARATIONS FOR PLANTING HAVE BEEN COMPLETED AND INSTALL IMMEDIATELY. IF PLANTING IS DELAYED MORE THAN SIX HOURS AFTER DELIVERY, SET PLANTS AND TREES IN SHADED LOCATION, PROTECT FROM WEATHER AND MECHANICAL DAMAGE, AND KEEP ROOTS MOIST.
- 4.1. SET BALLED STOCK ON GROUND AND COVER BALL WITH SOIL, PEAT MOSS, SAWDUST, OR OTHER ACCEPTABLE MATERIAL
- 4.2. WATER ROOT SYSTEMS OF PLANTS STORED ON-SITE DEEPLY AND THOROUGHLY WITH A FINE-MIST SPRAY. WATER AS OFTEN AS NECESSARY TO MAINTAIN ROOT SYSTEMS IN A MOIST, BUT NOT OVERLY WET CONDITION.

EXCAVATION FOR TREES & SHRUBS

- 1. EXCAVATE CIRCULAR PLANTING PITS AS INDICATED IN DRAWINGS. TRIM PERIMETER OF BOTTOM LEAVING CENTER AREA OF BOTTOM RAISED SLIGHTLY TO SUPPORT ROOT BALL AND ASSIST IN DRAINAGE AWAY FROM CENTER. DO NOT FURTHER DISTURB BASE. ENSURE THAT ROOT BALL WILL SIT ON UNDISTURBED BASE SOIL TO PREVENT SETTLING. SCARIFY SIDES OF PLANTING PIT SMEARED OR SMOOTHED DURING EXCAVATION.
- 1.1. EXCAVATE APPROXIMATELY THREE TIMES AS WIDE AS BALL DIAMETER FOR BALLED AND BURLAPPED STOCK. 1.2. DO NOT EXCAVATE DEEPER THAN DEPTH OF THE ROOT BALL, MEASURED FROM THE ROOT
- FLARE TO THE BOTTOM OF THE ROOT BALL
- 1.3. IF AREA UNDER THE PLANT WAS INITIALLY DUG TOO DEEP, ADD SOIL TO RAISE IT TO CORRECT LEVEL AND THOROUGHLY TAMP THE ADDED SOIL TO PREVENT SETTLING.
- MAINTAIN REQUIRED ANGELS OF REPOSE OF ADJACENT MATERIALS AS SHOWN IN DRAWINGS. DO NOT EXCAVATE SUBGRADES OF ADJACENT PAVING, STRUCTURES, HARDSCAPES, OR OTHER NEW OR EXISTING IMPROVEMENTS. 1.5. MAINTAIN SUPERVISION OF EXCAVATIONS DURING WORKING HOURS.
- 1.6. KEEP EXCAVATIONS COVERED OR OTHERWISE PROTECTED WHEN UNATTENDED BY **INSTALLER'S PERSONNEL.**
- 2. SUBSOIL AND TOPSOIL REMOVED FROM EXCAVATIONS MAY BE USED AS PLANTING SOIL IF THEY CONFORM TO THE REQUIREMENTS LISTED IN THESE SPECIFICATIONS.
- 3. NOTIFY OWNER'S PROJECT REPRESENTATIVE IF UNEXPECTED ROCK OR OBSTRUCTIONS DETRIMENTAL TO TREES OR SHRUBS ARE ENCOUNTERED IN EXCAVATIONS.
- 4. NOTIFY OWNER'S PROJECT REPRESENTATIVE IF SUBSOIL CONDITIONS EVIDENCE UNEXPECTED WATER SEEPAGE OR RETENTION IN TREE OR SHRUB PLANTING PITS.

TURF SEEDING

- DELIVERY:
- DELIVER PACKAGED SEED MATERIALS IN ORIGINAL, UNOPENED CONTAINERS LABELED AS TO NAME AND 1.1. ADDRESS OF SUPPLIER; SPECIFIC BLEND OF SEED; AND INDICATION OF CONFORMANCE WITH STATE AND FEDERAL LAWS, AS APPLICABLE.
- 2. PROJECT CONDITIONS:
- SEED DURING ONE OF THE FOLLOWING PERIODS. 2.1.
- 2.1.1. SPRING SEEDING SEASON: APRIL 1 TO JUNE 15 2.1.2. FALL SEEDING SEASON: AUGUST 15 TO OCTOBER 1
- 3. PRODUCTS
- PROVIDE THE FOLLOWING FOR TURFGRASS SEED BASIS OF DESIGN: REINDEERS DELUXE 50 SEED 3.0.1. MIX OR APPROVED EQUAL
- 3.0.2. TURFGRASS SEED MIX TO BE FERTILIZED WITH 'SCOTT'S STARTER FERTILIZER' BY THE 'SCOTTS MIRACLE-GRO COMPANY' OR APPROVED EQUAL.
- 4. PROCEED WITH INSTALLATION ONLY AFTER UNSATISFACTORY CONDITIONS HAVE BEEN MET REMOVE ANY AND ALL UNDESIRABLE VEGETATION THAT HAS GERMINATED IN THE AREAS TO BE SEEDED OR SODDED. CONTRACTOR SHALL EVALUATE THE USE OF A BROAD SPECTRUM. NON-PERSISTENT
- GLYSOPHATE-BASED HERBICIDE BASED ON SITE CONDITIONS. 5.1. DO NOT APPLY SEED UNTIL FIVE TO SEVEN DAYS AFTER LAST HERBICIDE TREATMENT.
- 6. FINISH GRADING: GRADE AREAS TO A SMOOTH, UNIFORM SURFACE PLANE WITH LOOSE, UNIFORMLY FINE TEXTURE. GRADE TO WITHIN PLUS OR MINUS ¹/₂ INCH OF FINISH ELEVATION. ROLL AND RAKE, REMOVE RIDGES, AND FILL DEPRESSIONS TO MEET FINISH GRADES. LIMIT FINISH GRADING TO AREAS THAT CAN BE IMMEDIATELY SEEDED AND STABILIZED WITH EROSION CONTROL MATERIAL
- MOISTEN PREPARED AREA BEFORE SEEDING IF SOIL IS DRY. WATER THOROUGHLY AND ALLOW SURFACE DRY BEFORE SEEDING OR SODDING. DO NOT CREATE MUDDY SOIL.
- 8. NO SEEDING SHALL OCCUR ON FROZEN GROUND OR AT TEMPERATURES LOWER THAN 32 DEGREES
- FARENHEIT OR IN THE FOLLOWING 5 DAYS AFTER PLANNED SEEDING OR SODDING. 9. SEEDING RATES TO BE PERFORMED IN ACCORDANCE WITH SEED SUPPLIER RECOMMENDATIONS.

TREE & SHRUB PLANTING

- NO ADDITIONAL COST TO THE OWNER.
- PLANTS FOUND TO HAVE STEM GIRDLING ROOTS AND/OR KINKED ROOTS AT THE TIME OF TO THE OWNER.
- FROM ROOT BALL AREA.
- LEADERS.
- ROOT FLARE 2 INCHES ABOVE ADJACENT FINISH GRADES. 5.1. USE SOIL MATERIALS FROM EXCAVATION FOR BACKFILL
- BALL IS CRACKED OR BROKEN BEFORE OR DURING PLANTING OPERATION.
- AND AIR POCKETS. WHEN PLANTING PIT IS APPROXIMATELY ONE-HALF FILLED, WATER MORE WATER IS ABSORBED.
- OF SOIL.

TREE & SHRUB MATERIAL:

- KNOTS, SUN SCALD, INJURIES, ABRASIONS, AND DISFIGUREMENT
- STEM GIRDLING ROOTS WILL BE REJECTED.
- NURSERY
- ACCEPTABLE.
- VISIBLE BEFORE PLANTING. 3. SELECT STOCK FOR UNIFORM HEIGHT AND SPREAD.

PLANTING SOIL

- PLANTING SOIL SHALL BE PLACED IN ONE CONTINUOUS VOLUME FOR THE WIDTH OF LANDSCAPE AREAS, AND A MINIMUM OF 3X THE DIAMETER OF THE ROOT BALL LENGTHWISE 1. INSTALL PLANTING SOIL FOR PLANT BEDS IN 6" LIFTS, MINIMUM 8" DEPTH.
- DO NOT APPLY PLANTING SOIL TO SATURATED OR FROZEN SUBGRADES.
- PASSING THE 1" SIEVE, FREE OF ROCKS, DEBRIS, AND OF NOXIOUS WEEDS. THAN 1-INCH.

METAL EDGING

MULCH.

- 1. STANDARD PROFILE, COMMERCIAL-GRADE, EXTRUDED ALUMINUM EDGING, FABRICATED IN SECTIONS TO RECEIVE STAKES.
- 1.1. BASIS OF DESIGN: CLEANLINE BY PERMALOC OR APPROVED EQUAL
- 1.2. EDGING SIZE: 3/16-INCH-WIDE BY 5.5 INCHES DEEP 1.3. STAKES: ALUMINUM, ASTM 221, ALLOY 6061-T6, 18-INCHES LONG.
- 1.4. FINISH: BLACK DURAFLEX
- 15 INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING: CURV-RITE, INC., PERMALOC

STONE MULCH MATERIAL & INSTALLATION:

- SUBSTANCES, OF THE FOLLOWING TYPE, SIZE RANGE, AND COLOR:
- 1.1. MATERIAL: ANGULAR WASHED STONE. 1.2. SIZE: 1-1/2" DIAMETER
- 1.3. DEPTH: 3" MINIMUM DEPTH PLACED IN ONE LIFT
- 1.4. COLOR RANGE: BLEND OF DARK GREY & BLUE TONES
- 2. LIGHTLY COMPACT AREAS TO RECEIVE STONE MULCH
- 3. INSTALL WEED BARRIER FABRIC IN ACCORDANCE WITH MANUFACTURER'S WRITTEN AND CONCRETE FLATWORK SO IT IS NOT VISIBLE FROM SURFACE.
- OF ADJACENT PAVED AREAS OR METAL EDGING.
- **BARK MULCH MATERIAL & INSTALLATION**

PLANS.

- 1.1. SIZE RANGE: MAXIMUM 2.5" TO 3" 1.2. COLOR: NATURAL, UN-DYED

2. KEEP BARK MULCH 2" CLEAR OF ALL STEMS OF PLANT MATERIAL

TURF SOD INSTALLATION:

INCH OF FINISH ELEVATIONS

CLEAN-UP AND PROTECTION

ORDERLY CONDITION.

REPLACE DAMAGED PLANTINGS.

WAI KWAYS

1.

1. BEFORE PLANTING VERIFY THAT ROOT FLARE IS VISIBLE AT TOP OF ROOT BALL. IF ROOT FLARE IS NOT VISIBLE, REMOVE SOIL IN A LEVEL MANNER FROM THE ROOT BALL TO WHERE THE TOP-MOST ROOT EMERGES FROM THE TRUNK. AFTER SOIL REMOVAL TO EXPOSE ROOT FLARE, VERIFY THAT ROOT BALL STILL MEETS SIZE REQUIREMENTS. PLANT MATERIAL WITHOUT ROOT FLARE VISIBLE OR PLANTED TOO LOW WILL BE RE-PLANTED AT THE REQUEST OF THE LANDSCAPE ARCHITECT AT

PLANTING WILL BE REJECTED AND REPLACEMENTS SHALL BE PROVIDED AT NO ADDITIONAL COST

3. REMOVE ALL TWINE, STRING, WIRE, AND ALL OTHER NON-BIODEGRADABLE MATERIAL ENTIRELY

REMOVE ONLY DEAD, DYING, OR BROKEN BRANCHES. DO NOT PRUNE FOR SHAPE. DO CUT TREE

5. SET BALLED AND BURLAPPED STOCK PLUMB AND IN CENTER OF PLANTING PIT OR TRENCH WITH

5.2. CAREFULLY CUT AND REMOVE BURLAP, ROPE, AND WIRE BASKETS FROM THE ENTIRE ROOT BALL. REMOVE PALLETS, IF ANY, BEFORE SETTING. DO NOT USE PLANTING STOCK IF ROOT 5.3. BACKFILL AROUND ROOT BALL IN LAYERS, TAMPING TO SETTLE SOIL AND ELIMINATE VOIDS

THOROUGHLY BEFORE PLACING REMAINDER OF BACKFILL. REPEAT WATERING UNTIL NO 5.4. CONTINUE BACKFILLING PROCESS. WATER AGAIN AFTER PLACING AND TAMPING FINAL LAYER

1. GENERAL: FURNISH NURSERY-GROWN PLANTS TRUE TO GENUS, SPECIES, VARIETY, CULTIVAR STEM FORM, SHEARING, AND OTHER FEATURES INDICATED IN PLANT SCHEDULE SHOWN AND DRAWINGS.; AND WITH HEALTHY ROOT SYSTEMS DEVELOPED BY TRANSPLANTING OR ROOT PRUNING. PROVIDE WELL-SHAPED, FULLY BRANCHED, HEALTHY, VIGOROUS STOCK, DENSELY FOLIATED WHEN IN LEAF AND FREE OF DISEASE, PESTS, EGGS, LARVAE, AND DEFECTS SUCH AS

1.1. TREES WITH DAMAGED, CROOKED, OR MULTIPLE LEADERS; TIGHT VERTICAL BRANCHES WHERE BARK IS SQUEEZED BETWEEN TWO BRANCHES OR BETWEEN BRANCH AND TRUNK ("INCLUDED BARK"); CROSSING TRUNKS; CUT-OFF LIMBS MORE THAN ³/₄" IN DIAMETER; OR WITH

1.2. COLLECTED STOCK: DO NOT USE PLANTS HARVESTED FROM THE WILD, FROM NATIVE STANDS, FROM AN ESTABLISHED LANDSCAPE PLANTING, OR NOT GROWN IN A STATE CERTIFIED

1.3. PLANT MATERIAL SHALL BE PROVIDED IN THE CONTAINER TYPE INDICATED IN THE DRAWINGS (B&B, CONTAINER, BARE ROOT, ETC.), UNLESS THE CONTRACTOR RECEIVES WRITTEN APPROVAL FROM THE LANDSCAPE ARCHITECT THAT SUBSTITUTION OF CONTAINER TYPE IS

2. FURNISH TREES WITH ROOT BALLS MEASURED FROM TOP OF ROOT BALL. ROOT FLARE SHALL BE

3. PLANTING SOIL SHALL BE A MIX OF 6-PARTS TOPSOIL, 1-PART COMPOST (APPROVED FOR USE ON THE PROJECT). THOROUGHLY BLEND PLANTING SOIL OFF-SITE BEFORE SPREADING. 3.1. THE PROJECT WILL ACCEPT ONLY CLEAN, SALVAGED OR IMPORTED TOPSOIL CAPABLE OF 3.2. STRIPPED, SALVAGED, OR MINED TOPSOIL MUST BE TAKEN FROM THE TOP 6-INCHES OF THE A-HORIZON, HAVING A DARK BROWN TO BLACK COLOR WITH A GRANULAR STRUCTURE AND CLAY CONTENT OF LESS THAN 25%, VERIFIED WITH A RIBBON TEST THAT YIELDS NO MORE

STANDARD LENGTHS WITH INTERLOCKING SECTIONS WITH LOOPS STAMPED FROM FACE OF

MANUFACTURERS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, AVAILABLE MANUFACTURERS OFFERING PRODUCTS THAT MAY BE INCORPORATED INTO THE WORK CORPORATION, RUSSELL, J.D. COMPANY (THE), SURE-LOC EDGING CORPORATION

INSTALL METAL EDGE IN ACCORDANCE WITH MANUFACTURER'S WRITTEN INSTRUCTIONS. 3. ENSURE THAT METAL EDGING IS PROPERLY INSTALLED AND SECURED BEFORE INSTALLING STONE

1. SHALL BE HARD, DURABLE, STONE, WASHED FREE OF LOAM, SAND, CLAY, AND OTHER FOREIGN

1.5. BASIS OF DESIGN: 1-1/2" 'AMERICAN HERITAGE' AGGREGATE BY COUNTY MATERIALS.

DISCHARGE OF SOIL-BEARING WATER RUNOFF OR AIRBORNE DUST TO ADJACENT PROPERTIES AND

INSTRUCTIONS; COMPLETELY COVER AREA TO BE MULCHED, OVERLAPPING EDGES OF FABRIC LENGTHS A MINIMUM OF 6-INCHES AND SECURING SEAMS WITH GALVANIZED PINS. WEED BARRIER FABRIC SHALL BE WRAPPED VERTICALLY UP THE OUTSIDE EDGES OF SURROUNDING CONCRETE FLATWORK OR CURB AND SECURED IN PLACE. HOLD FABRIC 2" CLEAR OF TOP OF ADJACENT CURB

4. PLACE AND FINISH STONE MULCH AS INDICATED IN DRAWINGS, ENSURING A SMOOTH, LEVEL TOP SURFACE FOR ALL STONE MULCH AREAS HELD APPROXIMATELY 1/2" BELOW THE TOP SURFACE

1. TWICE-SHREDDED HARDWOOD BARK MULCH TO BE PROVIDED AS TOP-DRESSING FOR ALL TREE CIRCLES FOR SINGLY PLANTED TREES LOCATED IN TURF GRASS AREAS OR AS INDICATED ON THE

1.3. PROVIDE 3" DEPTH MULCH FOR ALL PLANTING BEDS INDICATED AS BARK MULCH PLANTING BED

PROTECT STRUCTURES, UTILITIES, SIDEWALKS, PAVEMENTS, AND OTHER FACILITIES, TREES, SHRUB, AND PLANTINGS FROM DAMAGE CAUSED BY PLANTING OPERATIONS. 2. INSTALL EROSION-CONTROL MEASURES TO PREVENT EROSION OR DISPLACEMENT OF SOILS AND

3. LOOSEN SUBGRADE TO A MINIMUM DEPTH OF 4 INCHES. REMOVE STONES LARGER THAN 1 INCH. SPREAD PLANTING SOIL TO A DEPTH OF 4 INCHES. FINISH GRADE TOPSOIL TO PLUS OR MINUS ½

4. APPLY GRANULAR STARTER LAWN FERTILIZER DIRECTLY TO THE SURFACE OF THE FINISH GRADE. MOISTEN PREPARED AREA BEFORE PLANTING IF SOIL IS DRY. DO NOT CREATE MUDDY SOIL. 5. LAY SOD WITHIN 24 HOURS OF HARVESTING. LAY SOD TO FORM A SOLID MASS WITH TIGHTLY

FITTED JOINTS. BUTT ENDS AND SIDES OF SOD; DO NOT STRETCH OR OVERLAP. STAGGER SOD STRIPS OR PADS TO OFFSET JOINTS IN ADJACENT COURSES,

6. SATURATE SOD WITH FINE WATER SPRAY WITHIN TWO HOURS OF PLANTING. DURING FIRST WEEK AFTER PLANTING, WATER DAILY OR MORE FREQUENTLY AS NECESSARY TO MAINTAIN MOIST SOIL TO A MINIMUM DEPTH OF 1 ½ INCHES BELOW SOD.

1. DURING PLANTING, KEEP ADJACENT PAVING AND CONSTRUCTION CLEAN AND WORK AREA IN AN

PROTECT PLANTS FROM DAMAGE DUE TO LANDSCAPE OPERATIONS AND OPERATIONS OF OTHER CONTRACTORS AND TRADES. MAINTAIN PROTECTION DURING INSTALLATION. TREAT, REPAIR, OR

3. AFTER INSTALLATION REMOVE ALL NURSERY TAGS, NURSERY STAKES, TIE TAPE, LABELS, WIRE, STRING, AND OTHER DEBRIS FROM PLANT MATERIAL, PLANTING AREAS, AND PROJECT SITE.

- 1. PLANT EACH TREE SUCH THAT THE ROOT FLARE IS VISIBLE AT THE TOP OF THE ROOT BALL. DO NOT COVER THE TOP OF THE ROOT BALL WITH SOIL.
- 2. DEPTH OF THE PLANTING HOLE SHOULD BE DETERMINED AND DUG AFTER THE ROOT FLARE IS LOCATED. PLANTING HOLE MUST BE NO DEEPER THAN THE HEIGHT OF THE ROOT BALL.
- 3. IF PLANT IS SHIPPED WITH A WIRE BASKET AROUND THE ROOT BALL, CUT AND REMOVE THE WIRE BASKET ENTIRELY. REMOVE ALL TWINE, ROPE, AND BURLAP COMPLETELY FROM ALL ROOT BALLS.
- 4. PLACE ROOT BALL ON UNEXCAVATED OR TAMPED SOIL
- 5. DO NOT PLACE MULCH IN CONTACT WITH STEMS. 6. WATER ALL PLANTS WITHIN 2 HOURS OF INSTALLATION.
- 7. PRUNE ONLY AS NECESSARY TO REMOVE UNHEALTHY BRANCHES. DO NOT REMOVE MORE THAN $\frac{1}{3}$ OF THE ORIGINAL PLANT MASS.
 - KEYED LEGEND EDGING BLACK ANODIZED ALUMINUM EDGING PREPARED SUBGRADE PRESSURE SO THAT BALL DOES NOT SHIFT

TYPICAL TREE PLANTING ۲. A / SCALE:NT

- NOTES 1. MAKE 1" TO 2" DEEP VERTICAL CUTS EVERY 6" AROUND THE CIRCUMFERENCE OF THE ROOT BALL BEFORE PLANTING TO LOOSEN POT-BOUND ROOTS.
- 2. PLANT EACH SHRUB SUCH THAT THE ROOT FLARE IS VISIBLE AT THE TOP OF THE ROOT BALL. DO NOT COVER THE TOP OF THE ROOT BALL WITH SOIL.
- 3. PLANTING HOLE MUST NOT BE DEEPER THAN THE HEIGHT OF THE ROOT BALL. 4. DO NOT PLACE MULCH IN CONTACT WITH STEMS.
- 5. PLACE ROOT BALL ON UNEXCAVATED OR TAMPED SOIL.
- 6. WATER ALL PLANTS WITHIN 2 HOURS OF INSTALLATION.
- 7. PRUNE ONLY AS NECESSARY TO REMOVE UNHEALTHY BRANCHES. DO NOT REMOVE MORE THAN $\frac{1}{3}$ OF THE ORIGINAL PLANT MASS.
- 8. SEGREGATE ANY SOIL FROM BELOW WARNING LAYER EXCAVATED DURING PLANTING FOR OFF-SITE DISPOSAL. COORDINATE DISPOSAL WITH ENVIRONMENTAL CONSULTANT.
- 9. FOR SHRUBS PLANTED WITHIN PLANTING BEDS, CONTRACTOR SHALL PROVIDE PLANTING SOIL CONTINUOUSLY FOR THE ENTIRE PLANTING BED AND INDIVIDUAL SHRUBS SHALL BE PLANTED INTO THE PREPARED PLANTING SOIL. MULCH SURFACE FOR PLANTING BEDS SHALL ALSO BE CONTINUOUS ACROSS THE ENTIRE SURFACE AND HELD ¹/₂" MIN. TO 1" MAX. BELOW ADJACENT PAVEMENTS.

KEYED LEGEND

- 1 3" DEPTH DECORATIVE STONE MULCH, AMERICAN HERITAGE 1-1/2" OR APPROVED EQUAL, KEEP 2" CLEAR OF STEMS
- WOVEN GEOTEXTILE FILTER FABRIC, WRAP UP SIDES OF EDGING
- > PLANTING SOIL AS SPECIFIED, PLANTING SOIL SHALL BE PLACED IN ONE CONTINUOUS VOLUME FOR THE ENTIRE AREA OF ANY GIVEN PLANT BED
- \langle 4 \rangle 1" TO 2" DEEP VERTICAL CUTS EVERY 6" AROUND PERIMETER
- 5 PREPARED SUBGRADE
- (6) TAMP SOIL AROUND BALL BASE FIRMLY WITH FOOT PRESSURE SO THAT BALL DOES NOT SHIFT


 \smallsetminus TYPICAL SHRUB PLANTING


- 1. DO NOT COVER THE TOP OF THE ROOT BALL WITH SOIL.
- 2. PLANTING HOLE MUST NOT BE DEEPER THAN THE HEIGHT OF THE ROOT BALL
- 3. DO NOT PLACE MULCH IN CONTACT WITH STEMS. 4. WATER ALL PLANTS THOROUGHLY WITHIN 2 HOURS OF INSTALLATION.
- 5. PRUNE ONLY AS NECESSARY TO REMOVE UNHEALTHY OR DEAD PLANT PARTS.
- DO NOT REMOVE MORE THAN $\frac{1}{3}$ OF THE ORIGINAL PLANT MASS.
- 6. FOR PLANTS PLANTED WITHIN PLANTING BEDS, CONTRACTOR SHALL PROVIDE PLANTING SOIL CONTINUOUSLY FOR THE ENTIRE PLANTING BED AND INDIVIDUAL SHRUBS SHALL BE PLANTED INTO THE PREPARED PLANTING SOIL. MULCH SURFACE FOR PLANTING BEDS SHALL ALSO BE CONTINUOUS ACROSS THE ENTIRE SURFACE AND HELD ¹/₂" MIN. TO 1" MAX. BELOW ADJACENT PAVEMENTS


KEYED LEGEND


- PERENNIAL, ORNAMENTAL GRASS, OR SHEETS 3" DEPTH DECORATIVE STONE MULCH, AMERICAN HERITAGE 1-1/2" OR APPROVED EQUAL, KEEP 3" CLEAR OF STEMS WOVEN GEOTEXTILE FILTER FABRIC, WRAP UP SIDES OF EDGING PLANTING SOIL, PLANTING SOIL SHALL BE
- $\langle 5 \rangle$ PREPARED SUBGRADE

TYPICAL ORNAMENTAL GRASS PLANTING SCALE:NTS









TREE PIT WIDTH - 2X BALL

DIAMETER MINIMUM, OR FULL

EXTENTS OF PLANTING BED

\langle 1 \rangle 3" DEPTH DECORATIVE STONE MULCH, AMERICAN HERITAGE 1-1/2" OR APPROVED EQUAL. PROVIDE 4'-0" DIAMETER MULCH RINGS AT THE BASE OF ANY TREES PLANTED IN LAWN.


 \langle 2 \rangle $\,$ WOVEN GEOTEXTILE FILTER FABRIC, WRAP UP SIDES OF

> PLANTING SOIL, PLANTING SOIL SHALL BE PLACED IN ONE CONTINUOUS VOLUME FOR THE ENTIRE AREA OF ANY GIVEN PLANT BED.

TAMP SOIL AROUND BALL BASE FIRMLY WITH FOOT


GROUNDCOVER PLUG, SEE LANDSCAPE PLAN

PLACED IN ONE CONTINUOUS VOLUME FOR THE ENTIRE AREA OF ANY GIVEN PLANT BED



D STONE MULCH PLANTING BED SCALE:NTS


- KEYED LEGEND 1 ADJACENT LAWN
- 2 BLACK ANODIZED ALUMINUM EDGING
- $\langle 3 \rangle$ 3" DEPTH DECORATIVE STONE MULCH
- WOVEN GEOTEXTILE FILTER FABRIC, WRAP UP SIDES OF CURB AND EDGING
- $\langle 5 \rangle$ PLANTING SOIL
- $\langle 6 \rangle$ PREPARED SUBGRADE




KEYED LEGEND

- (1) ADJACENT LAWN $\langle 2 \rangle$ BLACK ANODIZED ALUMINUM EDGING
- $\langle 3 \rangle$ BUILDING FACE $\langle 4 \rangle$ 3" DEPTH STONE MULCH
- 5 WOVEN GEOTEXTILE FILTER FABRIC, WRAP UP SIDES OF BUILDING AND EDGING
- $\langle 6 \rangle$ PREPARED SUBGRADE

SHEET TITLE Landscape Specifications & Details





BI		
DI	ΔΝ	
	.Ar	

REV #	DESCRIPTION	DATE

REVISIONS

Address:1300 W. Canal Street Milwaukee, WI 53233 Landscape Architect of Record - Rosheen Styczinski

Cedarburg, WI 53012 Engineer of Record - Linda Johnson **RTM Engineering Consultants** Phone: 414.273.1432

Address: 316 N. Milwaukee Street, Suite 560

Engineer of Record - Timothy Larsen, PE

Milwaukee, WI 53202

Landscape Architect

The Sigma Group

Phone: 414 643 4200

TerraTec Engineerinç Phone: 262.377.9905 Address: W67N222 Evergreen Blvd., Suite 205

Project Manager - Lee Anderson P:262.945.7709

Address: 10505 Corporate Drive, Suite 100 Architect of Record - Jon P. Wallenkamp P:414.690.3197

Pleasant Prairie, Wisconsin 53158

ARCHITEC Kueny Architects Phone: 262.857.8101

©2025 Kueny Architects L.L.C. - All Rights Reserved CONSULTANTS

10505 Corporate Drive, Pleasant Prairie, WI 53158 phone: 262.857.8101 web: www.kuenyarch.com

KUEN ARCHITECTS



0 Chapman Drive, Waukesha, WI 53189

Issue Description

Waukesha Water Utility

PROJECT ISSUE DATE:

January 23, 2025

OWNER:

PROJEC