

Public Works – Engineering Division

201 Delafield Street
Waukesha, Wisconsin 53188-3633

**Alex Damien, P.E.,
Director**
adamien@waukesha-wi.gov
1-262-524-3600

**CITY OF WAUKESHA ENGINEERING DIVISION
REQUEST FOR PROPOSALS**

FOR

SARATOGA LAKE DREDGING STUDY

Proposals must be submitted no later than
noon local time on **Wednesday, April 23, 2025**

For further information regarding this RFP,
contact Jonathan Schapekahn, P.E.
jschapekahn@waukesha-wi.gov
(262) 524-3584

Late submittals will be rejected.

Issued: March 28, 2025

Table of Contents

A. General	3
1 Invitation	
2 Background Information	
B. Anticipated Scope of Services	3
1 Task 1 – Dam Safety Assessment	
2 Task 2 – Pre-Dredging Sediment Sampling and Analysis & Preliminary Dredging Design	
3 Task 3 – Conceptual Dam Removal Design	
4 Task 4 – Conceptual Designs for Improved Riverwalk Area	
5 Task 5 – Master Plan Reporting	
C. Information Available from the City of Waukesha	5
D. Submittal Process	5
1 Proposal Format	
2 Evaluation of Proposals and Selection of Consultant	
3 Award Schedule	
4 Submission of Proposal	
5 Requests for Clarification	
E. Attachments	
1 Attachment A – Saratoga Mill Dam Inspection Report, Ayres Associates, January 2019	
2 Attachment B – Saratoga Survey & Sampling Report, Ayres Associates, November 2019	
3 Attachment C – Frame Park Site Exhibit, raSmith, September 22, 2022	

A. General

1. Invitation

The City of Waukesha Engineering Division is soliciting proposals for engineering services for a feasibility and master planning study for Saratoga Mill Dam, Saratoga Lake, and the riverwalk area surrounding the Fox River in the vicinity of the dam and lake in downtown Waukesha, Wisconsin. The objective of the study is to investigate options for keeping and improving the dam and lake, removing the dam, and/or improving the surrounding riverwalk area. Qualified firms will have experience in dam safety and hydraulic engineering, dredging design, community engagement, landscape architecture, and civil site design.

2. Background Information

The Saratoga Mill Dam (Dam Key Sequence Number 630, Field File Number 67.23) impounds the Fox River in downtown Waukesha to form Saratoga Lake. While currently operating safely, the dam is over 100 years old and significant sediment has accumulated in the lake upstream. The City of Waukesha owns and operates the dam and desires to explore various options for the future of the dam and lake. These options may include improving the dam and dredging the lake upstream or removing the dam and restoring the river. Both options may be accompanied by improving the surrounding riverwalk area. The scope of work must include robust community engagement, which will help to guide the selected consultant to develop design alternatives in line with the community's overall vision.

B. Anticipated Scope of Services

1. Task 1 – Dam Safety Assessment

The dam was last inspected in 2018 by Ayres Associates Inc (Ayres). See Attachment A for the inspection report.

- Complete a complete inspection of Saratoga Mill Dam (including underwater) in accordance with Wisconsin Department of Natural Resources (WDNR) guidelines.
- Prepare and submit a dam inspection report to the City for review and comment. The inspection is for use in this study and does not need to be submitted to WDNR as a part of this scope.
- Based on the inspection's findings, prepare an opinion of probable cost for any recommended improvements and repairs needed to maintain safe operation and compliance with WDNR regulations.

Deliverables to include: Dam inspection report, Opinion of probable cost.

2. Task 2 – Pre-Dredging Sediment Sampling and Analysis & Preliminary Dredging Design

In 2019, Ayres completed a survey and sampling report for Saratoga Lake (see Attachment B). This study included a bathymetric survey, sediment depth probes, sediment sampling and testing, and the development of preliminary dredging plans.

- Prepare sediment sampling and mapping plan. Submit to city and WDNR for review and approval. Perform sediment sampling and analysis in accordance with WDNR requirements.
- Create preliminary dredging design drawings. Obtain bathymetric survey data as necessary.

- Prepare an opinion of probable cost for the dredging project. Opinion to include hauling and associated disposal costs required based on the composition of the sediment sampled.

Deliverables to include: Sediment sampling and mapping plan, Sediment sampling and analysis data, Bathymetric survey data, Preliminary dredging design drawing(s), Opinion of probable cost.

3. Task 3 – Conceptual Dam Removal Design

- Prepare a conceptual design for the removal of Saratoga Mill Dam. Conceptual design shall include requirements for sediment capture and disposal, stream stabilization, the complete removal of the existing water control structure, and other project components the consultant anticipates would be needed to remove the dam in compliance with WDNR regulations.
- Complete a hydrologic and hydraulic study as necessary to evaluate the potential physical and regulatory impacts associated with dam removal.
- Obtain survey data as necessary.
- Prepare opinion of probable cost for the removal of the dam.

Deliverables to include: Conceptual dam removal drawings(s), Hydrologic & hydraulic study report, Opinion of probable cost.

4. Task 4 – Conceptual Designs for Improved Riverwalk Area

Following a potential dam removal, significant City-owned space adjacent to the Fox River will be expanded because of the loss of the impoundment. This may present opportunities for expanding the riverwalk area adjacent to the Fox River and adding recreational and ecological enhancements. Should the dam remain in place, there may also be opportunities for enhancing the existing riverwalk area to improve access and recreation. With these potential alternatives in mind, the consultant shall:

- Plan, organize, attend, and lead two public community engagement sessions to obtain input on desired features and improvements to the riverwalk area adjacent to the Fox River should the Saratoga Mill Dam be removed or kept in place.
- Based on the findings from these sessions, prepare two conceptual designs, one with and one without the dam, that incorporate recreational and ecological enhancements in line with the community's vision. Each design is to include:
 - Opinion of probable cost
 - Assessment of potential regulatory concerns and impacts
 - Descriptions of funding sources including the identification of specific eligible grants, which may be available to offset the costs of each of the potential projects.
- Include time for incorporating up to two rounds of City review comments as each of the conceptual designs is developed.
- Obtain survey data as necessary.

Conceptual plans and renderings are to be developed with the aim of clearly conveying design ideas to the City and public. Consultant may also propose other methods of communicating design concepts to the City and other interested stakeholders.

Deliverables to include for each alternative: Conceptual drawings and renderings, Opinion of probable cost, Report summarizing potential regulatory issues and funding sources.

5. Task 5 – Master Plan Reporting

Consultant shall prepare a final report to consolidate and clearly convey all findings and conceptual designs prepared during tasks 1 through 4. Consultant shall also present findings at one Board of Public Works meeting, up to two City Council meetings, and up to two public information meetings.

Deliverables: Master plan report.

C. Information Available from the City of Waukesha

- AutoCAD file of Site Exhibit of Frame Park from 2022. PDF copy of exhibit included as Attachment C.

D. Submittal Process

1. Proposal Format

The consultant shall provide the appropriate information in sufficient detail to demonstrate that the evaluation criteria have been satisfied as specified in Section “Evaluation of Proposals”.

Proposals are to contain the following sections:

- Executive Summary – The Executive Summary should include a clear statement of the consultant’s understanding of the RFP including a summary of the Scope of Work, and the consultant’s approach to the project. Include, at a minimum, an outline of the contents of the proposal and a summary of the proposed services.
- Detailed Scope of Services – Describe in detail how services will be provided. Include detailed listing and description of tasks and deliverables. Include all tasks that are necessary to meet the desired scope of services, even if not listed in this RFP. Note any specific concerns or design challenges you have identified.
- Experience and Capacity – Describe your firm’s background and related experience demonstrating ability to provide required services. List projects of a similar nature including location, and construction cost.
- References – List references (contact names, phone numbers and email addresses) from at least three (3) previous or current similar projects.
- Personnel Listing – Summarize the qualifications and experience of the specific individuals who will actually be carrying out the work. Include resumes indicating specific, applicable experience. Specify the project tasks for which they are responsible. Include any anticipated subconsultants.
- Timeline – Estimated timeline to complete the project, including a detailed breakdown of anticipated time needed to deliver each task described in Scope of Services. **Master Plan Reporting task to be completed by the end of March 2026.**
- Meetings – Indicate the number of expected meetings. At a minimum, include the following meetings with the City of Waukesha:
 - Initial kick-off meeting
 - Bi-weekly check-in meetings/conference calls
 - Task 2 – review meeting
 - Task 3 – review meeting
 - Task 4 – two review meetings
- Public Meetings – Indicate the number of public meetings including at a minimum:
 - Two public community engagement sessions

- One Board of Public Works (BPW) meeting
- Two Common Council meetings
- Two public information meetings
- Other – Any other information that the respondent considers important and which may help the City better understand the firm, their approach, or level of service. Attachments showing general firm information and organization may be included. Excessive or irrelevant materials will not be favorably received.
- Cost/Fees – Provide the number of hours, by position and by task, for the proposed services outlined. This shall include a separate tabular breakdown showing labor rates by position, mark-up, overhead and profit, with lump sum prices for each individual Scope of Services Task. The lump sum prices may be adjusted during contract development based upon a refinement of the level of effort and scope. Include costs for all subconsultants. **The cost/fees are to be submitted in a separate PDF attachment to the proposal email submission.**

2. Evaluation of Proposals and Selection of Consultant

Proposals will be reviewed by a staff selection committee. The committee may select a short list for formal interviews as part of the final selection as deemed necessary. The City is looking for the most qualified team and will use a qualification and cost-based selection process to select a consultant for this project. Several criteria will be considered in the selection of the consultant, including:

- Quality, thoroughness, and clarity of proposal.
- Qualifications and experience of staff (includes a review of references) specifically related to projects involving dam inspections, renovations and/or removal, hydrologic & hydraulic studies, dredging, related permitting, and riverwalk enhancement.
- How well the scope of services offered achieves the project objectives and aligns with the project tasks.
- Project management approach.
- Cost of services proposed.

If an interview is deemed necessary, the City will schedule and arrange for interviews at a mutually agreeable time. The City of Waukesha, at its sole discretion, reserves the right to accept or reject any or all proposals in the best interest of the City of Waukesha without explanation or recourse.

3. Award Schedule

Anticipated Board of Public Works approval of recommended consultant:

Thursday, May 8, 2025.

Anticipated Common Council approval of recommended consultant:

Tuesday, May 20, 2025.

4. Submission of Proposal

The proposal must be received by **noon local time on Wednesday, April 23, 2025.**

All proposals must be clearly labeled "Proposal for Saratoga Lake Dredging Study".

Project Contact:
City of Waukesha Engineering Division
Jonathan Schapekahn, P.E.
jschapekahn@waukesha-wi.gov

The consultant shall email the city project contact:

- A copy of the proposal as a single PDF file.
- Costs/fees in a separate single PDF file.

Note: Late submissions, hard copy, or facsimile transmittals will not be considered.

Notice: Any and all costs arising from preparation of proposal submittal and participation in the selection process incurred by the engineering firm shall be borne by the firm without reimbursement compensation by the City of Waukesha.

5. Requests for Clarification

Prospective responders shall direct inquiries or questions to RFP to:
Jonathan Schapekahn, jschapekahn@waukesha-wi.gov, (262) 524-3584.

If questions are received, it is the city's intention to send responses to all proposal holders of record by Wednesday, April 16, 2025.

Notice

Confidentiality of Proposals, Contracts, and Supporting Materials

Wisconsin's Open Records Law requires that all records kept by the City be available for inspection by the public, with only very limited exceptions. This includes bids, proposals, and supporting materials such as plans and specifications, contracts, and other documents submitted in response to the City's Requests for Proposals.

Please be aware that the materials you submit in response to the City's RFP will be public record, and will be available to the public, including other bidders. Marking them "confidential" will have no effect. If you must submit materials that you feel are trade secrets and must be kept confidential, then you must obtain the City Attorney's written approval of the materials as confidential trade secrets before submission. That approval may be denied, according to the requirements of the Open Records Law.

Attachment A

Saratoga Mill Dam Inspection Report

Field File No. 67.23

Key Sequence No. 630

Waukesha County, Wisconsin



Prepared for:

**City of Waukesha
Waukesha, Wisconsin**

January 2019

January 8, 2019

Ms. Katie Jelacic, PE
City of Waukesha Engineering Division
City Hall Annex
130 Delafield Street
Waukesha, WI 53188

Re: Dam Safety Inspection Report, Saratoga Mill Dam
WDNR Field File No. 67.23, Key Sequence No. 630

Dear Ms. Jelacic,

Ayres Associates completed an inspection of the Saratoga Mill Dam on October 3rd and November 6th, 2018, in accordance with Wisconsin Department of Natural Resources (WDNR) guidelines. Two visits were made to the site because flows were above normal on October 3rd. On November 6th flows were lower, but still higher than normal. The following list describes recommendations based on our inspection and due dates based on the WDNR's suggested time frames. Please note that dam structures are referenced from left to right while looking in a downstream direction.

1. Benchmarks December 1, 2019

There are no benchmarks on the dam. NR 333 requires that all large dams have one benchmark on the dam and two benchmarks off the dam. One benchmark is required on the dam and should be set in an accessible location such as the deck of the overlook above the spillway. It may be possible to tie benchmark into existing off-site benchmarks such as benchmarks on the downstream bridge. Benchmarks should be in NAVD88 datum.

2. IOMP and EAP June 1, 2019

Ayres Associates is in the process of preparing an Emergency Action Plan (EAP) and Inspection, Operation and Maintenance Plan (IOMP). Final plans will be submitted to DNR for approval by the date above

Summary of Required Work and Schedule

The following schedule has been established for completing the necessary modifications, repairs, and/or reports.

Item	Completion Date
1. Benchmarks	December 1, 2019
2. Submit EAP and IOMP	June 1, 2019

Ms. Katie Jelacic
January 8, 2019
Page 2 of 2

Note the Saratoga Mill dam does not include earthen embankments, an auxiliary spillway nor a lake drain. In the 2010 inspection of the dam, seepage was noted on the right abutment near the stairs. This seepage was not observed during either site visit in 2018. We also could not visually inspect downstream of the spillway for scour or undermining. We recommend that in a period of low flows, the City visually inspect the dam to document the presence of adequate riprap at the toe of the spillway.

The inspection checklist, consultant checklist, certification, and photos from the inspection are enclosed, along with a CD containing electronic files. We have sent the same items to the WDNR representative. The inspection process will be complete when the WDNR sends you a letter which approves our inspection and recommendations. Be sure to inform the WDNR prior to performing any work on the dam other than routine maintenance.

Please let us know if we can be of further assistance to you.

Sincerely,

Ayres Associates Inc



Christopher T. Goodwin, PE
Manager, Water Resources
GoodwinC@AyresAssociates.com
Direct: 715.831.7682

Enclosures

cc: Michelle Hase, WDNR

SPILLWAY--PRINCIPAL - FIXED CREST							Action		
Item	N	P	Notes/ Observations				M	I	R
1 Fixed Crest	X		No problem		Not applicable		Could not inspect		
A. Dimensions Top Width: Crest Elevation:			Fixed crest wier 105 feet long.						
B. Materials									
C. Shape (sharp-crested, broad-crested, ogee, chute, gated, overflow, morning glory, dropbox, labyrinth)			Overflow ogee with 4 stop log bays						
D. Debris Prevention (racks, booms, etc.):			No prevention, no debris noted						
E. Concrete Condition *			Good						
F. Flashboards (none, number): Type (Metal, wood): Dimensions: Operability:			NA						
G. Abutments Condition: * Seepage/wetness:			Good No wetness observed in either site visit				3		
H. Drains Type: Weep holes, Relief drains, Other: Flow Rate:			No problem	x	Not applicable	x	Could not inspect		
I. Other									
N= Noted; P= Photo; M= Monitor I= Investigate; R= Repair F.F.= Field File; RT = Right; LT = Left U/S = Upstream; D/S = Downstream			Action Suggestion Controlled = Gated		1. Requires immediate action 2. Plan to do soon 3. Do when convenient Uncontrolled = Overflow				
Additional Comments:									
* Type of Concrete Problems: Spalling, cracks, exposed rebar, misalignment, joints, bug holes, efflorescence, popouts, honeycombing, scaling, craze/map cracks, isolated crack, disintegration, other									
Saratoga Mill Dam			F.F #: 67.23			Date: 10/03/18		Page 3 of 5	

Saratoga Mill Dam (Key Sequence No. 630)	
October 3, 2019	
File Name	Description
0063010031801.jpg	Dam Warning Sign and Portage Route
0063010031802.jpg	Overflow Spillway from Right Overlook
0063010031803.jpg	Stop Logs
0063010031804.jpg	Downstream Bridge
0063010031805.jpg	Upstream View of Dam
0063010031806.jpg	Upstream View of Dam
0063010031807.jpg	Overflow Spillway from Left Abutment
0063010031808.jpg	Left Abutment



Saratoga Mill Dam
 0063010031801.jpg
 Dam Warning Sign and Portage Route



Saratoga Mill Dam
0063010031802.jpg
Overflow Spillway from Right Overlook



Saratoga Mill Dam
0063010031803.jpg
Stop Logs



Saratoga Mill Dam
0063010031804.jpg
Downstream Bridge



Saratoga Mill Dam
0063010031805.jpg
Upstream View of Dam



Saratoga Mill Dam
0063010031806.jpg
Upstream View of Dam



Saratoga Mill Dam
0063010031807.jpg
Overflow Spillway from Left Abutment



Saratoga Mill Dam
0063010031808.jpg
Left Abutment

Consultant Inspection Process Form – for dam inspected by outside consultant

Task	<input checked="" type="checkbox"/>	Date Completed	Responsible Party	
			Owner/ Consultant	DNR
Inspection Notification *Notify dam owner of DNR inspection date/time	X	09/24/18	X	
File Research *Review last inspection report, photos, database, aerial photos, ownership information, etc.	X	09/24/18	X	
Field Inspection *Physically inspect dam, conduct survey if required	X	10/03/18	X	
Inspection Checklist *Fill out form documenting observations during inspection	X	10/03/18	X	
Photo Documentation *Print and label photos, back up digital copies	X	10/03/18	X	
Review Sufficiency Rating *Complete Sufficiency Rating questionnaire based on current condition of the dam.				X
Review Hazard Rating *Review downstream development for changes, check if downstream zoning is adopted	X	10/03/18	X	
Review EAP *Review and update EAP, submit to DNR	X	11/15/18	X	
Review IOM *Review and update IOM, submit to DNR	X	11/15/18	X	
Inspection Report Submitted to DNR Regional Engineer	X		X	
Inspection Report Submitted to DNR Central Office				X
Response Letter *DNR letter which outlines work needed to be completed on the dam based on consultant inspection				X
Update database *Update owner contact information, follow-up dates, inspection dates, etc. on DNR database				X
Notify DNR of planned work * Determine if plans and specs are needed for the proposed dam work, issue proper permits or plan approvals			X	
Complete Required Elements *Owner completes required items listed in inspection report			X	
Enforcement *Pursue enforcement action against the dam owner if the required elements are not completed by the appropriate deadlines				X

Dam Name: Saratoga Mill Dam

Field File #: 67.23

Engineer Completing Form: Christopher T. Goodwin, PE

Key Sequence #: 630

Certification for Dam Inspection

Local Dam Name (PRINT): Saratoga Mill Dam

DNR Field File #: 67.23

I certify that I have completed the checklist truthfully and factually:

Certifier's Name (print): Christopher T. Goodwin, PE

Company Name: Ayres Associates

Signature: _____

Date: _____

Multidisciplinary: I am experienced in the technical disciplines or I am working with other professionals experienced in the technical disciplines to properly inspect this dam and appurtenant works. Technical disciplines, in addition to general civil engineering, may include geotechnical, geological, hydrologic, structural, and mechanical:

Yes No

Engineer's Wisconsin Registration Number: 32520-6

Expiration Date: 7/31/2020

Engineer's Seal (optional):

Attachment B

Saratoga Survey and Sampling Report

Waukesha County, Wisconsin



Prepared for:

City of Waukesha

November 2019

Saratoga Survey and Sampling Report

Waukesha County, Wisconsin



3433 Oakwood Hills Parkway
Eau Claire, WI 54701-7698
715.834.3161 • Fax: 715.831.7500
www.AyresAssociates.com

Contents

	<u>Page No.</u>
Introduction	1
Methods.....	2
Results.....	2
Sediment Volume Results.....	2
Sediment Testing Results	3
Proposed Dredging and Dredging Options.....	3-4
Cost Estimate.....	4
Recommendation	4

List of Attachments

- Attachment 1 Sediment Sampling Plan
- Attachment 2 Conceptual Dredge Drawings
- Attachment 3 Cost Estimate
- Attachment 4 Sample Analytical Results

Methods

A sediment sampling plan was prepared and submitted to the Wisconsin Department of Natural Resources (WDNR) in September 2018. The WDNR reviewed the plan and it was approved on September 24, 2018. A copy of the approved plan is included in Attachment 1.

A bathymetric survey of the lake was completed on October 3, 2018. The soundings were obtained using a 235 Sonarmite BT kHz Echosounder and positioned with a submeter Trimble 6000 Series GeoXH GPS. The survey area was between the West Moreland Boulevard Bridge to the Saratoga Dam. The water surface elevation for Saratoga Lake was based on the National Geodetic Survey benchmark (OM0112) set vertically in the northeast corner of Waukesha Family Practice Center building, elevation 819.6 NAVD88. A level loop with was done to determine the water surface elevation of 811.47 NAVD88. The water surface was higher than normal due to recent large rain events. See Attachment 2 for the 2018 bathymetric contours and typical native lake bed cross sections.

Six sediment sample was collected with an AMS multistage sediment sampler with three samples located within the sediment expected to be dredged and three sample located in the native bed expected to be remain after dredging. The samples were visually classified and then sent to Pace Analytical Laboratories for physical and chemical testing. The results of the tested samples are summarized on Table 1 and the lab reports are included in Attachment 4.

The lake bed was probed until refusal along cross sections within the proposed dredge area. This was done to estimate the depth of the deposited sediment in each lake. Estimates of the volume of deposited sediment are shown on page 5 of the Conceptual Dredge Drawings in Attachment 2.

Results

Sediment Volume Results

Sediment depth probes were conducted along several cross sections within the lake. Survey poles were lowered to the top of the sediment and the depth was recorded. The survey poles were then pushed into the sediment until refusal and that measurement was recorded. Both measurements were measured from the water surface. The probe locations were geolocated within our hydrosurvey software, HYPACK. The sediment probes were done on several cross sections within the proposed dredge area, see page 4 of the Conceptual Dredge Drawings in Attachment 2.

The original river channel was at elevation approximately 801 at the north end of the project area, between elevation 802 and 803 on the middle and southern (downstream) end of proposed dredging project. At the north end of project sediment thickness is between four and eight feet, two to six feet in the middle section and less than two foot at downstream southern limits.

The dredge volumes were calculated using the drafting program AutoCAD Civil 3D. An existing bed surface was created for the proposed dredge area from the bathymetric survey data. An assumed native lake bed surface was also created from the sediment probe cross section data. A volume surface was created comparing the existing top of sediment surface to the assumed native lake bed surface. The dredge volumes were calculated from the comparison surface. Ayres estimates approximately 65,000 cubic yards are available to be dredged if dredging occurs to the assumed native lake bed.

Sample Testing Results

Six sediment samples were collected by Ayres Associates in 2018 and sent to Pace Laboratories in Minneapolis, Minnesota for testing. The below table shows only the detects that exceed NR 720 limits. See Attachment 4 for the complete lab testing results.

Table 1: Saratoga Lake Sediment Sampling							Non-Industrial Direct Contact RCL	Industrial Direct Contact RCL	Ground Water RCL	Back ground Threshold Value		
October 3, 2018 Samples Detects Only												
Detects Only	Sample						1	2	3	4	5	6
	1	2	3	4	5	6						
Arsenic	31.8	18.3	22.1	13.6	15.6	15.4	0.677	3	0.584	8		
Cadmium	3.4	0.97 J	0.88 J	0.92 J			71.1	985	0.752	1		
Lead	281	66.4	60.0	38.8			400	800	27.	52		
Nickel	48.7	18.1	21.4	20.1	14.4	18.9	1,550.	22,500.	13.0612	31		
Benzo(a)anthracene	2.80	20.1					1.14	20.8	NA	NA		
Benzo(a)pyrene	2.81	19.5	0.522	1.02	0.134		0.115	2.11	0.47	NA		
Benzo(b)fluoranthene	3.62	23.9	0.685	1.51			1.15	21.1	0.4781	NA		
Chrysene	2.72	19.8	0.506	1.04			115	2110	0.1442	NA		
Dibenz(a,h)anthracene	0.436	3.46		0.180			0.115	2.11	NA	NA		
Indeno(1,2,3-cd)pyrene	1.63	10.7					1.15	21.1	NA	NA		
Naphthalene		1.49					5.52	24.1	0.6582	NA		
Cumulative												
Exceedance Count	6	6	1	4	2	1						
Hazard Index	1.19969	1.9617	0.1333	0.5684	0.5258	0.5075						
Cumulative Cancer Risk	8.50E-05	2.8E-04	8.3E-06	3.6E-05	2.7E-05	2.5E-05						
<i>NR720 Groundwater RCL Exceedance</i>												
NR 720 Non Industrial Exceedance												
NR 720 Industrial Exceedance												
All results in mg/kg, equivalent to PPM												

Proposed Dredging and Disposal Options

During the survey in October 2018 the water elevation was 811.47. Top of sediment elevations averaged 808, which results in about 3.5 feet of water column. Estimated historic river bed elevation, based on sediment probe refusal, is elevation 802 at north end of project and 805 at south end. We recognize that the river bed elevation at the downstream end of the project is higher than upstream. We theorize this is because sediment at the downstream end has compacted over time and elevation 805 is not the pre-dam river bed. Typically, the DNR limits dredging to the native lake/river bed. A case could be made to allow dredging deeper than elevation 805 at the southern end of project, however this material may also be difficult to remove with a hydraulic dredge. The proposed dredging limits shown in Attachment 2 dredge the Fox River to the elevation of firm sediment versus what was the pre-dam river channel. The proposed dredging limits will result in an increase in water column of approximately 9.5 feet at north upstream end of dredging limits and 6.5 feet at south end of project.

Dredging is typically completed by either mechanical or hydraulic dredging. Mechanical dredging is often done after a reservoir drawdown and completed in winter. Hydraulic dredging is typically completed in summer season. The stop logs in the Saratoga Dam spillway can be removed, which will partially dewater the reservoir, however with recent climactic events with above average precipitation

and the limited number of stoplog bays in the dam, much of the sediment to be dredged would not be dewatered to allow mechanical dredging. Therefore, dredging will likely have to be completed at normal pool, which is typically done hydraulically.

Hydraulic dredging uses a suction/cutting head to remove sediment from the water body. A slurry of approximately 50% water and 50% sediment is pumped by the dredge to a staging area where the material can be dewatered and then transported to final disposal site. If the disposal site is close enough to sediment source, it is possible to pump the slurry to the final disposal site, however for the Saratoga project, no nearby disposal sites are available.

It is possible to mechanically dredging without dewatering. This is typically done from barges and using barges to transport sediment to an off-loading area. Turbidity control is more difficult when mechanically dredging is done under full pool and this option may not be allowed by the WDNR. This option, if desired, would need to be evaluated during the pre-permit application process.

The proposed dredging limits are detailed in the Attachment 2 drawings. If the project would be hydraulically dredged, a staging area nearby the reservoir is needed. A proposed dewatering/staging area is shown in the drawings in Attachment 2. Within this area the sediment is typically pumped into dewatering bags (or other dewatering method) were the sediment can dewater enough to be trucked to the disposal site. The City of Waukesha has researched available disposal sites and at this time, the only available disposal locations are to dispose of the sediment in a landfill.

Cost Estimate

To dredge 65,000 cubic yards hydraulically, Ayres estimates the project to cost in the 6 million to 7-million-dollar range. Cost can range greatly for dredging projects, but Ayres estimates \$20 - \$25 per cubic yard for hydraulic dredging and \$10 - \$15 for mechanical dredging. These dollar amounts are based on recent hydraulic and mechanically dredge projects Ayres has been involved with the last few years. To dispose of dredge material at a landfill, Ayres reached out to Waste Management and Advanced Disposal for budgetary pricing of sediment disposal. Waste Management has a budgetary price of \$36.50 per ton. Advanced Disposal's budgetary price range of \$15 to \$40 per ton. Ayres is assuming 1 cubic yard of sediment will weigh approximately 1.3 tons (variable due to water content). See Attachment 3 for the detailed cost breakdown and pricing proposals from the landfill representatives.

Recommendations

Disposing of the sediment within a landfill is the costliest disposal option for this sediment. If a non-landfill site can be located, the estimated project costs would likely decrease, but without an alternative site available, a landfill may be the only option. The Ayres environmental team reviewed the results and recommended a suitable method of disposal of the contaminated material would be land spreading with a two-foot thick cap of clean fill material, but this method must be approved by the DNR. If the City of Waukesha can locate a non-landfill disposal site, estimated projects will likely decrease. After the dredging method and disposal method is determined, a pre dredging application can be submitted to the DNR to start the permitting process.

Attachment 1
Sediment Sampling Plan

September 20, 2018

Craig Helker
Water Resources Management Specialist
Wisconsin Department of Natural Resources
craig.helker@wisconsin.gov

Re: Saratoga Lake Sediment Sampling and Analysis Plan

Dear: Mr. Helker,

The purpose of this letter is to submit a sampling and analysis plan for sediment that is planned to be removed due to a proposed upcoming Saratoga Impoundment Dredging project. The sampling is planned to occur concurrently with a sediment profile survey. The sediment profile survey will provide a basis for estimating a potential volumetric range of sediment that will be removed during the dredging.

Please approve or advise modifications to the attached sediment sampling and analysis plan.

If the plan is approved, the completed sampling report and analytical results will be submitted to your office.

Sincerely,

Ayres Associates Inc



Rob Wayne
Environmental Scientist
715.831.7506
WayneR@AyresAssociates.com

**Sediment Sampling and Analysis Plan
Saratoga Lake – Waukesha County, WI**


Preliminary Application Summary, per NR 347.05:

- Name of waterbody and project location:
 - Saratoga Lake/Fox River – Located in City of Waukesha, WI
- Volume of material to be dredged:
 - TBD, if any at all. Purpose of this study is to determine the volumetric build-up of sediment in Saratoga Lake for possible future dredging of Saratoga Lake.
- Dredging method and equipment:
 - TBD
- Disposal method:
 - TBD
- Brief description of known historical chemical use in the waterbody for vegetation / algae control, including year, chemical, and amount applied:
 - It is unknown if any chemicals were used.
 - Most land in the Saratoga Lake watershed is and historically has been residential and agricultural.
- Any previous sediment sampling:
 - 1993 Sediment Sampling
- Copy of a map showing area to be dredged, depth of cut, and proposed sediment sampling site, bathymetry of area to be dredged:
 - See attached map for proposed sediment sampling locations. Bathymetry of existing Saratoga Lake to be mapped based on concurrent sediment profile survey planned to be completed with the sediment sampling work.
- Anticipated starting and completion dates of the proposed project:
 - Preliminary Design by November 2018.

Sampling and Analysis Plan:

- Parameters to be analyzed for, including analytical methods and detection levels:
 - See highlighted rows in attached Table 1.
- Updated sampling location map:
 - See attached map. Proposed locations for sediment sampling and analysis as well as sediment survey profiling are outlined on the map. Exact locations may vary due to field conditions.
- Planned sectioning of cores at each sample location:
 - Two samples will be taken at the sample location point identified on attached map. One sample will be taken in the sediment that is expected to be dredged and one sample will be taken in the lake bed that is expected to remain after sediment removal.
 - At each cross-section line, a probe will be extended to the bottom of the impoundment to measure elevation of the bed. Then, the probe will be hand-pushed into the sediment until refusal to measure depth to 'hard bottom'.
- Sampling methods and sample handling procedures:
 - Sampling will be done from a boat in October 2018.
 - Sampling will be completed in accordance with section 6.2 of the attached document, *Guidance for Applying the Sediment Sampling and Analysis Requirements of Chapter NR 347, Wisconsin Administrative Code*.



- Analytical laboratory certified under NR 149, Adm. Code to conduct parameter analysis.
 - Samples will be tested at a WI DNR approved lab.
 - Pace Analytical Services, LLC in Minneapolis, MN



Notes:

1. Cross section lines is where sediement depth probes will occur.
2. Six sediment samples will be taken. One is sediment that is expected to be removed and one is native sediment that is expected to remain at each of the sample locations.

**Sediment Sample Plan
Saratoga Dam**



**AYRES
ASSOCIATES**

Sustainable solutions since 1959

3433 Oakwood Hills Parkway
Eau Claire, Wisconsin 54701

Saratoga Dam Sediment Sampling - Planned Samples include all highlighted fields.

Table 1. Sediment Sampling Parameters with Suggested Methods and Analyses

Parameter	Suggested Analytical Method (Suggested Detection Level) (mg/kg, dry weight unless noted)	Suggested Base Parameter Analyses ¹	
		Great Lakes or Urban/ Industrial	Inland Waters (Rural/ Forested)
Inorganics - Metals			
Arsenic	SW-846 3050B/6010B EPA 6010 or 7060 (5)	X	X
Barium	SW-846 3050B/6010B (0.2)		
Cadmium	SW-846 3050B/6010B EPA 7131 (0.6)	X	X
Chromium (total)	SW-846 3050B/6010B EPA 6010 or 7191 (0.6)	X	X
Copper	SW-846 3050B/6010B EPA 6010 or 7211 (0.5)	X	X
Cyanide	SW-846 9010B/9014 (0.4)		
Lead	SW-846 3050B/6010B EPA 6010 or 7421 (3)	X	X
Manganese	SW-846 3050B/6010B (0.1)		
Mercury	SW-846 7471A EPA 7471 (0.015)	X	X
Nickel	SW-846 3050B/6010B EPA 6010 (2)	X	X
Selenium	SW-846 3050B/6010B (8)	X	
Zinc	SW-846 3050B/6010B EPA 6010 or 7951 (2)	X	X
Inorganics - Nutrients			
Oil & Grease	SW-846 9070	X	
Total Phosphorus	EPA 365.2/365.3 or USGS I-6600-85 (9.9)	X	X
Nitrate + Nitrite	LACHAT 12-107-04-1-B (0.25)	X	X
Ammonia-Nitrogen	LACHAT 12-107-06-1-A (0.16)	X	X
Total Kjeldahl Nitrogen		X	X
Organics			
Aldrin	SW-846 8081 EPA 8081, 354440B, 3541 (0.01)		
Chlordane	SW-846 8081 EPA 8081, 354440B, 3541 (0.009)	X	
Dieldrin	SW-846 8081 EPA 8081, 354440B, 3541 (0.01)		
Endrin	SW-846 8081 EPA 8081, 354440B, 3541 (0.01)		
Heptachlor	SW-846 8081 EPA 8081, 354440B, 3541 (0.01)		
Lindane (Gamma BHC)	SW-846 8081 EPA 8081, 354440B, 3541 (0.01)		

¹ Suggested base parameter list reflects additions to NR347 Table 1, based on scientific research and experience with dredging projects.

Parameter	Suggested Analytical Method (Suggested Detection Level) (mg/kg, dry weight unless noted)	Suggested Base Parameter Analyses ¹	
		Great Lakes or Urban/ Industrial	Inland Waters (Rural/ Forested)
DDT	SW-846 8081 EPA 8081, 354440B, 3541 (0.01)	X	
DDD & DDE	SW-846 8081 EPA 8081, 354440B, 3541 (0.01)	X	
Toxaphene	SW-846 8081 (0.01)		
PCBs (Total)	SW-846 8081 EPA 8081, 3540B, 3541 (0.04)	X	X
		Tied to Fish Advisories	
2,3,7,8-dioxin, 2,3,7,8-furan and 15 2,3,7,8-substituted dioxin and furan congeners	EPA 8290 (1 – 10 pg/g)		
Total Organic Carbon	SW 846 8081 SW846-EPA 9060 (0.2%)	X	X
Polycyclic Aromatic Hydrocarbons (PAHs)	EPA 8310	X	
Naphthalene	(0.019)		
Phenanthrene	(0.017)		
Pyrene	(0.012)		
Fluorene	(0.058)		
2-Methylnaphthelene			
Acenaphthene	(0.017)		
Acenaphthylene	(0.021)		
Anthracene	(0.0071)		
Benzo (a) anthracene	(0.019)		
Benzo (a) pyrene	(0.023)		
Benzo (e) pyrene			
Benzo (b) fluoranthene	(0.032)		
Benzo (g,h,i) perylene	(0.022)		
Benzo (k) fluoranthene	(0.021)		
Chrysene	(0.0074)		
Dibenzo(a,h)anthracene	(0.008)		
Fluoranthene	(0.029)		
Indeno (1,2,3-cd) pyrene	(0.034)		
Physical Tests			
Particle Size Analysis – Sieve and Hydrometer Analysis	ASTM D-422 (%)	X	X
Moisture Content	ASTM D-2216 (%)	X	X
Atterburg Limits (Liquid Limit and Plastic Limit)	ASTM D4318 (as moisture content)		
Specific Gravity	ASTM D-854 (Ratio, unitless)		



Attachment 2
Conceptual Dredge Drawings

SARATOGA CONCEPTUAL DREDGING PLANS

CITY OF WAUKESHA

WAUKESHA COUNTY, WISCONSIN

NOVEMBER 2019



Sheet Index	
Sheet Number	Sheet Title
1	TITLE
2	LEGEND
3	EXISTING CONTOURS
4	SAMPLES AND PROBE LOCATIONS
5	CROSS SECTIONS
6	CROSS SECTIONS

DIGGERS HOTLINE
1-800-242-8511 OR 811



WAUKESHA COUNTY, WISCONSIN



DES BY	CTG			NOT FOR CONSTRUCTION			
DR BY	RJW	PROJ NO	26-1083.00				
CHK BY	CTG	DATE	NOVEMBER 2019	NO	DATE	REVISION	


SARATOGA CONCEPTUAL DREDGING PLANS
CITY OF WAUKESHA
WAUKESHA COUNTY, WISCONSIN




TITLE

SHEET NO.
1

EXISTING



NEW



ABBREVIATIONS:

AB ANCHOR BOLT	DEFL DEFLECTION	ID INSIDE DIAMETER	PC POINT OF CURVE	T&B TOP & BOTTOM
ABV ABOVE	DEG / ° DEGREE	IF INSIDE FACE	PE PRIVATE ENTRANCE	TC TOP OF CURB
ADJ ADJUST	DF DRINKING FOUNTAIN	IN (") INCHES	PED PEDESTAL	TELE TELEPHONE
AFF ABOVE FINISHED FLOOR	DI DUCTILE IRON	INCL INCLUDE	PERF PERFORATE	THK THICKNESS
AL ALUMINUM	DIA DIAMETER	INF INFLUENT	PI POINT OF INTERSECTION	THRU THROUGH
ALT ALTERNATE WITH	DIM DIMENSION	INL INLET	PKG PARKING	TP TELEPHONE POLE
ALT/ ALTERNATE	DISCH DISCHARGE	INSUL INSULATION	P PLATE	TYP TYPICAL
APPROX APPROXIMATE	DN DOWN	INT INTERIOR	PL PLACE	T/ TOP OF
ASPH ASPHALT	DP DEPTH	INV INVERT	PL P PROPERTY LINE	
AUTO AUTOMATIC	DR DOOR	IP IRON PIPE	PP POWER POLE	UG UNDERGROUND GAS
AVE AVENUE	DTL DETAIL	IPS IRON PIPE SIZE	PSF POUNDS PER SQUARE FOOT	UE UNDERGROUND ELECTRICAL
@ AT	DW DRIVEWAY		PSI POUNDS PER SQUARE INCH	UNEXC UNEXCAVATED
B CRS BASE COURSE	DWG DRAWING	JT JOINT	PT POINT OF TANGENCY	UNO UNLESS NOTED OTHERWISE
BC BACK OF CURB	E EAST	KGV KNIFE GATE VALVE	PV PLUG VALVE	USH UNITED STATES HIGHWAY
BD BOARD	EA EACH	LAB LABORATORY	PVC POLYVINYL CHLORIDE	UT UNDERGROUND TELEPHONE
BEL BELOW	EF EACH FACE	LAV LAVATORY	PVMT PAVEMENT	UV UNDERGROUND VIDEO
BETWN BETWEEN	EFF EFFLUENT	LC LENGTH OF CURVE	PW POTABLE WATER	
BF BACK FACE	EJ EXPANSION JOINT	LF LINEAL FEET	% PERCENT	V VALVE
BFV BUTTERFLY VALVE	EL ELEVATION	LG LENGTH	QTY QUANTITY	V&B VALVE & BOX
BIT BITUMINOUS	ELB ELBOW	LOC LOCATION	RAD RADIUS	VAR VARIABLE
BLD BLIND	ELEC ELECTRICAL	LP LIGHT POLE	RCP REINFORCED CONCRETE PIPE	VER VERTICAL
BLDG BUILDING	EQ EQUAL	LR LONG RADIUS	RD ROAD	VC VERTICAL CURVE
BLK BLOCK	EQUIP EQUIPMENT	LS LUMP SUM	RDWY ROADWAY	W WEST
BLKG BLOCKING	ER END OF RADIUS	LT	RD ROOF DRAIN	W/ WITH
BLVD BOULEVARD	EST ESTIMATE		REDWY REDUCER	W/O WITHOUT
BM BENCHMARK	EW EACH WAY	MAS MASONRY	REF REFERENCE	WD WIDTH
BO BREAKOFF	EWC ELECTRIC WATER COOLER	MAX MAXIMUM	REF REINFORCING	WM WATER MAIN
BRG BEARING	EX EXISTING	MECH MECHANICAL	REIN REINFORCING	WS WATER SURFACE
BRK BRICK	EXH EXHAUST	MFG MANUFACTURER	REM REMOVE	WTP WATER TREATMENT PLANT
BS BACK OF SIDEWALK	EXP EXPANSION	MH MANHOLE	REPL REPLACE	WTR WATER
BTM BOTTOM	EXT EXTERIOR	MIN MINIMUM	REQD REQUIRED	WWF WELDED WIRE FABRIC
BV BALL VALVE	FD FLOOR DRAIN	MISC MISCELLANEOUS	REV REVISED	WWW WOVEN WIRE MESH
B/ BASELINE	FDN FOUNDATION	MJ MECHANICAL JOINT	RM ROOM	WWTP WASTEWATER TREATMENT PLANT
B/ BOTTOM OF	FERT FERTILIZER	MP MID POINT	RR RAILROAD	
C&G CURB AND GUTTER	F-F FACE TO FACE	MTL MATERIAL	RT RIGHT	
CB CATCH BASIN	F-G FIBERGLASS	N NORTH	RW RIGHT OF WAY	
CF CUBIC FOOT	FIN FINISHED	NF NEAR FACE	S SOUTH	
CHKD P CHECKERED PLATE	FL FLOWLINE	NIC NOT IN CONTRACT	SAN SANITARY	
CI CAST IRON	FLG FLANGED	NO NUMBER	SAMH SANITARY MANHOLE	
CJ CONTROL JOINT	FLR FLOOR	NOM NOMINAL	SCH SCHEDULE	
CL / C CENTERLINE	FM FORCE MAIN	NPW NON-POTABLE WATER	SEC SECTION	
CHL CHLORINE	FN FENCE	NTS NOT TO SCALE	SF SQUARE FOOT	
CLG CEILING	FT (') FOOT	OC ON CENTER	SHT SHEET	
CLR CLEAR	FTG FOOTING	OD OUTSIDE DIAMETER	SIM SIMILAR	
CMP CORRUGATED METAL PIPE	FUT FUTURE	OE OVERHEAD ELECTRIC	SL SLOPE	
CMU CONCRETE MASONRY UNIT	G GAS	OF OUTSIDE FACE	SPA SPACE	
CO CLEANOUT	GA GAGE	OH OVERHEAD	SPEC SPECIFICATION	
CONC CONCRETE	GAR GARAGE	OPG OPENING	SQ SQUARE	
CONN CONNECTION	GEN GENERAL	OT OVERHEAD TELEPHONE	SS STAINLESS STEEL	
CONST CONSTRUCTION	GRD GRADE, GROUND		SSMH STORM SEWER MANHOLE	
CONST JT CONSTRUCTION JOINT	GV GATE VALVE		ST STREET	
CONT CONTINUOUS	GRAV GRAVEL		STD STANDARD	
CONTR CONTRACTOR	GW GROUNDWATER		STH STATE TRUNK HIGHWAY	
CONTR JT CONTRACTOR JOINT			STL STEEL	
COR CORNER	HB HOSE BIB		STM STORM	
CP CONTROL POINT	HM HOLLOW METAL		STP SEWAGE TREATMENT PLANT	
CPLG COUPLING	HORZ HORIZONTAL		SURF SURFACE	
CRS COURSE	HSE HOUSE		SW SIDEWALK	
CSP CORRUGATED STEEL PIPE	HT HEIGHT		SWR SEWER	
CTG CASTING	HW HOT WATER		SY SQUARE YARD	
CTH COUNTY TRUNK HIGHWAY	HWR HOT WATER RETURN		SYS SYSTEM	
CULV CULVERT	HYD HYDRANT			
CV CHECK VALVE				
CW COLD WATER				
CY CUBIC YARD				



AA-Standard.snb 11/20/2019 V:\WR-ECW\Kensal\Saratoga Dam Dredging\CAD\Title.dwg, Layout: LEGEND

DES BY	CTG	NOT FOR CONSTRUCTION			
DR BY	RJW	PROJ NO	26-1083.00		
CHK BY	CTG	DATE	NOVEMBER 2019	NO	DATE
			REVISION	NO	DATE
			REVISION	NO	DATE



SARATOGA CONCEPTUAL DREDGING PLANS
CITY OF WAUKESHA
WAUKESHA COUNTY, WISCONSIN



LEGEND

SHEET NO.
2

NOTES:
 1. SOUNDINGS WERE OBTAINED USING A 235 SONAR MITE BT kHz ECHOSOUNDER AND POSITIONED WITH A SUBMETER TRIMBLE GPS
 2. WATER SURFACE ELEVATION = 811.47



DES BY	CTG		NOT FOR CONSTRUCTION					
DR BY	RJW	PROJ NO	26-1083.00					
CHK BY	CTG	DATE	NOVEMBER 2019	NO	DATE	REVISION	NO	DATE



SARATOGA CONCEPTUAL DREDGING PLANS
 CITY OF WAUKESHA
 WAUKESHA COUNTY, WISCONSIN



EXISTING CONTOURS

AA-Standard.snb
 11/20/2019
 V:\WR-EC\Waukesha\Saratoga Dam Dredging\CA Existing Contours.dwg, Layout: EXISTING CONTOURS

NOTES:
 1. SEDIMENT SAMPLES COLLECTED WITH A AMS MULTI-STAGE SEDIMENT SAMPLER.
 2. RANGE POLES WERE USED TO DETERMINE SEDIMENT THICKNESS.



AA-Standard.snb
 11/20/2019
 V:\WR-EC\Waukesha\Saratoga Dam Dredging\CA\Existing Contours.dwg; Layout: SAMPLES AND PROBE LOCATIONS

DES BY	CTG						
DR BY	RJW	PROJ NO	26-1083.00				
CHK BY	CTG	DATE	NOVEMBER 2019	NO	DATE	REVISION	

SARATOGA CONCEPTUAL DREDGING PLANS
 CITY OF WAUKESHA
 WAUKESHA COUNTY, WISCONSIN




SAMPLES AND PROBE LOCATIONS
 SHEET NO. 4


NOTES:

1. SOUNDINGS WERE OBTAINED USING A 235 SONAR/MTM BT kHz ECHOSOUNDER AND POSITIONED WITH A SUBMETER TRIMBLE GPS.
2. WATER SURFACE ELEVATION = 811.47
3. SEDIMENT SAMPLES COLLECTED WITH A AMS MULTI-STAGE SEDIMENT SAMPLER.
4. RANGE POLES WERE USED TO DETERMINE SEDIMENT THICKNESS.
5. APPROXIMATELY 65,000 CY OF SEDIMENT WITHIN SURVEY AREA.
6. NO DREDGING WITHIN 10 FEET OF THE SHORELINE.


CROSS SECTION 33+61



CROSS SECTION 26+14



CROSS SECTION 20+57



AA-Standard.stb 11/20/2019 V:\WR-EC\Waukesha\Saratoga Dam Dredging\CA\Existing Contours.dwg Layout: CROSS SECTIONS

DES BY	CTG	PROJ NO					
DR BY	RJW	26-1083.00					
CHK BY	CTG	DATE	NO	DATE	NO	DATE	REVISION
		NOVEMBER 2019					

SARATOGA CONCEPTUAL DREDGING PLANS
CITY OF WAUKESHA
WAUKESHA COUNTY, WISCONSIN




CROSS SECTIONS

SHEET NO.
5


NOTES:

1. SOUNDINGS WERE OBTAINED USING A 235 SONAR/MTM BT kHz ECHOSOUNDER AND POSITIONED WITH A SUBMETER TRIMBLE GPS.
2. WATER SURFACE ELEVATION = 811.47
3. SEDIMENT SAMPLES COLLECTED WITH A AMS MULTI-STAGE SEDIMENT SAMPLER.
4. RANGE POLES WERE USED TO DETERMINE SEDIMENT THICKNESS.
5. APPROXIMATELY 65,000 CY OF SEDIMENT WITHIN SURVEY AREA.
6. NO DREDGING WITHIN 10 FEET OF THE SHORELINE.


CROSS SECTION 16+27



CROSS SECTION 11+76



CROSS SECTION 6+74



AA-Standard.stb 11/20/2019 I:\261\Waukesha\Saratoga Dam Dredging\CAD\Existing Contours.dwg, Layout: CROSS SECTIONS (2)

DES BY	CTG	PROJ NO	26-1083.00				
DR BY	RJW	DATE	NOVEMBER 2019	NO	DATE	REVISION	
CHK BY	CTG						

SARATOGA CONCEPTUAL DREDGING PLANS
CITY OF WAUKESHA
WAUKESHA COUNTY, WISCONSIN



CROSS SECTIONS

SHEET NO.

6

Attachment 3
Cost Estimate



Opinion of Probable Cost

Nov-19

Project: Saratoga Dredging
 Client: City of Waukesha
 Location: Waukesha, WI
 Project No.: 26-1083.00

References: 1.) *Heavy Construction Cost Data*. RSMMeans. 32th Annual Edition. 2018.

RS Means Item Number and Description	Unit	Quantity	2018 Bare Costs			Total Incl O&P	Total Item Cost Incl O&P	Notes:
			Material	Labor	Equipment			
35 24 13.13 Cutter Suction Dredging								
1500 Hydraulic method, pumped	C.Y.	65000		9.15	7.50	16.65	22.00 \$	1,430,000.00
35 24 23.13 Mobilization								
100 Dredging	Total	1		29,600	28800.00	58,400	76,500 \$	76,500.00
31 23 23.20 Hauling								
1468 12 C.Y. Truck, 35 MPH avg, Cycle 20 miles	C.Y.	65000		3.83	5.65	9.48	11.95 \$	776,750.00
Misc								
Dewatering of Dredged Sediment	C.Y.	65000					10 \$	650,000.00 Previous bids
Landfill Disposal	Ton	84500					36.5 \$	3,084,250.00 Price from Waste Management
Erosion Control (Silt Fence/Turbidity Barriers)	L.S.	1					\$	15,000.00 Previous bids
Site Restoration	L.S.	1					\$	20,000.00 Previous bids
Subtotal for Division 31 - Earthwork =							\$	6,052,500.00

Subtotal for All Divisions = \$ 6,052,500.00
Contingency (15%) = \$ 907,875.00
Total Construction Cost = \$ 6,960,375.00



October 3, 2019

Mr Rob Wayne
Ayres & Associates
Eau Claire, WI

Project: City of Waukesha-Fox River Dredge Project, 2020-2021

Dear Rob,

Waste Management of Wisconsin is pleased to provide you with pricing for disposal per your request. Based upon the information provided, the following summarizes our quotation.

DISPOSAL FACILITY:

Orchard Ridge Landfill	Metro Security Landfill
W124 N9355 Boundary Road	10712 S. 124 th Street
Menomonee Falls, WI 53051	Franklin, WI 53132

WASTE STREAMS

Waste Description	Contaminated Dredge Sediment
Estimated Volume	65,000 cubic yards
Disposal Method	Direct Landfill

Estimated Disposal Pricing

Base	\$21.00/ton
WI Generator Tax	\$13.00/ton
Landfill Environmental Fee	\$ 1.50/ton
<u>Disposal Fuel Surcharge</u>	<u>\$ 1.00/ton</u>
ALL IN	\$36.50 per ton
Profile Approval Fee	\$100 (one time) per profile submitted.

Credit Charges (after 45 days) 1.5% of outstanding invoice balance.

SPECIAL CONDITIONS:

Waste must meet acceptability criteria at the site and comply with local, state and federal regulations, as well as the sites permit requirements.



Strength and moisture requirements are:

1. No free liquid—Pass Paint Filter test.
2. Able to
 - a. Support its own weight;
 - b. Support the weight of material placed over it;
 - c. Be capable of being worked and managed by the Disposal Site's low ground pressure bulldozers.

The dredge material must be dewatered as necessary to pass the paint filter test prior to disposal. The dredge material must be transported in leak proof and covered trucks to prevent leakage and air borne transport of sediments.

The dredge material must be stabilized and received in a soil like consistency that allows Orchard Ridge Landfill, or Metro Security landfill to follow the regulatory requirements of placing the material in a manner such that it supports its own weight, supports the weight of other materials placed over it without slumping, and maintains the integrity and stability of the landfill slopes.

ANALYTICAL TESTING REQUIREMENTS:

Complete and submit profile with analytical testing attached – submit online www.wmsolutions.com

***Pricing is contingent upon review and approval of profile submittal along with full lab testing results.**

Customers must have a current Waste Management Industrial Service Agreement.

Pricing is open for consideration for a period of 30 days. Upon acceptance, pricing remains in effect up to and including 60 days from the date of the quote. Pricing based solely on the information available at this time. Additional information may be required prior to approval.

Please do not hesitate to contact me at the phone number below with any questions you may have or if you require any further assistance.

Sincerely,
Brian

Brian Smith
Industrial Account Manager
Manufacturing & Industrial
Bsmith45@WM.com
414-793-0232

From: [Scott Kleinhans](#)
To: [Wayne, Robert](#)
Subject: RE: Dredging Disposal Quote
Date: Tuesday, August 27, 2019 2:37:35 PM
Attachments: [image001.png](#)

Wayne,

There are several issues that will affect the potential pricing. Moisture content, material strength and daily volume intake are three of the biggest. With that said, I can give you a range for budgetary purposes.

The stronger and dryer the material is the lower the cost. If we have to do any type of special handling, monofiling or drainage, the pricing will go up.

For budget purposes, you can use \$15-\$40/T for disposal. Again, this is very preliminary and will depend greatly on what the material ends up looking like coming to the landfill.

Please feel free to reach out with any other questions.

Thanks,

Scott Kleinhans | Landfill Sales



Advanced Disposal Emerald Park Landfill, LLC
W124 S10629 S. 124th St. | Muskego | WI 53150
T: 414-529-1360 | F: 414-529-1478 | M: 414-807-7101 | E: scott.kleinhans@advanceddisposal.com

Advanced Disposal Mallard Ridge Landfill, Inc.
W8470 State RD 11 | Delavan | WI 53115
T: 262-724-3257 | F: 262-724-5479

Connect with us: AdvancedDisposal.com [Facebook](#) [YouTube](#)

Clean & Green: Please consider the environment before printing this e-mail

This e-mail message from Advanced Disposal Services is for the sole use of the intended recipient(s) and may contain confidential and privileged information. Any unauthorized review, use, disclosure or distribution is prohibited. If you are not the intended recipient, please communicate with the sender by reply e-mail and destroy all copies of the original message and delete same from all computers.

From: Wayne, Robert [mailto:WayneR@AyresAssociates.com]
Sent: Tuesday, August 27, 2019 2:11 PM
To: Scott Kleinhans <scott.kleinhans@advanceddisposal.com>
Subject: RE: Dredging Disposal Quote

We are still in the conceptual phase but it is anticipated to start in 2020 or 2021 and the duration would be approximately 3 months.

Robert J Wayne

Environmental Scientist

Office: 715.834.3161 • Direct: 715.831.7506

WayneR@AyresAssociates.com

www.AyresAssociates.com

From: Scott Kleinhans <scott.kleinhans@advanceddisposal.com>

Sent: Tuesday, August 27, 2019 10:05 AM

To: Wayne, Robert <WayneR@AyresAssociates.com>

Cc: Goodwin, Chris <Goodwinc@AyresAssociates.com>

Subject: RE: Dredging Disposal Quote

Wayne,

I do have a couple questions that revolve around project timing. Any idea on a start date? Thoughts on project duration. If I can get an idea on when things will happen, that will help.

Thanks,

Scott Kleinhans | Landfill Sales



Advanced Disposal Emerald Park Landfill, LLC

W124 S10629 S. 124th St. | Muskego | WI 53150

T: 414-529-1360 | F: 414-529-1478 | M: 414-807-7101 | E: scott.kleinhans@advanceddisposal.com

Advanced Disposal Mallard Ridge Landfill, Inc.

W8470 State RD 11 | Delavan | WI 53115

T: 262-724-3257 | F: 262-724-5479

Connect with us: AdvancedDisposal.com [Facebook](#) [YouTube](#)

Clean & Green: Please consider the environment before printing this e-mail

This e-mail message from Advanced Disposal Services is for the sole use of the intended recipient(s) and may contain confidential and privileged information. Any unauthorized review, use, disclosure or distribution is prohibited. If you are not the intended recipient, please communicate with the sender by reply e-mail and destroy all copies of the original message and delete same from all computers.

From: Wayne, Robert [<mailto:WayneR@AyresAssociates.com>]

Sent: Tuesday, August 27, 2019 9:26 AM

To: Scott Kleinhans <scott.kleinhans@advanceddisposal.com>

Cc: Goodwin, Chris <Goodwinc@AyresAssociates.com>

Subject: Dredging Disposal Quote

Hi Scott,

We are working with the City of Waukesha on a dredging project in the Fox River and we are looking

into disposal site options for 65,000 CY of contaminated soil.

Can you provide me with a quote for disposing of the sediment?

Attached are the soil testing results.

The conceptual plan for dredging would be to dewater the sediment in geotextile tubes until the acceptable moisture content. What moisture content is acceptable for disposal?

Let me know if you need any additional information.

Thank you,

Rob



Robert J Wayne

Environmental Scientist

Ayres Associates

3433 Oakwood Hills Parkway • Eau Claire, WI 54701-7698

Office: 715.834.3161 • Direct: 715.831.7506

WayneR@AyresAssociates.com

www.AyresAssociates.com

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Attachment 4
Sample Analytical Results

Saratoga Lake Sediment Sampling

October 3, 2018 Samples
Complete Sampling Results

Non-Industrial Direct Contact RCL	Industrial Direct Contact RCL	Ground Water RCL	Back ground Threshold Value
-----------------------------------	-------------------------------	------------------	-----------------------------

Parameter	Sample					
	1	2	3	4	5	6
Arsenic	31.8	18.3	22.1	13.6	15.6	15.4
Cadmium	3.4	0.97 J	0.88 J	0.92 J	0.35 J	0.31 J
Chromium	104	27.6	30.0	30.0	18.1	22.4
Copper	69.5	69.8	38.4	66.1	25.1	30.1
Lead	281	66.4	60.0	38.8	20.8	23.3
Nickel	48.7	18.1	21.4	20.1	14.4	18.9
Zinc	444	187	157	186	79.3	94.0
Mercury	0.17 J	0.17 J	0.17 J	0.13 J	0.073 J	0.078 J
PCB, Total	<0.0653	<0.0584	<0.0560	<0.0615	<0.0497	<0.0443
PCB-1016 (Aroclor 1016)	<0.0761	<0.0680	<0.0653	<0.0716	<0.0579	<0.0516
PCB-1221 (Aroclor 1221)	<0.0960	<0.0858	<0.0824	<0.0904	<0.0731	<0.0652
PCB-1232 (Aroclor 1232)	<0.109	<0.0976	<0.0937	<0.103	<0.0832	<0.0742
PCB-1242 (Aroclor 1242)	<0.0927	<0.0828	<0.0795	<0.0873	<0.0706	<0.0629
PCB-1248 (Aroclor 1248)	<0.0820	<0.0732	<0.0703	<0.0771	<0.0624	<0.0556
PCB-1254 (Aroclor 1254)	<0.0804	<0.0718	<0.0689	<0.0757	<0.0612	<0.0546
PCB-1260 (Aroclor 1260)	<0.0653	<0.0584	<0.0560	<0.0615	<0.0497	<0.0443
PCB-1262 (Aroclor 1262)	<0.0944	<0.0843	<0.0809	<0.0888	<0.0718	<0.0641
PCB-1268 (Aroclor 1268)	<0.0886	<0.0791	<0.0760	<0.0834	<0.0674	<0.0601
2-Methylnaphthalene	<0.0209	0.420	0.0226	<0.0197	<0.0032	<0.0029
Acenaphthene	0.293	3.55	0.0320	<0.0159	<0.0026	<0.0023
Acenaphthylene	0.405	1.73	0.0319	<0.0193	0.0317	<0.0028
Anthracene	0.799	10.1	0.0891	0.143	0.0244	<0.0026
Benzo(a)anthracene	2.80	20.1	0.440	0.744	0.119	0.0300
Benzo(a)pyrene	2.81	19.5	0.522	1.02	0.134	0.0340
Benzo(b)fluoranthene	3.62	23.9	0.685	1.51	0.175	0.0490
Benzo(e)pyrene	2.07	13.2	0.405	0.819	0.0962	0.0258
Benzo(g,h,i)perylene	1.79	11.9	0.381	0.770	0.0904	0.0245
Benzo(k)fluoranthene	1.57	9.59	0.242	0.599	0.0575	0.0174
Chrysene	2.72	19.8	0.506	1.04	0.131	0.0351
Dibenz(a,h)anthracene	0.436	3.46	0.0792	0.180	<0.0029	<0.0026
Fluoranthene	7.34	51.5	1.11	2.11	0.214	0.0726
Fluorene	0.562	4.35	0.0449	<0.0122	<0.0020	<0.0018
Indeno(1,2,3-cd)pyrene	1.63	10.7	0.310	0.712	0.0741	0.0205
Naphthalene	<0.0319	1.49	<0.0055	<0.0301	<0.0049	<0.0044
Phenanthrene	3.68	35.6	0.418	0.715	0.0539	0.0221
Pyrene	5.76	39.0	0.881	1.56	0.206	0.0651

0.677	3	0.584	8
71.1	985	0.752	1
100000	100000	360,000.	44
3,130.	46,700.	91.6	69.5
400	800	27.	52
1,550.	22,500.	13.0612	31
23,500.	100,000.	NA	150
3.13	3.13	0.208	NA
0.234	0.967	0.0094	NA
4.11	28	NA	NA
0.213	0.883	NA	NA
0.19	0.792	NA	NA
0.235	0.972	NA	NA
0.236	0.975	NA	NA
0.239	0.988	NA	NA
0.243	1	NA	NA
NA	NA	NA	NA
NA	NA	NA	NA
239	3010	NA	NA
3590	45200	NA	NA
NA	NA	NA	NA
17900	100000	196.9492	NA
1.14	20.8	NA	NA
0.115	2.11	0.47	NA
1.15	21.1	0.4781	NA
NA	NA	NA	NA
NA	NA	NA	NA
11.5	211	NA	NA
115	2110	0.1442	NA
0.115	2.11	NA	NA
2390	30100	88.8778	NA
2390	30100	14.8299	NA
1.15	21.1	NA	NA
5.52	24.1	0.6582	NA
NA	NA	NA	NA
1790	22600	54.5455	NA

Cumulative

Exceedance Count	6	6	1	4	2	1
Hazard Index	1.19969	1.9617	0.1333	0.5684	0.5258	0.5075
Cumulative Cancer Risk	8.50E-05	2.8E-04	8.3E-06	3.6E-05	2.7E-05	2.5E-05

NR720 Groundwater RCL Exceedence

NR 720 Non Industrial Exceedence

NR 720 Industrial Exceedence

All results in mg/kg, equivalent to PPM

Saratoga Lake Sediment Sampling

October 3, 2018 Samples
Detects Only

Non-Industrial Direct Contact RCL	Industrial Direct Contact RCL	Ground Water RCL	Back ground Threshold Value
-----------------------------------	-------------------------------	------------------	-----------------------------

Detects Only	Sample					
	1	2	3	4	5	6
Arsenic	<u>31.8</u>	<u>18.3</u>	<u>22.1</u>	<u>13.6</u>	<u>15.6</u>	<u>15.4</u>
Cadmium	3.4	0.97J	0.88J	0.92J		
Lead	281	66.4	60.0	38.8		
Nickel	48.7	18.1	21.4	20.1	14.4	18.9
Benzo(a)anthracene	<u>2.80</u>	<u>20.1</u>				
Benzo(a)pyrene	<u>2.81</u>	<u>19.5</u>	<u>0.522</u>	<u>1.02</u>	<u>0.134</u>	
Benzo(b)fluoranthene	<u>3.62</u>	<u>23.9</u>	0.685	<u>1.51</u>		
Chrysene	2.72	19.8	0.506	1.04		
Dibenz(a,h)anthracene	<u>0.436</u>	<u>3.46</u>		<u>0.180</u>		
Indeno(1,2,3-cd)pyrene	<u>1.63</u>	<u>10.7</u>				
Naphthalene		1.49				

0.677	3	0.584	8
71.1	985	0.752	1
400	800	27.	52
1,550.	22,500.	13.0612	31
1.14	20.8	NA	NA
0.115	2.11	0.47	NA
1.15	21.1	0.4781	NA
115	2110	0.1442	NA
0.115	2.11	NA	NA
1.15	21.1	NA	NA
5.52	24.1	0.6582	NA

Cumulative

Exceedance Count	6	6	1	4	2	1
Hazard Index	1.19969	1.9617	0.1333	0.5684	0.5258	0.5075
Cumulative Cancer Risk	8.50E-05	2.8E-04	8.3E-06	3.6E-05	2.7E-05	2.5E-05

NR720 Groundwater RCL Exceedence

NR 720 Non Industrial Exceedence

NR 720 Industrial Exceedence

All results in mg/kg, equivalent to PPM

October 30, 2018

Peter Haug
Ayres Associates
3433 Oakwood Hills Parkway
Eau Claire, WI 54701

RE: Project: Saratoga Dam
Pace Project No.: 10450829

Dear Peter Haug:

Enclosed are the analytical results for sample(s) received by the laboratory on October 09, 2018. The results relate only to the samples included in this report. Results reported herein conform to the most current, applicable TNI/NELAC standards and the laboratory's Quality Assurance Manual, where applicable, unless otherwise noted in the body of the report.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Bob Michels
bob.michels@pacelabs.com
(612)709-5046
Project Manager

Enclosures



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

CERTIFICATIONS

Project: Saratoga Dam
Pace Project No.: 10450829

Minnesota Certification IDs

1700 Elm Street SE, Minneapolis, MN 55414-2485
A2LA Certification #: 2926.01
Alabama Certification #: 40770
Alaska Contaminated Sites Certification #: 17-009
Alaska DW Certification #: MN00064
Arizona Certification #: AZ0014
Arkansas DW Certification #: MN00064
Arkansas WW Certification #: 88-0680
California Certification #: 2929
CNMI Saipan Certification #: MP0003
Colorado Certification #: MN00064
Connecticut Certification #: PH-0256
EPA Region 8+Wyoming DW Certification #: via MN 027-053-137
Florida Certification #: E87605
Georgia Certification #: 959
Guam EPA Certification #: MN00064
Hawaii Certification #: MN00064
Idaho Certification #: MN00064
Illinois Certification #: 200011
Indiana Certification #: C-MN-01
Iowa Certification #: 368
Kansas Certification #: E-10167
Kentucky DW Certification #: 90062
Kentucky WW Certification #: 90062
Louisiana DEQ Certification #: 03086
Louisiana DW Certification #: MN00064
Maine Certification #: MN00064
Maryland Certification #: 322
Massachusetts Certification #: M-MN064
Michigan Certification #: 9909

Minnesota Certification #: 027-053-137
Minnesota Dept of Ag Certification #: via MN 027-053-137
Minnesota Petrofund Certification #: 1240
Mississippi Certification #: MN00064
Montana Certification #: CERT0092
Nebraska Certification #: NE-OS-18-06
Nevada Certification #: MN00064
New Hampshire Certification #: 2081
New Jersey Certification #: MN002
New York Certification #: 11647
North Carolina DW Certification #: 27700
North Carolina WW Certification #: 530
North Dakota Certification #: R-036
Ohio DW Certification #: 41244
Ohio VAP Certification #: CL101
Oklahoma Certification #: 9507
Oregon NwTPH Certification #: MN300001
Oregon Secondary Certification #: MN200001
Pennsylvania Certification #: 68-00563
Puerto Rico Certification #: MN00064
South Carolina Certification #: 74003001
Tennessee Certification #: TN02818
Texas Certification #: T104704192
Utah Certification #: MN00064
Virginia Certification #: 460163
Washington Certification #: C486
West Virginia DW Certification #: 9952 C
West Virginia DEP Certification #: 382
Wisconsin Certification #: 999407970
Wyoming UST Certification #: via A2LA 2926.01

Virginia Minnesota Certification ID's

315 Chestnut Street, Virginia, MN 55792
Montana Certificate #CERT0103
Alaska Certification UST-107
Minnesota Dept of Health Certification #: 027-137-445

North Dakota Certification: # R-203
Wisconsin DNR Certification #: 998027470
WA Department of Ecology Lab ID# C1007

Green Bay Certification IDs

1241 Bellevue Street, Green Bay, WI 54302
Florida/NELAP Certification #: E87948
Illinois Certification #: 200050
Kentucky UST Certification #: 82
Louisiana Certification #: 04168
Minnesota Certification #: 055-999-334
New York Certification #: 12064
North Dakota Certification #: R-150

Virginia VELAP ID: 460263
South Carolina Certification #: 83006001
Texas Certification #: T104704529-14-1
Wisconsin Certification #: 405132750
Wisconsin DATCP Certification #: 105-444
USDA Soil Permit #: P330-16-00157
Federal Fish & Wildlife Permit #: LE51774A-0

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE SUMMARY

Project: Saratoga Dam

Pace Project No.: 10450829

Lab ID	Sample ID	Matrix	Date Collected	Date Received
10450829001	1	Solid	10/03/18 12:30	10/09/18 09:20
10450829002	2	Solid	10/03/18 12:35	10/09/18 09:20
10450829003	3	Solid	10/03/18 12:40	10/09/18 09:20
10450829004	4	Solid	10/03/18 12:45	10/09/18 09:20
10450829005	5	Solid	10/03/18 12:50	10/09/18 09:20
10450829006	6	Solid	10/03/18 12:55	10/09/18 09:20

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE ANALYTE COUNT

Project: Saratoga Dam

Pace Project No.: 10450829

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
10450829001	1	EPA 8082A	RAG	12	PASI-M
		EPA 6010	TXW	7	PASI-G
		EPA 7471	AJT	1	PASI-G
		ASTM D2974	JDL	1	PASI-M
		EPA 8270D by SIM	STB	20	PASI-M
		EPA 350.1	DMB	1	PASI-V
		EPA 351.2	DMB	1	PASI-V
		EPA 353.2	DMB	1	PASI-V
		EPA 365.1	DMB	1	PASI-V
		EPA 9060A	CSD	4	PASI-V
10450829002	2	EPA 8082A	RAG	12	PASI-M
		EPA 6010	TXW	7	PASI-G
		EPA 7471	AJT	1	PASI-G
		ASTM D2974	JDL	1	PASI-M
		EPA 8270D by SIM	STB	20	PASI-M
		EPA 350.1	DMB	1	PASI-V
		EPA 351.2	DMB	1	PASI-V
		EPA 353.2	DMB	1	PASI-V
		EPA 365.1	DMB	1	PASI-V
		EPA 9060A	CSD	4	PASI-V
10450829003	3	EPA 8082A	RAG	12	PASI-M
		EPA 6010	TXW	7	PASI-G
		EPA 7471	AJT	1	PASI-G
		ASTM D2974	JDL	1	PASI-M
		EPA 8270D by SIM	STB	20	PASI-M
		EPA 350.1	DMB	1	PASI-V
		EPA 351.2	DMB	1	PASI-V
		EPA 353.2	DMB	1	PASI-V
		EPA 365.1	DMB	1	PASI-V
		EPA 9060A	CSD	4	PASI-V
10450829004	4	EPA 8082A	RAG	12	PASI-M
		EPA 6010	TXW	7	PASI-G
		EPA 7471	AJT	1	PASI-G
		ASTM D2974	JDL	1	PASI-M
		EPA 8270D by SIM	STB	20	PASI-M
		EPA 350.1	DMB	1	PASI-V
		EPA 351.2	DMB	1	PASI-V

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE ANALYTE COUNT

Project: Saratoga Dam

Pace Project No.: 10450829

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
10450829005	5	EPA 353.2	DMB	1	PASI-V
		EPA 365.1	DMB	1	PASI-V
		EPA 9060A	CSD	4	PASI-V
		EPA 8082A	RAG	12	PASI-M
		EPA 6010	TXW	7	PASI-G
		EPA 7471	AJT	1	PASI-G
		ASTM D2974	JDL	1	PASI-M
		EPA 8270D by SIM	STB	20	PASI-M
		EPA 350.1	DMB	1	PASI-V
		EPA 351.2	DMB	1	PASI-V
		EPA 353.2	DMB	1	PASI-V
		EPA 365.1	DMB	1	PASI-V
		EPA 9060A	CSD	4	PASI-V
		EPA 8082A	RAG	12	PASI-M
10450829006	6	EPA 6010	TXW	7	PASI-G
		EPA 7471	AJT	1	PASI-G
		ASTM D2974	JDL	1	PASI-M
		EPA 8270D by SIM	STB	20	PASI-M
		EPA 350.1	DMB	1	PASI-V
		EPA 351.2	DMB	1	PASI-V
		EPA 353.2	DMB	1	PASI-V
		EPA 365.1	DMB	1	PASI-V
		EPA 9060A	CSD	4	PASI-V

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: Saratoga Dam
Pace Project No.: 10450829

Sample: 1 **Lab ID: 10450829001** Collected: 10/03/18 12:30 Received: 10/09/18 09:20 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8082A GCS PCB									
Analytical Method: EPA 8082A Preparation Method: EPA 3550									
PCB-1016 (Aroclor 1016)	ND	ug/kg	76.1	22.8	1	10/12/18 07:51	10/12/18 21:04	12674-11-2	
PCB-1221 (Aroclor 1221)	ND	ug/kg	96.0	28.8	1	10/12/18 07:51	10/12/18 21:04	11104-28-2	
PCB-1232 (Aroclor 1232)	ND	ug/kg	109	32.8	1	10/12/18 07:51	10/12/18 21:04	11141-16-5	
PCB-1242 (Aroclor 1242)	ND	ug/kg	92.7	27.8	1	10/12/18 07:51	10/12/18 21:04	53469-21-9	
PCB-1248 (Aroclor 1248)	ND	ug/kg	82.0	24.6	1	10/12/18 07:51	10/12/18 21:04	12672-29-6	
PCB-1254 (Aroclor 1254)	ND	ug/kg	80.4	24.1	1	10/12/18 07:51	10/12/18 21:04	11097-69-1	
PCB-1260 (Aroclor 1260)	ND	ug/kg	65.3	19.6	1	10/12/18 07:51	10/12/18 21:04	11096-82-5	
PCB-1262 (Aroclor 1262)	ND	ug/kg	94.4	28.3	1	10/12/18 07:51	10/12/18 21:04	37324-23-5	
PCB-1268 (Aroclor 1268)	ND	ug/kg	88.6	26.6	1	10/12/18 07:51	10/12/18 21:04	11100-14-4	
PCB, Total	ND	ug/kg	65.3	19.6	1	10/12/18 07:51	10/12/18 21:04	1336-36-3	
Surrogates									
Tetrachloro-m-xylene (S)	75	%	48-125		1	10/12/18 07:51	10/12/18 21:04	877-09-8	
Decachlorobiphenyl (S)	73	%	30-134		1	10/12/18 07:51	10/12/18 21:04	2051-24-3	
6010 MET ICP									
Analytical Method: EPA 6010 Preparation Method: EPA 3050									
Arsenic	31.8	mg/kg	11.5	2.4	1	10/18/18 09:13	10/27/18 10:11	7440-38-2	
Cadmium	3.4	mg/kg	1.1	0.30	1	10/18/18 09:13	10/27/18 10:11	7440-43-9	
Chromium	104	mg/kg	2.3	0.64	1	10/18/18 09:13	10/27/18 10:11	7440-47-3	
Copper	69.5	mg/kg	3.4	1.0	1	10/18/18 09:13	10/27/18 10:11	7440-50-8	
Lead	281	mg/kg	4.6	1.4	1	10/18/18 09:13	10/27/18 10:11	7439-92-1	
Nickel	48.7	mg/kg	2.3	0.53	1	10/18/18 09:13	10/27/18 10:11	7440-02-0	
Zinc	444	mg/kg	9.2	2.3	1	10/18/18 09:13	10/27/18 10:11	7440-66-6	
7471 Mercury									
Analytical Method: EPA 7471 Preparation Method: EPA 7471									
Mercury	0.17J	mg/kg	0.29	0.086	1	10/17/18 13:25	10/18/18 09:32	7439-97-6	
Dry Weight / %M by ASTM D2974									
Analytical Method: ASTM D2974									
Percent Moisture	59.9	%	0.10	0.10	1		10/18/18 13:14		
8270D MSSV PAH by SIM									
Analytical Method: EPA 8270D by SIM Preparation Method: EPA 3550									
Acenaphthene	293	ug/kg	16.9	5.1	5	10/17/18 17:48	10/19/18 03:10	83-32-9	
Acenaphthylene	405	ug/kg	20.5	6.2	5	10/17/18 17:48	10/19/18 03:10	208-96-8	
Anthracene	799	ug/kg	19.4	5.8	5	10/17/18 17:48	10/19/18 03:10	120-12-7	
Benzo(a)anthracene	2800	ug/kg	44.7	13.4	5	10/17/18 17:48	10/19/18 03:10	56-55-3	
Benzo(a)pyrene	2810	ug/kg	28.4	8.5	5	10/17/18 17:48	10/19/18 03:10	50-32-8	
Benzo(b)fluoranthene	3620	ug/kg	15.4	4.6	5	10/17/18 17:48	10/19/18 03:10	205-99-2	
Benzo(e)pyrene	2070	ug/kg	29.8	8.9	5	10/17/18 17:48	10/19/18 03:10	192-97-2	
Benzo(g,h,i)perylene	1790	ug/kg	26.2	7.9	5	10/17/18 17:48	10/19/18 03:10	191-24-2	N2
Benzo(k)fluoranthene	1570	ug/kg	35.0	10.5	5	10/17/18 17:48	10/19/18 03:10	207-08-9	
Chrysene	2720	ug/kg	56.3	16.9	5	10/17/18 17:48	10/19/18 03:10	218-01-9	
Dibenz(a,h)anthracene	436	ug/kg	19.1	5.7	5	10/17/18 17:48	10/19/18 03:10	53-70-3	
Fluoranthene	7340	ug/kg	88.6	26.6	25	10/17/18 17:48	10/19/18 13:10	206-44-0	
Fluorene	562	ug/kg	13.0	3.9	5	10/17/18 17:48	10/19/18 03:10	86-73-7	
Indeno(1,2,3-cd)pyrene	1630	ug/kg	27.7	8.3	5	10/17/18 17:48	10/19/18 03:10	193-39-5	
2-Methylnaphthalene	ND	ug/kg	20.9	6.3	5	10/17/18 17:48	10/19/18 03:10	91-57-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: Saratoga Dam

Pace Project No.: 10450829

Sample: 1 **Lab ID: 10450829001** Collected: 10/03/18 12:30 Received: 10/09/18 09:20 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270D MSSV PAH by SIM		Analytical Method: EPA 8270D by SIM Preparation Method: EPA 3550							
Naphthalene	ND	ug/kg	31.9	9.6	5	10/17/18 17:48	10/19/18 03:10	91-20-3	
Phenanthrene	3680	ug/kg	79.5	23.9	5	10/17/18 17:48	10/19/18 03:10	85-01-8	
Pyrene	5760	ug/kg	317	95.1	25	10/17/18 17:48	10/19/18 13:10	129-00-0	
Surrogates									
2-Fluorobiphenyl (S)	90	%	42-125		5	10/17/18 17:48	10/19/18 03:10	321-60-8	D3
p-Terphenyl-d14 (S)	89	%	57-125		5	10/17/18 17:48	10/19/18 03:10	1718-51-0	
350.1 Ammonia		Analytical Method: EPA 350.1 Preparation Method: EPA 350.1							
Nitrogen, Ammonia	821	mg/kg	42.7	20.6	2	10/11/18 14:36	10/12/18 07:20	7664-41-7	
351.2 Total Kjeldahl Nitrogen		Analytical Method: EPA 351.2 Preparation Method: EPA 351.2							
Nitrogen, Kjeldahl, Total	6980	mg/kg	1190	520	5	10/15/18 10:16	10/16/18 16:00	7727-37-9	
353.2 Nitrogen, NO2/NO3		Analytical Method: EPA 353.2 Preparation Method: EPA 353.2							
Nitrogen, NO2 plus NO3	ND	mg/kg	1.2	0.29	1	10/12/18 07:44	10/12/18 15:51		N3
365.1 Phosphorus, Total		Analytical Method: EPA 365.1 Preparation Method: SM 4500P B							
Phosphorus	743	mg/kg	144	68.3	10	10/10/18 14:00	10/11/18 09:05	7723-14-0	
Total Organic Carbon		Analytical Method: EPA 9060A							
RPD%	5.7	%			1		10/25/18 10:45		
Total Organic Carbon	87800	mg/kg	2710	561	1		10/25/18 10:36	7440-44-0	
Total Organic Carbon	92900	mg/kg	2970	615	1		10/25/18 10:45	7440-44-0	
Mean Total Organic Carbon	90300	mg/kg	2840	588	1		10/25/18 10:45	7440-44-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: Saratoga Dam
Pace Project No.: 10450829

Sample: 2 **Lab ID: 10450829002** Collected: 10/03/18 12:35 Received: 10/09/18 09:20 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8082A GCS PCB									
Analytical Method: EPA 8082A Preparation Method: EPA 3550									
PCB-1016 (Aroclor 1016)	ND	ug/kg	68.0	20.4	1	10/12/18 07:51	10/12/18 21:20	12674-11-2	
PCB-1221 (Aroclor 1221)	ND	ug/kg	85.8	25.8	1	10/12/18 07:51	10/12/18 21:20	11104-28-2	
PCB-1232 (Aroclor 1232)	ND	ug/kg	97.6	29.3	1	10/12/18 07:51	10/12/18 21:20	11141-16-5	
PCB-1242 (Aroclor 1242)	ND	ug/kg	82.8	24.9	1	10/12/18 07:51	10/12/18 21:20	53469-21-9	
PCB-1248 (Aroclor 1248)	ND	ug/kg	73.2	22.0	1	10/12/18 07:51	10/12/18 21:20	12672-29-6	
PCB-1254 (Aroclor 1254)	ND	ug/kg	71.8	21.6	1	10/12/18 07:51	10/12/18 21:20	11097-69-1	
PCB-1260 (Aroclor 1260)	ND	ug/kg	58.4	17.5	1	10/12/18 07:51	10/12/18 21:20	11096-82-5	
PCB-1262 (Aroclor 1262)	ND	ug/kg	84.3	25.3	1	10/12/18 07:51	10/12/18 21:20	37324-23-5	
PCB-1268 (Aroclor 1268)	ND	ug/kg	79.1	23.8	1	10/12/18 07:51	10/12/18 21:20	11100-14-4	
PCB, Total	ND	ug/kg	58.4	17.5	1	10/12/18 07:51	10/12/18 21:20	1336-36-3	
Surrogates									
Tetrachloro-m-xylene (S)	76	%	48-125		1	10/12/18 07:51	10/12/18 21:20	877-09-8	
Decachlorobiphenyl (S)	74	%	30-134		1	10/12/18 07:51	10/12/18 21:20	2051-24-3	
6010 MET ICP									
Analytical Method: EPA 6010 Preparation Method: EPA 3050									
Arsenic	18.3	mg/kg	10.6	2.2	1	10/18/18 09:13	10/27/18 10:13	7440-38-2	
Cadmium	0.97J	mg/kg	1.1	0.28	1	10/18/18 09:13	10/27/18 10:13	7440-43-9	
Chromium	27.6	mg/kg	2.1	0.59	1	10/18/18 09:13	10/27/18 10:13	7440-47-3	
Copper	69.8	mg/kg	3.1	0.94	1	10/18/18 09:13	10/27/18 10:13	7440-50-8	
Lead	66.4	mg/kg	4.2	1.3	1	10/18/18 09:13	10/27/18 10:13	7439-92-1	
Nickel	18.1	mg/kg	2.1	0.49	1	10/18/18 09:13	10/27/18 10:13	7440-02-0	
Zinc	187	mg/kg	8.5	2.2	1	10/18/18 09:13	10/27/18 10:13	7440-66-6	
7471 Mercury									
Analytical Method: EPA 7471 Preparation Method: EPA 7471									
Mercury	0.17J	mg/kg	0.24	0.073	1	10/17/18 13:25	10/18/18 09:35	7439-97-6	
Dry Weight / %M by ASTM D2974									
Analytical Method: ASTM D2974									
Percent Moisture	55.2	%	0.10	0.10	1		10/18/18 13:14		
8270D MSSV PAH by SIM									
Analytical Method: EPA 8270D by SIM Preparation Method: EPA 3550									
Acenaphthene	3550	ug/kg	15.2	4.5	5	10/17/18 17:48	10/19/18 03:31	83-32-9	
Acenaphthylene	1730	ug/kg	18.3	5.5	5	10/17/18 17:48	10/19/18 03:31	208-96-8	
Anthracene	10100	ug/kg	347	104	100	10/17/18 17:48	10/19/18 14:34	120-12-7	
Benzo(a)anthracene	20100	ug/kg	800	240	100	10/17/18 17:48	10/19/18 14:34	56-55-3	
Benzo(a)pyrene	19500	ug/kg	509	153	100	10/17/18 17:48	10/19/18 14:34	50-32-8	
Benzo(b)fluoranthene	23900	ug/kg	276	83.0	100	10/17/18 17:48	10/19/18 14:34	205-99-2	
Benzo(e)pyrene	13200	ug/kg	533	160	100	10/17/18 17:48	10/19/18 14:34	192-97-2	N2
Benzo(g,h,i)perylene	11900	ug/kg	469	141	100	10/17/18 17:48	10/19/18 14:34	191-24-2	
Benzo(k)fluoranthene	9590	ug/kg	626	188	100	10/17/18 17:48	10/19/18 14:34	207-08-9	
Chrysene	19800	ug/kg	1010	303	100	10/17/18 17:48	10/19/18 14:34	218-01-9	
Dibenz(a,h)anthracene	3460	ug/kg	17.1	5.1	5	10/17/18 17:48	10/19/18 03:31	53-70-3	
Fluoranthene	51500	ug/kg	317	95.2	100	10/17/18 17:48	10/19/18 14:34	206-44-0	
Fluorene	4350	ug/kg	232	69.6	100	10/17/18 17:48	10/19/18 14:34	86-73-7	
Indeno(1,2,3-cd)pyrene	10700	ug/kg	496	149	100	10/17/18 17:48	10/19/18 14:34	193-39-5	
2-Methylnaphthalene	420	ug/kg	18.7	5.6	5	10/17/18 17:48	10/19/18 03:31	91-57-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: Saratoga Dam
Pace Project No.: 10450829

Sample: 2 **Lab ID: 10450829002** Collected: 10/03/18 12:35 Received: 10/09/18 09:20 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270D MSSV PAH by SIM									
Analytical Method: EPA 8270D by SIM Preparation Method: EPA 3550									
Naphthalene	1490	ug/kg	28.6	8.6	5	10/17/18 17:48	10/19/18 03:31	91-20-3	
Phenanthrene	35600	ug/kg	1420	427	100	10/17/18 17:48	10/19/18 14:34	85-01-8	
Pyrene	39000	ug/kg	1130	340	100	10/17/18 17:48	10/19/18 14:34	129-00-0	
Surrogates									
2-Fluorobiphenyl (S)	84	%	42-125		5	10/17/18 17:48	10/19/18 03:31	321-60-8	D3
p-Terphenyl-d14 (S)	98	%	57-125		5	10/17/18 17:48	10/19/18 03:31	1718-51-0	
350.1 Ammonia									
Analytical Method: EPA 350.1 Preparation Method: EPA 350.1									
Nitrogen, Ammonia	595	mg/kg	21.2	10.2	1	10/11/18 14:36	10/12/18 07:01	7664-41-7	
351.2 Total Kjeldahl Nitrogen									
Analytical Method: EPA 351.2 Preparation Method: EPA 351.2									
Nitrogen, Kjeldahl, Total	3550	mg/kg	223	97.8	1	10/15/18 10:16	10/16/18 15:48	7727-37-9	
353.2 Nitrogen, NO2/NO3									
Analytical Method: EPA 353.2 Preparation Method: EPA 353.2									
Nitrogen, NO2 plus NO3	ND	mg/kg	1.1	0.26	1	10/12/18 07:44	10/12/18 15:53		N3
365.1 Phosphorus, Total									
Analytical Method: EPA 365.1 Preparation Method: SM 4500P B									
Phosphorus	2000	mg/kg	140	66.3	10	10/10/18 14:00	10/11/18 09:06	7723-14-0	
Total Organic Carbon									
Analytical Method: EPA 9060A									
RPD%	0.20	%			1		10/25/18 11:29		
Total Organic Carbon	59800	mg/kg	5910	1220	1		10/25/18 11:22	7440-44-0	
Total Organic Carbon	59900	mg/kg	5880	1220	1		10/25/18 11:29	7440-44-0	
Mean Total Organic Carbon	59900	mg/kg	5910	1220	1		10/25/18 11:29	7440-44-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: Saratoga Dam

Pace Project No.: 10450829

Sample: 3 **Lab ID: 10450829003** Collected: 10/03/18 12:40 Received: 10/09/18 09:20 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8082A GCS PCB									
Analytical Method: EPA 8082A Preparation Method: EPA 3550									
PCB-1016 (Aroclor 1016)	ND	ug/kg	65.3	19.6	1	10/12/18 07:51	10/12/18 22:08	12674-11-2	
PCB-1221 (Aroclor 1221)	ND	ug/kg	82.4	24.7	1	10/12/18 07:51	10/12/18 22:08	11104-28-2	
PCB-1232 (Aroclor 1232)	ND	ug/kg	93.7	28.1	1	10/12/18 07:51	10/12/18 22:08	11141-16-5	
PCB-1242 (Aroclor 1242)	ND	ug/kg	79.5	23.9	1	10/12/18 07:51	10/12/18 22:08	53469-21-9	
PCB-1248 (Aroclor 1248)	ND	ug/kg	70.3	21.1	1	10/12/18 07:51	10/12/18 22:08	12672-29-6	
PCB-1254 (Aroclor 1254)	ND	ug/kg	68.9	20.7	1	10/12/18 07:51	10/12/18 22:08	11097-69-1	
PCB-1260 (Aroclor 1260)	ND	ug/kg	56.0	16.8	1	10/12/18 07:51	10/12/18 22:08	11096-82-5	
PCB-1262 (Aroclor 1262)	ND	ug/kg	80.9	24.3	1	10/12/18 07:51	10/12/18 22:08	37324-23-5	
PCB-1268 (Aroclor 1268)	ND	ug/kg	76.0	22.8	1	10/12/18 07:51	10/12/18 22:08	11100-14-4	
PCB, Total	ND	ug/kg	56.0	16.8	1	10/12/18 07:51	10/12/18 22:08	1336-36-3	
Surrogates									
Tetrachloro-m-xylene (S)	71	%	48-125		1	10/12/18 07:51	10/12/18 22:08	877-09-8	
Decachlorobiphenyl (S)	70	%	30-134		1	10/12/18 07:51	10/12/18 22:08	2051-24-3	
6010 MET ICP									
Analytical Method: EPA 6010 Preparation Method: EPA 3050									
Arsenic	22.1	mg/kg	10.3	2.2	1	10/18/18 09:13	10/27/18 10:20	7440-38-2	
Cadmium	0.88J	mg/kg	1.0	0.27	1	10/18/18 09:13	10/27/18 10:20	7440-43-9	
Chromium	30.0	mg/kg	2.1	0.57	1	10/18/18 09:13	10/27/18 10:20	7440-47-3	
Copper	38.4	mg/kg	3.0	0.91	1	10/18/18 09:13	10/27/18 10:20	7440-50-8	
Lead	60.0	mg/kg	4.1	1.2	1	10/18/18 09:13	10/27/18 10:20	7439-92-1	
Nickel	21.4	mg/kg	2.1	0.48	1	10/18/18 09:13	10/27/18 10:20	7440-02-0	
Zinc	157	mg/kg	8.2	2.1	1	10/18/18 09:13	10/27/18 10:20	7440-66-6	
7471 Mercury									
Analytical Method: EPA 7471 Preparation Method: EPA 7471									
Mercury	0.17J	mg/kg	0.24	0.072	1	10/17/18 13:25	10/18/18 09:37	7439-97-6	
Dry Weight / %M by ASTM D2974									
Analytical Method: ASTM D2974									
Percent Moisture	53.2	%	0.10	0.10	1		10/18/18 13:14		
8270D MSSV PAH by SIM									
Analytical Method: EPA 8270D by SIM Preparation Method: EPA 3550									
Acenaphthene	32.0	ug/kg	2.9	0.87	1	10/17/18 17:48	10/18/18 22:38	83-32-9	
Acenaphthylene	31.9	ug/kg	3.5	1.1	1	10/17/18 17:48	10/18/18 22:38	208-96-8	
Anthracene	89.1	ug/kg	3.3	1.0	1	10/17/18 17:48	10/18/18 22:38	120-12-7	
Benzo(a)anthracene	440	ug/kg	7.7	2.3	1	10/17/18 17:48	10/18/18 22:38	56-55-3	
Benzo(a)pyrene	522	ug/kg	4.9	1.5	1	10/17/18 17:48	10/18/18 22:38	50-32-8	
Benzo(b)fluoranthene	685	ug/kg	2.6	0.79	1	10/17/18 17:48	10/18/18 22:38	205-99-2	
Benzo(e)pyrene	405	ug/kg	5.1	1.5	1	10/17/18 17:48	10/18/18 22:38	192-97-2	N2
Benzo(g,h,i)perylene	381	ug/kg	4.5	1.3	1	10/17/18 17:48	10/18/18 22:38	191-24-2	
Benzo(k)fluoranthene	242	ug/kg	6.0	1.8	1	10/17/18 17:48	10/18/18 22:38	207-08-9	
Chrysene	506	ug/kg	9.7	2.9	1	10/17/18 17:48	10/18/18 22:38	218-01-9	
Dibenz(a,h)anthracene	79.2	ug/kg	3.3	0.98	1	10/17/18 17:48	10/18/18 22:38	53-70-3	
Fluoranthene	1110	ug/kg	15.2	4.6	5	10/17/18 17:48	10/19/18 11:26	206-44-0	
Fluorene	44.9	ug/kg	2.2	0.67	1	10/17/18 17:48	10/18/18 22:38	86-73-7	
Indeno(1,2,3-cd)pyrene	310	ug/kg	4.8	1.4	1	10/17/18 17:48	10/18/18 22:38	193-39-5	
2-Methylnaphthalene	22.6	ug/kg	3.6	1.1	1	10/17/18 17:48	10/18/18 22:38	91-57-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: Saratoga Dam

Pace Project No.: 10450829

Sample: 3 **Lab ID: 10450829003** Collected: 10/03/18 12:40 Received: 10/09/18 09:20 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270D MSSV PAH by SIM		Analytical Method: EPA 8270D by SIM Preparation Method: EPA 3550							
Naphthalene	ND	ug/kg	5.5	1.6	1	10/17/18 17:48	10/18/18 22:38	91-20-3	
Phenanthrene	418	ug/kg	13.6	4.1	1	10/17/18 17:48	10/18/18 22:38	85-01-8	
Pyrene	881	ug/kg	54.3	16.3	5	10/17/18 17:48	10/19/18 11:26	129-00-0	
Surrogates									
2-Fluorobiphenyl (S)	83	%	42-125		1	10/17/18 17:48	10/18/18 22:38	321-60-8	
p-Terphenyl-d14 (S)	81	%	57-125		1	10/17/18 17:48	10/18/18 22:38	1718-51-0	
350.1 Ammonia		Analytical Method: EPA 350.1 Preparation Method: EPA 350.1							
Nitrogen, Ammonia	424	mg/kg	20.2	9.8	1	10/11/18 14:36	10/12/18 07:03	7664-41-7	
351.2 Total Kjeldahl Nitrogen		Analytical Method: EPA 351.2 Preparation Method: EPA 351.2							
Nitrogen, Kjeldahl, Total	3220	mg/kg	214	93.5	1	10/15/18 10:16	10/16/18 15:49	7727-37-9	
353.2 Nitrogen, NO2/NO3		Analytical Method: EPA 353.2 Preparation Method: EPA 353.2							
Nitrogen, NO2 plus NO3	ND	mg/kg	1.1	0.25	1	10/12/18 07:44	10/12/18 15:54		N3
365.1 Phosphorus, Total		Analytical Method: EPA 365.1 Preparation Method: SM 4500P B							
Phosphorus	1460	mg/kg	118	55.8	10	10/10/18 14:00	10/11/18 09:07	7723-14-0	
Total Organic Carbon		Analytical Method: EPA 9060A							
RPD%	5.1	%			1		10/25/18 11:44		
Total Organic Carbon	59700	mg/kg	3940	816	1		10/25/18 11:36	7440-44-0	
Total Organic Carbon	62800	mg/kg	4290	888	1		10/25/18 11:44	7440-44-0	
Mean Total Organic Carbon	61300	mg/kg	4120	852	1		10/25/18 11:44	7440-44-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: Saratoga Dam
Pace Project No.: 10450829

Sample: 4 **Lab ID: 10450829004** Collected: 10/03/18 12:45 Received: 10/09/18 09:20 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8082A GCS PCB									
Analytical Method: EPA 8082A Preparation Method: EPA 3550									
PCB-1016 (Aroclor 1016)	ND	ug/kg	71.6	21.5	1	10/12/18 07:51	10/12/18 22:24	12674-11-2	
PCB-1221 (Aroclor 1221)	ND	ug/kg	90.4	27.1	1	10/12/18 07:51	10/12/18 22:24	11104-28-2	
PCB-1232 (Aroclor 1232)	ND	ug/kg	103	30.9	1	10/12/18 07:51	10/12/18 22:24	11141-16-5	
PCB-1242 (Aroclor 1242)	ND	ug/kg	87.3	26.2	1	10/12/18 07:51	10/12/18 22:24	53469-21-9	
PCB-1248 (Aroclor 1248)	ND	ug/kg	77.1	23.2	1	10/12/18 07:51	10/12/18 22:24	12672-29-6	
PCB-1254 (Aroclor 1254)	ND	ug/kg	75.7	22.7	1	10/12/18 07:51	10/12/18 22:24	11097-69-1	
PCB-1260 (Aroclor 1260)	ND	ug/kg	61.5	18.5	1	10/12/18 07:51	10/12/18 22:24	11096-82-5	
PCB-1262 (Aroclor 1262)	ND	ug/kg	88.8	26.7	1	10/12/18 07:51	10/12/18 22:24	37324-23-5	
PCB-1268 (Aroclor 1268)	ND	ug/kg	83.4	25.0	1	10/12/18 07:51	10/12/18 22:24	11100-14-4	
PCB, Total	ND	ug/kg	61.5	18.5	1	10/12/18 07:51	10/12/18 22:24	1336-36-3	
Surrogates									
Tetrachloro-m-xylene (S)	78	%	48-125		1	10/12/18 07:51	10/12/18 22:24	877-09-8	
Decachlorobiphenyl (S)	77	%	30-134		1	10/12/18 07:51	10/12/18 22:24	2051-24-3	
6010 MET ICP									
Analytical Method: EPA 6010 Preparation Method: EPA 3050									
Arsenic	13.6	mg/kg	11.1	2.3	1	10/18/18 09:13	10/27/18 10:22	7440-38-2	
Cadmium	0.92J	mg/kg	1.1	0.29	1	10/18/18 09:13	10/27/18 10:22	7440-43-9	
Chromium	30.0	mg/kg	2.2	0.62	1	10/18/18 09:13	10/27/18 10:22	7440-47-3	
Copper	66.1	mg/kg	3.3	0.98	1	10/18/18 09:13	10/27/18 10:22	7440-50-8	
Lead	38.8	mg/kg	4.4	1.3	1	10/18/18 09:13	10/27/18 10:22	7439-92-1	
Nickel	20.1	mg/kg	2.2	0.51	1	10/18/18 09:13	10/27/18 10:22	7440-02-0	
Zinc	186	mg/kg	8.9	2.3	1	10/18/18 09:13	10/27/18 10:22	7440-66-6	
7471 Mercury									
Analytical Method: EPA 7471 Preparation Method: EPA 7471									
Mercury	0.13J	mg/kg	0.25	0.074	1	10/17/18 13:25	10/18/18 09:39	7439-97-6	
Dry Weight / %M by ASTM D2974									
Analytical Method: ASTM D2974									
Percent Moisture	57.4	%	0.10	0.10	1		10/18/18 13:14		
8270D MSSV PAH by SIM									
Analytical Method: EPA 8270D by SIM Preparation Method: EPA 3550									
Acenaphthene	ND	ug/kg	15.9	4.8	5	10/17/18 17:48	10/19/18 03:52	83-32-9	
Acenaphthylene	ND	ug/kg	19.3	5.8	5	10/17/18 17:48	10/19/18 03:52	208-96-8	
Anthracene	143	ug/kg	18.3	5.5	5	10/17/18 17:48	10/19/18 03:52	120-12-7	
Benzo(a)anthracene	744	ug/kg	42.1	12.6	5	10/17/18 17:48	10/19/18 03:52	56-55-3	
Benzo(a)pyrene	1020	ug/kg	26.8	8.0	5	10/17/18 17:48	10/19/18 03:52	50-32-8	
Benzo(b)fluoranthene	1510	ug/kg	14.5	4.4	5	10/17/18 17:48	10/19/18 03:52	205-99-2	
Benzo(e)pyrene	819	ug/kg	28.0	8.4	5	10/17/18 17:48	10/19/18 03:52	192-97-2	N2
Benzo(g,h,i)perylene	770	ug/kg	24.7	7.4	5	10/17/18 17:48	10/19/18 03:52	191-24-2	
Benzo(k)fluoranthene	599	ug/kg	33.0	9.9	5	10/17/18 17:48	10/19/18 03:52	207-08-9	
Chrysene	1040	ug/kg	53.0	15.9	5	10/17/18 17:48	10/19/18 03:52	218-01-9	
Dibenz(a,h)anthracene	180	ug/kg	18.0	5.4	5	10/17/18 17:48	10/19/18 03:52	53-70-3	
Fluoranthene	2110	ug/kg	16.7	5.0	5	10/17/18 17:48	10/19/18 03:52	206-44-0	
Fluorene	ND	ug/kg	12.2	3.7	5	10/17/18 17:48	10/19/18 03:52	86-73-7	
Indeno(1,2,3-cd)pyrene	712	ug/kg	26.1	7.8	5	10/17/18 17:48	10/19/18 03:52	193-39-5	
2-Methylnaphthalene	ND	ug/kg	19.7	5.9	5	10/17/18 17:48	10/19/18 03:52	91-57-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: Saratoga Dam

Pace Project No.: 10450829

Sample: 4 **Lab ID: 10450829004** Collected: 10/03/18 12:45 Received: 10/09/18 09:20 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270D MSSV PAH by SIM		Analytical Method: EPA 8270D by SIM Preparation Method: EPA 3550							
Naphthalene	ND	ug/kg	30.1	9.0	5	10/17/18 17:48	10/19/18 03:52	91-20-3	
Phenanthrene	715	ug/kg	74.9	22.5	5	10/17/18 17:48	10/19/18 03:52	85-01-8	
Pyrene	1560	ug/kg	59.7	17.9	5	10/17/18 17:48	10/19/18 03:52	129-00-0	
Surrogates									
2-Fluorobiphenyl (S)	81	%	42-125		5	10/17/18 17:48	10/19/18 03:52	321-60-8	D3
p-Terphenyl-d14 (S)	86	%	57-125		5	10/17/18 17:48	10/19/18 03:52	1718-51-0	
350.1 Ammonia		Analytical Method: EPA 350.1 Preparation Method: EPA 350.1							
Nitrogen, Ammonia	121	mg/kg	20.1	9.7	1	10/11/18 14:36	10/12/18 07:04	7664-41-7	
351.2 Total Kjeldahl Nitrogen		Analytical Method: EPA 351.2 Preparation Method: EPA 351.2							
Nitrogen, Kjeldahl, Total	690	mg/kg	223	97.8	1	10/15/18 10:16	10/16/18 15:50	7727-37-9	
353.2 Nitrogen, NO2/NO3		Analytical Method: EPA 353.2 Preparation Method: EPA 353.2							
Nitrogen, NO2 plus NO3	ND	mg/kg	1.1	0.27	1	10/12/18 07:44	10/12/18 15:56		N3
365.1 Phosphorus, Total		Analytical Method: EPA 365.1 Preparation Method: SM 4500P B							
Phosphorus	201	mg/kg	14.2	6.8	1	10/10/18 14:00	10/11/18 09:11	7723-14-0	
Total Organic Carbon		Analytical Method: EPA 9060A							
RPD%	1.8	%			1		10/25/18 11:59		
Total Organic Carbon	18300	mg/kg	2320	480	1		10/25/18 11:51	7440-44-0	
Total Organic Carbon	18000	mg/kg	2260	468	1		10/25/18 11:59	7440-44-0	
Mean Total Organic Carbon	18200	mg/kg	2290	474	1		10/25/18 11:59	7440-44-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: Saratoga Dam
Pace Project No.: 10450829

Sample: 5 **Lab ID: 10450829005** Collected: 10/03/18 12:50 Received: 10/09/18 09:20 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8082A GCS PCB									
Analytical Method: EPA 8082A Preparation Method: EPA 3550									
PCB-1016 (Aroclor 1016)	ND	ug/kg	57.9	17.4	1	10/12/18 07:51	10/12/18 22:40	12674-11-2	
PCB-1221 (Aroclor 1221)	ND	ug/kg	73.1	21.9	1	10/12/18 07:51	10/12/18 22:40	11104-28-2	
PCB-1232 (Aroclor 1232)	ND	ug/kg	83.2	25.0	1	10/12/18 07:51	10/12/18 22:40	11141-16-5	
PCB-1242 (Aroclor 1242)	ND	ug/kg	70.6	21.2	1	10/12/18 07:51	10/12/18 22:40	53469-21-9	
PCB-1248 (Aroclor 1248)	ND	ug/kg	62.4	18.7	1	10/12/18 07:51	10/12/18 22:40	12672-29-6	
PCB-1254 (Aroclor 1254)	ND	ug/kg	61.2	18.4	1	10/12/18 07:51	10/12/18 22:40	11097-69-1	
PCB-1260 (Aroclor 1260)	ND	ug/kg	49.7	14.9	1	10/12/18 07:51	10/12/18 22:40	11096-82-5	
PCB-1262 (Aroclor 1262)	ND	ug/kg	71.8	21.6	1	10/12/18 07:51	10/12/18 22:40	37324-23-5	
PCB-1268 (Aroclor 1268)	ND	ug/kg	67.4	20.2	1	10/12/18 07:51	10/12/18 22:40	11100-14-4	
PCB, Total	ND	ug/kg	49.7	14.9	1	10/12/18 07:51	10/12/18 22:40	1336-36-3	
Surrogates									
Tetrachloro-m-xylene (S)	77	%	48-125		1	10/12/18 07:51	10/12/18 22:40	877-09-8	
Decachlorobiphenyl (S)	74	%	30-134		1	10/12/18 07:51	10/12/18 22:40	2051-24-3	
6010 MET ICP									
Analytical Method: EPA 6010 Preparation Method: EPA 3050									
Arsenic	15.6	mg/kg	9.0	1.9	1	10/18/18 09:13	10/27/18 10:25	7440-38-2	
Cadmium	0.35J	mg/kg	0.90	0.24	1	10/18/18 09:13	10/27/18 10:25	7440-43-9	
Chromium	18.1	mg/kg	1.8	0.50	1	10/18/18 09:13	10/27/18 10:25	7440-47-3	
Copper	25.1	mg/kg	2.7	0.80	1	10/18/18 09:13	10/27/18 10:25	7440-50-8	
Lead	20.8	mg/kg	3.6	1.1	1	10/18/18 09:13	10/27/18 10:25	7439-92-1	
Nickel	14.4	mg/kg	1.8	0.41	1	10/18/18 09:13	10/27/18 10:25	7440-02-0	
Zinc	79.3	mg/kg	7.2	1.8	1	10/18/18 09:13	10/27/18 10:25	7440-66-6	
7471 Mercury									
Analytical Method: EPA 7471 Preparation Method: EPA 7471									
Mercury	0.073J	mg/kg	0.21	0.064	1	10/17/18 13:25	10/18/18 09:41	7439-97-6	
Dry Weight / %M by ASTM D2974									
Analytical Method: ASTM D2974									
Percent Moisture	47.5	%	0.10	0.10	1		10/18/18 13:15		
8270D MSSV PAH by SIM									
Analytical Method: EPA 8270D by SIM Preparation Method: EPA 3550									
Acenaphthene	ND	ug/kg	2.6	0.78	1	10/17/18 17:48	10/18/18 22:59	83-32-9	
Acenaphthylene	31.7	ug/kg	3.1	0.94	1	10/17/18 17:48	10/18/18 22:59	208-96-8	
Anthracene	24.4	ug/kg	3.0	0.89	1	10/17/18 17:48	10/18/18 22:59	120-12-7	
Benzo(a)anthracene	119	ug/kg	6.8	2.1	1	10/17/18 17:48	10/18/18 22:59	56-55-3	
Benzo(a)pyrene	134	ug/kg	4.4	1.3	1	10/17/18 17:48	10/18/18 22:59	50-32-8	
Benzo(b)fluoranthene	175	ug/kg	2.4	0.71	1	10/17/18 17:48	10/18/18 22:59	205-99-2	
Benzo(e)pyrene	96.2	ug/kg	4.6	1.4	1	10/17/18 17:48	10/18/18 22:59	192-97-2	N2
Benzo(g,h,i)perylene	90.4	ug/kg	4.0	1.2	1	10/17/18 17:48	10/18/18 22:59	191-24-2	
Benzo(k)fluoranthene	57.5	ug/kg	5.4	1.6	1	10/17/18 17:48	10/18/18 22:59	207-08-9	
Chrysene	131	ug/kg	8.6	2.6	1	10/17/18 17:48	10/18/18 22:59	218-01-9	
Dibenz(a,h)anthracene	ND	ug/kg	2.9	0.88	1	10/17/18 17:48	10/18/18 22:59	53-70-3	
Fluoranthene	214	ug/kg	2.7	0.81	1	10/17/18 17:48	10/18/18 22:59	206-44-0	
Fluorene	ND	ug/kg	2.0	0.60	1	10/17/18 17:48	10/18/18 22:59	86-73-7	
Indeno(1,2,3-cd)pyrene	74.1	ug/kg	4.2	1.3	1	10/17/18 17:48	10/18/18 22:59	193-39-5	
2-Methylnaphthalene	ND	ug/kg	3.2	0.96	1	10/17/18 17:48	10/18/18 22:59	91-57-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: Saratoga Dam

Pace Project No.: 10450829

Sample: 5 **Lab ID: 10450829005** Collected: 10/03/18 12:50 Received: 10/09/18 09:20 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270D MSSV PAH by SIM		Analytical Method: EPA 8270D by SIM Preparation Method: EPA 3550							
Naphthalene	ND	ug/kg	4.9	1.5	1	10/17/18 17:48	10/18/18 22:59	91-20-3	
Phenanthrene	53.9	ug/kg	12.2	3.7	1	10/17/18 17:48	10/18/18 22:59	85-01-8	
Pyrene	206	ug/kg	9.7	2.9	1	10/17/18 17:48	10/18/18 22:59	129-00-0	
Surrogates									
2-Fluorobiphenyl (S)	79	%	42-125		1	10/17/18 17:48	10/18/18 22:59	321-60-8	
p-Terphenyl-d14 (S)	77	%	57-125		1	10/17/18 17:48	10/18/18 22:59	1718-51-0	
350.1 Ammonia		Analytical Method: EPA 350.1 Preparation Method: EPA 350.1							
Nitrogen, Ammonia	85.4	mg/kg	16.3	7.9	1	10/11/18 14:36	10/12/18 07:11	7664-41-7	
351.2 Total Kjeldahl Nitrogen		Analytical Method: EPA 351.2 Preparation Method: EPA 351.2							
Nitrogen, Kjeldahl, Total	1750	mg/kg	173	75.8	1	10/19/18 15:15	10/23/18 12:30	7727-37-9	
353.2 Nitrogen, NO2/NO3		Analytical Method: EPA 353.2 Preparation Method: EPA 353.2							
Nitrogen, NO2 plus NO3	ND	mg/kg	0.94	0.22	1	10/12/18 07:44	10/12/18 15:57		N3
365.1 Phosphorus, Total		Analytical Method: EPA 365.1 Preparation Method: SM 4500P B							
Phosphorus	410	mg/kg	113	53.7	10	10/10/18 14:00	10/11/18 09:12	7723-14-0	M6
Total Organic Carbon		Analytical Method: EPA 9060A							
RPD%	9.9	%			1		10/25/18 12:18		
Total Organic Carbon	41500	mg/kg	4180	866	1		10/25/18 12:06	7440-44-0	
Total Organic Carbon	45800	mg/kg	4200	869	1		10/25/18 12:18	7440-44-0	
Mean Total Organic Carbon	43600	mg/kg	4190	867	1		10/25/18 12:18	7440-44-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: Saratoga Dam

Pace Project No.: 10450829

Sample: 6 **Lab ID: 10450829006** Collected: 10/03/18 12:55 Received: 10/09/18 09:20 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8082A GCS PCB									
Analytical Method: EPA 8082A Preparation Method: EPA 3550									
PCB-1016 (Aroclor 1016)	ND	ug/kg	51.6	15.5	1	10/12/18 07:51	10/12/18 22:56	12674-11-2	
PCB-1221 (Aroclor 1221)	ND	ug/kg	65.2	19.6	1	10/12/18 07:51	10/12/18 22:56	11104-28-2	
PCB-1232 (Aroclor 1232)	ND	ug/kg	74.2	22.3	1	10/12/18 07:51	10/12/18 22:56	11141-16-5	
PCB-1242 (Aroclor 1242)	ND	ug/kg	62.9	18.9	1	10/12/18 07:51	10/12/18 22:56	53469-21-9	
PCB-1248 (Aroclor 1248)	ND	ug/kg	55.6	16.7	1	10/12/18 07:51	10/12/18 22:56	12672-29-6	
PCB-1254 (Aroclor 1254)	ND	ug/kg	54.6	16.4	1	10/12/18 07:51	10/12/18 22:56	11097-69-1	
PCB-1260 (Aroclor 1260)	ND	ug/kg	44.3	13.3	1	10/12/18 07:51	10/12/18 22:56	11096-82-5	
PCB-1262 (Aroclor 1262)	ND	ug/kg	64.1	19.2	1	10/12/18 07:51	10/12/18 22:56	37324-23-5	
PCB-1268 (Aroclor 1268)	ND	ug/kg	60.1	18.1	1	10/12/18 07:51	10/12/18 22:56	11100-14-4	
PCB, Total	ND	ug/kg	44.3	13.3	1	10/12/18 07:51	10/12/18 22:56	1336-36-3	
Surrogates									
Tetrachloro-m-xylene (S)	70	%	48-125		1	10/12/18 07:51	10/12/18 22:56	877-09-8	
Decachlorobiphenyl (S)	69	%	30-134		1	10/12/18 07:51	10/12/18 22:56	2051-24-3	
6010 MET ICP									
Analytical Method: EPA 6010 Preparation Method: EPA 3050									
Arsenic	15.4	mg/kg	8.3	1.8	1	10/18/18 09:13	10/27/18 10:27	7440-38-2	
Cadmium	0.31J	mg/kg	0.83	0.22	1	10/18/18 09:13	10/27/18 10:27	7440-43-9	
Chromium	22.4	mg/kg	1.7	0.46	1	10/18/18 09:13	10/27/18 10:27	7440-47-3	
Copper	30.1	mg/kg	2.5	0.74	1	10/18/18 09:13	10/27/18 10:27	7440-50-8	
Lead	23.3	mg/kg	3.3	1.0	1	10/18/18 09:13	10/27/18 10:27	7439-92-1	
Nickel	18.9	mg/kg	1.7	0.39	1	10/18/18 09:13	10/27/18 10:27	7440-02-0	
Zinc	94.0	mg/kg	6.7	1.7	1	10/18/18 09:13	10/27/18 10:27	7440-66-6	
7471 Mercury									
Analytical Method: EPA 7471 Preparation Method: EPA 7471									
Mercury	0.078J	mg/kg	0.18	0.055	1	10/17/18 13:25	10/18/18 09:44	7439-97-6	
Dry Weight / %M by ASTM D2974									
Analytical Method: ASTM D2974									
Percent Moisture	41.1	%	0.10	0.10	1		10/18/18 13:15		
8270D MSSV PAH by SIM									
Analytical Method: EPA 8270D by SIM Preparation Method: EPA 3550									
Acenaphthene	ND	ug/kg	2.3	0.69	1	10/17/18 17:48	10/18/18 23:20	83-32-9	
Acenaphthylene	ND	ug/kg	2.8	0.84	1	10/17/18 17:48	10/18/18 23:20	208-96-8	
Anthracene	ND	ug/kg	2.6	0.79	1	10/17/18 17:48	10/18/18 23:20	120-12-7	
Benzo(a)anthracene	30.0	ug/kg	6.1	1.8	1	10/17/18 17:48	10/18/18 23:20	56-55-3	
Benzo(a)pyrene	34.0	ug/kg	3.9	1.2	1	10/17/18 17:48	10/18/18 23:20	50-32-8	
Benzo(b)fluoranthene	49.0	ug/kg	2.1	0.63	1	10/17/18 17:48	10/18/18 23:20	205-99-2	
Benzo(e)pyrene	25.8	ug/kg	4.1	1.2	1	10/17/18 17:48	10/18/18 23:20	192-97-2	N2
Benzo(g,h,i)perylene	24.5	ug/kg	3.6	1.1	1	10/17/18 17:48	10/18/18 23:20	191-24-2	
Benzo(k)fluoranthene	17.4	ug/kg	4.8	1.4	1	10/17/18 17:48	10/18/18 23:20	207-08-9	
Chrysene	35.1	ug/kg	7.7	2.3	1	10/17/18 17:48	10/18/18 23:20	218-01-9	
Dibenz(a,h)anthracene	ND	ug/kg	2.6	0.78	1	10/17/18 17:48	10/18/18 23:20	53-70-3	
Fluoranthene	72.6	ug/kg	2.4	0.73	1	10/17/18 17:48	10/18/18 23:20	206-44-0	
Fluorene	ND	ug/kg	1.8	0.53	1	10/17/18 17:48	10/18/18 23:20	86-73-7	
Indeno(1,2,3-cd)pyrene	20.5	ug/kg	3.8	1.1	1	10/17/18 17:48	10/18/18 23:20	193-39-5	
2-Methylnaphthalene	ND	ug/kg	2.9	0.86	1	10/17/18 17:48	10/18/18 23:20	91-57-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: Saratoga Dam
Pace Project No.: 10450829

Sample: 6 **Lab ID: 10450829006** Collected: 10/03/18 12:55 Received: 10/09/18 09:20 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270D MSSV PAH by SIM		Analytical Method: EPA 8270D by SIM Preparation Method: EPA 3550							
Naphthalene	ND	ug/kg	4.4	1.3	1	10/17/18 17:48	10/18/18 23:20	91-20-3	
Phenanthrene	22.1	ug/kg	10.8	3.3	1	10/17/18 17:48	10/18/18 23:20	85-01-8	
Pyrene	65.1	ug/kg	8.6	2.6	1	10/17/18 17:48	10/18/18 23:20	129-00-0	
Surrogates									
2-Fluorobiphenyl (S)	69	%	42-125		1	10/17/18 17:48	10/18/18 23:20	321-60-8	
p-Terphenyl-d14 (S)	76	%	57-125		1	10/17/18 17:48	10/18/18 23:20	1718-51-0	
350.1 Ammonia		Analytical Method: EPA 350.1 Preparation Method: EPA 350.1							
Nitrogen, Ammonia	55.6	mg/kg	13.9	6.7	1	10/11/18 14:36	10/12/18 07:12	7664-41-7	
351.2 Total Kjeldahl Nitrogen		Analytical Method: EPA 351.2 Preparation Method: EPA 351.2							
Nitrogen, Kjeldahl, Total	743	mg/kg	154	67.6	1	10/19/18 15:15	10/23/18 12:34	7727-37-9	
353.2 Nitrogen, NO2/NO3		Analytical Method: EPA 353.2 Preparation Method: EPA 353.2							
Nitrogen, NO2 plus NO3	ND	mg/kg	0.84	0.20	1	10/12/18 07:44	10/12/18 15:59		N3
365.1 Phosphorus, Total		Analytical Method: EPA 365.1 Preparation Method: SM 4500P B							
Phosphorus	403	mg/kg	106	50.4	10	10/10/18 14:00	10/11/18 09:15	7723-14-0	
Total Organic Carbon		Analytical Method: EPA 9060A							
RPD%	19.2	%			1		10/25/18 12:40		
Total Organic Carbon	46100	mg/kg	4410	913	1		10/25/18 12:31	7440-44-0	
Total Organic Carbon	55800	mg/kg	4230	876	1		10/25/18 12:40	7440-44-0	
Mean Total Organic Carbon	50900	mg/kg	4320	895	1		10/25/18 12:40	7440-44-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: Saratoga Dam

Pace Project No.: 10450829

QC Batch: 303477 Analysis Method: EPA 7471
 QC Batch Method: EPA 7471 Analysis Description: 7471 Mercury
 Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

METHOD BLANK: 1772526 Matrix: Solid
 Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Mercury	mg/kg	<0.035	0.12	10/18/18 08:58	

LABORATORY CONTROL SAMPLE: 1772527

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	mg/kg	.83	0.94	113	85-115	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 1772528 1772529

Parameter	Units	MS		MSD		MS		MSD		% Rec Limits	Max		Qual
		40177448001	Spike Conc.	Spike Conc.	Result	Result	% Rec	% Rec	RPD		RPD		
Mercury	mg/kg	7.9	.969	.957	11.1	8.6	335	72	85-115	26	20	P6,R1	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: Saratoga Dam
Pace Project No.: 10450829

QC Batch: 303599 Analysis Method: EPA 6010
QC Batch Method: EPA 3050 Analysis Description: 6010 MET
Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

METHOD BLANK: 1773393 Matrix: Solid
Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Arsenic	mg/kg	<1.0	5.0	10/27/18 09:40	
Cadmium	mg/kg	<0.13	0.50	10/27/18 09:40	
Chromium	mg/kg	<0.28	1.0	10/27/18 09:40	
Copper	mg/kg	<0.44	1.5	10/27/18 09:40	
Lead	mg/kg	<0.60	2.0	10/27/18 09:40	
Nickel	mg/kg	<0.23	1.0	10/27/18 09:40	
Zinc	mg/kg	<1.0	4.0	10/27/18 09:40	

LABORATORY CONTROL SAMPLE: 1773394

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Arsenic	mg/kg	50	49.5	99	80-120	
Cadmium	mg/kg	50	49.5	99	80-120	
Chromium	mg/kg	50	49.8	100	80-120	
Copper	mg/kg	50	49.8	100	80-120	
Lead	mg/kg	50	48.7	97	80-120	
Nickel	mg/kg	50	49.5	99	80-120	
Zinc	mg/kg	50	50.4	101	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 1773395 1773396

Parameter	Units	40177448001		MSD		MS		MSD		% Rec Limits	RPD	Max RPD	Qual
		Result	Spike Conc.	Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec					
Arsenic	mg/kg	15.5	58.3	58.1	69.4	69.9	92	94	75-125	1	20		
Cadmium	mg/kg	3.0	58.3	58.1	60.0	58.5	98	95	75-125	3	20		
Chromium	mg/kg	18.4	58.3	58.1	74.5	72.9	96	94	75-125	2	20		
Copper	mg/kg	193	58.3	58.1	215	223	39	53	75-125	4	20	M0	
Lead	mg/kg	609	58.3	58.1	712	842	176	400	75-125	17	20	P6	
Nickel	mg/kg	20.8	58.3	58.1	76.1	74.3	95	92	75-125	2	20		
Zinc	mg/kg	656	58.3	58.1	783	766	218	189	75-125	2	20	P6	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: Saratoga Dam
Pace Project No.: 10450829

QC Batch: 568823 Analysis Method: EPA 8082A
QC Batch Method: EPA 3550 Analysis Description: 8082A GCS PCB
Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

METHOD BLANK: 3086792 Matrix: Solid
Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
PCB-1016 (Aroclor 1016)	ug/kg	ND	30.6	10/12/18 18:09	
PCB-1221 (Aroclor 1221)	ug/kg	ND	38.6	10/12/18 18:09	
PCB-1232 (Aroclor 1232)	ug/kg	ND	44.0	10/12/18 18:09	
PCB-1242 (Aroclor 1242)	ug/kg	ND	37.3	10/12/18 18:09	
PCB-1248 (Aroclor 1248)	ug/kg	ND	33.0	10/12/18 18:09	
PCB-1254 (Aroclor 1254)	ug/kg	ND	32.3	10/12/18 18:09	
PCB-1260 (Aroclor 1260)	ug/kg	ND	26.3	10/12/18 18:09	
PCB-1262 (Aroclor 1262)	ug/kg	ND	38.0	10/12/18 18:09	
PCB-1268 (Aroclor 1268)	ug/kg	ND	35.6	10/12/18 18:09	
Decachlorobiphenyl (S)	%.	81	30-134	10/12/18 18:09	
Tetrachloro-m-xylene (S)	%.	83	48-125	10/12/18 18:09	

LABORATORY CONTROL SAMPLE: 3086793

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
PCB-1016 (Aroclor 1016)	ug/kg	667	600	90	66-125	
PCB-1260 (Aroclor 1260)	ug/kg	667	584	88	62-125	
Decachlorobiphenyl (S)	%.			81	30-134	
Tetrachloro-m-xylene (S)	%.			83	48-125	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 3086794 3086795

Parameter	Units	10450829002		3086795		MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual	
		MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result							
PCB-1016 (Aroclor 1016)	ug/kg	ND	1490	1480	1090	1160	73	78	30-150	6	30	
PCB-1260 (Aroclor 1260)	ug/kg	ND	1490	1480	1050	1110	71	75	30-138	6	30	
Decachlorobiphenyl (S)	%.						67	68	30-134			
Tetrachloro-m-xylene (S)	%.						68	70	48-125			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: Saratoga Dam
Pace Project No.: 10450829

QC Batch: 569962 Analysis Method: EPA 8270D by SIM
QC Batch Method: EPA 3550 Analysis Description: 8270D Solid PAH by SIM MSSV
Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

METHOD BLANK: 3092638 Matrix: Solid
Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
2-Methylnaphthalene	ug/kg	ND	1.7	10/18/18 20:12	
Acenaphthene	ug/kg	ND	1.4	10/18/18 20:12	
Acenaphthylene	ug/kg	ND	1.6	10/18/18 20:12	
Anthracene	ug/kg	ND	1.6	10/18/18 20:12	
Benzo(a)anthracene	ug/kg	ND	3.6	10/18/18 20:12	
Benzo(a)pyrene	ug/kg	ND	2.3	10/18/18 20:12	
Benzo(b)fluoranthene	ug/kg	ND	1.2	10/18/18 20:12	
Benzo(e)pyrene	ug/kg	ND	2.4	10/18/18 20:12	N2
Benzo(g,h,i)perylene	ug/kg	ND	2.1	10/18/18 20:12	
Benzo(k)fluoranthene	ug/kg	ND	2.8	10/18/18 20:12	
Chrysene	ug/kg	ND	4.5	10/18/18 20:12	
Dibenz(a,h)anthracene	ug/kg	ND	1.5	10/18/18 20:12	
Fluoranthene	ug/kg	ND	1.4	10/18/18 20:12	
Fluorene	ug/kg	ND	1.0	10/18/18 20:12	
Indeno(1,2,3-cd)pyrene	ug/kg	ND	2.2	10/18/18 20:12	
Naphthalene	ug/kg	ND	2.6	10/18/18 20:12	
Phenanthrene	ug/kg	ND	6.4	10/18/18 20:12	
Pyrene	ug/kg	ND	5.1	10/18/18 20:12	
2-Fluorobiphenyl (S)	%	93	42-125	10/18/18 20:12	
p-Terphenyl-d14 (S)	%	90	57-125	10/18/18 20:12	

LABORATORY CONTROL SAMPLE: 3092639

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
2-Methylnaphthalene	ug/kg	33.3	29.3	88	40-125	
Acenaphthene	ug/kg	33.3	27.1	81	52-125	
Acenaphthylene	ug/kg	33.3	27.8	83	50-125	
Anthracene	ug/kg	33.3	31.8	95	65-125	
Benzo(a)anthracene	ug/kg	33.3	28.6	86	60-125	
Benzo(a)pyrene	ug/kg	33.3	30.9	93	69-125	
Benzo(b)fluoranthene	ug/kg	33.3	31.1	93	61-125	
Benzo(e)pyrene	ug/kg	33.3	32.5	98	71-125	N2
Benzo(g,h,i)perylene	ug/kg	33.3	32.5	97	60-125	
Benzo(k)fluoranthene	ug/kg	33.3	30.3	91	67-125	
Chrysene	ug/kg	33.3	28.7	86	67-125	
Dibenz(a,h)anthracene	ug/kg	33.3	31.1	93	63-125	
Fluoranthene	ug/kg	33.3	30.5	92	75-125	
Fluorene	ug/kg	33.3	27.7	83	54-125	
Indeno(1,2,3-cd)pyrene	ug/kg	33.3	32.7	98	63-125	
Naphthalene	ug/kg	33.3	26.9	81	49-125	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: Saratoga Dam

Pace Project No.: 10450829

LABORATORY CONTROL SAMPLE: 3092639

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Phenanthrene	ug/kg	33.3	28.8	86	65-125	
Pyrene	ug/kg	33.3	29.7	89	64-125	
2-Fluorobiphenyl (S)	%			91	42-125	
p-Terphenyl-d14 (S)	%			87	57-125	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 3092640 3092641

Parameter	Units	3092640		3092641		MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual	
		MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result							
2-Methylnaphthalene	ug/kg	ND	34.8	34.9	29.9	25.3	86	72	30-125	17	30	
Acenaphthene	ug/kg	ND	34.8	34.9	30.5	25.9	87	74	30-125	16	30	
Acenaphthylene	ug/kg	ND	34.8	34.9	30.3	23.6	87	68	30-133	25	30	
Anthracene	ug/kg	ND	34.8	34.9	32.6	34.3	94	98	30-150	5	30	
Benzo(a)anthracene	ug/kg	ND	34.8	34.9	30.5	29.1	88	84	30-150	5	30	
Benzo(a)pyrene	ug/kg	ND	34.8	34.9	32.1	32.1	92	92	30-150	0	30	
Benzo(b)fluoranthene	ug/kg	ND	34.8	34.9	32.0	30.7	92	88	30-150	4	30	
Benzo(e)pyrene	ug/kg	ND	34.8	34.9	33.3	32.4	96	93	30-150	3	30	N2
Benzo(g,h,i)perylene	ug/kg	ND	34.8	34.9	34.3	33.1	98	95	30-150	4	30	
Benzo(k)fluoranthene	ug/kg	ND	34.8	34.9	29.2	28.4	84	81	30-150	3	30	
Chrysene	ug/kg	ND	34.8	34.9	29.3	28.3	84	81	30-150	3	30	
Dibenz(a,h)anthracene	ug/kg	ND	34.8	34.9	33.1	31.8	95	91	30-131	4	30	
Fluoranthene	ug/kg	ND	34.8	34.9	31.1	31.5	89	90	30-150	1	30	
Fluorene	ug/kg	ND	34.8	34.9	30.8	28.7	89	82	30-147	7	30	
Indeno(1,2,3-cd)pyrene	ug/kg	ND	34.8	34.9	33.9	32.7	97	94	30-150	3	30	
Naphthalene	ug/kg	ND	34.8	34.9	29.3	24.3	84	70	30-131	19	30	
Phenanthrene	ug/kg	ND	34.8	34.9	31.5	30.7	90	88	30-150	2	30	
Pyrene	ug/kg	ND	34.8	34.9	32.8	31.4	94	90	30-150	4	30	
2-Fluorobiphenyl (S)	%						93	76	42-125			
p-Terphenyl-d14 (S)	%						90	87	57-125			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: Saratoga Dam

Pace Project No.: 10450829

QC Batch: 154188 Analysis Method: EPA 350.1
 QC Batch Method: EPA 350.1 Analysis Description: 350.1 Ammonia
 Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

METHOD BLANK: 610188 Matrix: Solid
 Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Nitrogen, Ammonia	mg/kg	ND	9.0	10/12/18 06:54	

LABORATORY CONTROL SAMPLE: 610187

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Nitrogen, Ammonia	mg/kg	136	137	100	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 610189 610190

Parameter	Units	10450853001 Result	MS		MSD		MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
			Spike Conc.	MS Result	MSD Spike Conc.	MSD Result						
Nitrogen, Ammonia	mg/kg	104	175	247	175	257	81	87	90-110	4	10	M1

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 610191 610192

Parameter	Units	12117117001 Result	MS		MSD		MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
			Spike Conc.	MS Result	MSD Spike Conc.	MSD Result						
Nitrogen, Ammonia	mg/kg	29600	20700	46800	20700	46800	83	83	90-110	0	10	E,M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: Saratoga Dam

Pace Project No.: 10450829

QC Batch: 154346 Analysis Method: EPA 351.2
 QC Batch Method: EPA 351.2 Analysis Description: 351.2 TKN
 Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004

METHOD BLANK: 610827 Matrix: Solid
 Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Nitrogen, Kjeldahl, Total	mg/kg	ND	100	10/16/18 15:30	

LABORATORY CONTROL SAMPLE: 610826

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Nitrogen, Kjeldahl, Total	mg/kg	1050	1030	98	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 610828 610829

Parameter	Units	610828		610829		MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		10450400001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result						
Nitrogen, Kjeldahl, Total	mg/kg	ND	1100	1100	1180	1170	101	100	90-110	1	15

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
 without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: Saratoga Dam

Pace Project No.: 10450829

QC Batch: 154860 Analysis Method: EPA 351.2
QC Batch Method: EPA 351.2 Analysis Description: 351.2 TKN
Associated Lab Samples: 10450829005, 10450829006

METHOD BLANK: 613052 Matrix: Solid

Associated Lab Samples: 10450829005, 10450829006

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Nitrogen, Kjeldahl, Total	mg/kg	ND	111	10/23/18 12:29	

LABORATORY CONTROL SAMPLE: 613051

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Nitrogen, Kjeldahl, Total	mg/kg	1110	1040	94	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 613053 613054

Parameter	Units	613053		613054		MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		10450829005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result						
Nitrogen, Kjeldahl, Total	mg/kg	1750	1810	1810	3730	3700	110	108	90-110	1	15 E

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 613055 613056

Parameter	Units	613055		613056		MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		12117319006 Result	MS Spike Conc.	MSD Spike Conc.	MS Result						
Nitrogen, Kjeldahl, Total	mg/kg	2620	1210	1210	3320	3320	58	58	90-110	0	15 1M, M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: Saratoga Dam
Pace Project No.: 10450829

QC Batch: 154227 Analysis Method: EPA 353.2
QC Batch Method: EPA 353.2 Analysis Description: 353.2 Nitrate + Nitrite
Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

METHOD BLANK: 610293 Matrix: Solid
Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Nitrogen, NO2 plus NO3	mg/kg	ND	0.50	10/12/18 15:35	N3

LABORATORY CONTROL SAMPLE: 610292

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Nitrogen, NO2 plus NO3	mg/kg	9.9	9.5	96	90-110	N3

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 610294 610295

Parameter	Units	10450400001 Result	MS	MSD	MS Result	MSD	MS % Rec	MSD	% Rec Limits	RPD	Max RPD	Qual
			Spike Conc.	Spike Conc.		Result		% Rec				
Nitrogen, NO2 plus NO3	mg/kg	ND	12	12	11.5	11.6	95	96	90-110	0	10	N3

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 610296 610297

Parameter	Units	10450853001 Result	MS	MSD	MS Result	MSD	MS % Rec	MSD	% Rec Limits	RPD	Max RPD	Qual
			Spike Conc.	Spike Conc.		Result		% Rec				
Nitrogen, NO2 plus NO3	mg/kg	0.71	11.4	11.4	11.6	11.5	96	95	90-110	1	10	N3

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: Saratoga Dam
Pace Project No.: 10450829

QC Batch: 154045 Analysis Method: EPA 365.1
QC Batch Method: SM 4500P B Analysis Description: 365.1 Phosphorus, Total
Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

METHOD BLANK: 609580 Matrix: Solid
Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Phosphorus	mg/kg	ND	6.0	10/11/18 08:54	

LABORATORY CONTROL SAMPLE: 609579

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Phosphorus	mg/kg	26.3	27.1	103	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 609581 609582

Parameter	Units	10450403001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result	Conc.	Conc.	Result	Result	% Rec	% Rec				
Phosphorus	mg/kg	6600	884	920	5650	5970	-108	-69	90-110	6	10	M6

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 609650 609651

Parameter	Units	10450829005	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result	Conc.	Conc.	Result	Result	% Rec	% Rec				
Phosphorus	mg/kg	410	43.6	44.5	485	494	171	188	90-110	2	10	M6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: Saratoga Dam

Pace Project No.: 10450829

QC Batch: 155245 Analysis Method: EPA 9060A
 QC Batch Method: EPA 9060A Analysis Description: 9060 TOC Average
 Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

METHOD BLANK: 614698 Matrix: Solid
 Associated Lab Samples: 10450829001, 10450829002, 10450829003, 10450829004, 10450829005, 10450829006

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Mean Total Organic Carbon	mg/kg	ND	302	10/25/18 10:14	

LABORATORY CONTROL SAMPLE: 614699

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mean Total Organic Carbon	mg/kg	4270	3640	85	49-151	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 614700 614701

Parameter	Units	10450829001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Mean Total Organic Carbon	mg/kg	90300	93300	105000	170000	185000	86	90	70-130	8	25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALIFIERS

Project: Saratoga Dam
Pace Project No.: 10450829

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor and percent moisture.

LOQ - Limit of Quantitation adjusted for dilution factor and percent moisture.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

LABORATORIES

PASI-G Pace Analytical Services - Green Bay
PASI-M Pace Analytical Services - Minneapolis
PASI-V Pace Analytical Services - Virginia

ANALYTE QUALIFIERS

1M The samples were kept frozen; thawed and extracted within the 6 month holding time as indicated by Minnesota Department of Agriculture Guidance Document 11 for extractions and analysis.

D3 Sample was diluted due to the presence of high levels of non-target analytes or other matrix interference.

E Analyte concentration exceeded the calibration range. The reported result is estimated.

M0 Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.

M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

M6 Matrix spike and Matrix spike duplicate recovery not evaluated against control limits due to sample dilution.

N2 The lab does not hold NELAC/TNI accreditation for this parameter.

N3 Accreditation is not offered by the relevant laboratory accrediting body for this parameter.

P6 Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.

R1 RPD value was outside control limits.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Saratoga Dam
Pace Project No.: 10450829

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
10450829001	1	EPA 3550	568823	EPA 8082A	568957
10450829002	2	EPA 3550	568823	EPA 8082A	568957
10450829003	3	EPA 3550	568823	EPA 8082A	568957
10450829004	4	EPA 3550	568823	EPA 8082A	568957
10450829005	5	EPA 3550	568823	EPA 8082A	568957
10450829006	6	EPA 3550	568823	EPA 8082A	568957
10450829001	1	EPA 3050	303599	EPA 6010	303910
10450829002	2	EPA 3050	303599	EPA 6010	303910
10450829003	3	EPA 3050	303599	EPA 6010	303910
10450829004	4	EPA 3050	303599	EPA 6010	303910
10450829005	5	EPA 3050	303599	EPA 6010	303910
10450829006	6	EPA 3050	303599	EPA 6010	303910
10450829001	1	EPA 7471	303477	EPA 7471	303535
10450829002	2	EPA 7471	303477	EPA 7471	303535
10450829003	3	EPA 7471	303477	EPA 7471	303535
10450829004	4	EPA 7471	303477	EPA 7471	303535
10450829005	5	EPA 7471	303477	EPA 7471	303535
10450829006	6	EPA 7471	303477	EPA 7471	303535
10450829001	1	ASTM D2974	570083		
10450829002	2	ASTM D2974	570083		
10450829003	3	ASTM D2974	570083		
10450829004	4	ASTM D2974	570083		
10450829005	5	ASTM D2974	570083		
10450829006	6	ASTM D2974	570083		
10450829001	1	EPA 3550	569962	EPA 8270D by SIM	570265
10450829002	2	EPA 3550	569962	EPA 8270D by SIM	570265
10450829003	3	EPA 3550	569962	EPA 8270D by SIM	570265
10450829004	4	EPA 3550	569962	EPA 8270D by SIM	570265
10450829005	5	EPA 3550	569962	EPA 8270D by SIM	570265
10450829006	6	EPA 3550	569962	EPA 8270D by SIM	570265
10450829001	1	EPA 350.1	154188	EPA 350.1	154225
10450829002	2	EPA 350.1	154188	EPA 350.1	154225
10450829003	3	EPA 350.1	154188	EPA 350.1	154225
10450829004	4	EPA 350.1	154188	EPA 350.1	154225
10450829005	5	EPA 350.1	154188	EPA 350.1	154225
10450829006	6	EPA 350.1	154188	EPA 350.1	154225
10450829001	1	EPA 351.2	154346	EPA 351.2	154372
10450829002	2	EPA 351.2	154346	EPA 351.2	154372
10450829003	3	EPA 351.2	154346	EPA 351.2	154372
10450829004	4	EPA 351.2	154346	EPA 351.2	154372
10450829005	5	EPA 351.2	154860	EPA 351.2	154913
10450829006	6	EPA 351.2	154860	EPA 351.2	154913
10450829001	1	EPA 353.2	154227	EPA 353.2	154239
10450829002	2	EPA 353.2	154227	EPA 353.2	154239
10450829003	3	EPA 353.2	154227	EPA 353.2	154239

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Saratoga Dam
Pace Project No.: 10450829

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
10450829004	4	EPA 353.2	154227	EPA 353.2	154239
10450829005	5	EPA 353.2	154227	EPA 353.2	154239
10450829006	6	EPA 353.2	154227	EPA 353.2	154239
10450829001	1	SM 4500P B	154045	EPA 365.1	154123
10450829002	2	SM 4500P B	154045	EPA 365.1	154123
10450829003	3	SM 4500P B	154045	EPA 365.1	154123
10450829004	4	SM 4500P B	154045	EPA 365.1	154123
10450829005	5	SM 4500P B	154045	EPA 365.1	154123
10450829006	6	SM 4500P B	154045	EPA 365.1	154123
10450829001	1	EPA 9060A	155245		
10450829001	1	EPA 9060A	155246		
10450829002	2	EPA 9060A	155245		
10450829002	2	EPA 9060A	155246		
10450829003	3	EPA 9060A	155245		
10450829003	3	EPA 9060A	155246		
10450829004	4	EPA 9060A	155245		
10450829004	4	EPA 9060A	155246		
10450829005	5	EPA 9060A	155245		
10450829005	5	EPA 9060A	155246		
10450829006	6	EPA 9060A	155245		
10450829006	6	EPA 9060A	155246		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

WO#: 10450829



10450829

2276298

CHAIN-OF-CUSTODY / Analytical Request Docun
The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accu

Section A

Required Client Information:

Company: AMS Associates
 Address: 739 Oakwood Hills Dr
 Email To: Fred Clark LWT
 Phone: 733-831-7506 Fax:
 Project Name: Nov 1
 Project Number: 39173
 Report To:
 Copy To:
 Purchase Order No.:
 Project Name:
 Project Number:

Section B

Required Project Information:

Report To:
 Copy To:
 Purchase Order No.:
 Project Name:
 Project Number:

Section C

Invoice Information:

Attention:
 Company Name:
 Address:
 Pace Quote Reference:
 Pace Project Manager:
 Pace Profile #:
 Regulatory Agency:
 NPDES GROUND WATER DRINKING WATER
 UST RCRA OTHER
 Site Location
 STATE:

ITEM #	Section D Required Client Information	Matrix Codes MATRIX / CODE DW WT WW P SL OL WP AR TS OT	COLLECTED		SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives Unpreserved H ₂ SO ₄ HNO ₃ HCl NaOH Na ₂ S ₂ O ₃ Methanol Other	Analysis Test ↑ Y/N ↓	Requested Analysis Filtered (Y/N)		Pace Project No./ Lab I.D.
			DATE	TIME					DATE	TIME	
1	SAMPLE ID (A-Z, 0-9 / -) Sample IDs MUST BE UNIQUE	DW	10/18	12:30							001
2		WT	10/18	12:35							002
3		WW	10/18	12:40							003
4		P	10/18	12:45							004
5		SL	10/18	12:50							005
6		OL	10/18	12:55							006
7		WP									
8		AR									
9		TS									
10		OT									
11											
12											

ADDITIONAL COMMENTS

RELINQUISHED BY / AFFILIATION DATE TIME
 [Signature] Pace 10/18 9:20 Y Y

ACCEPTED BY / AFFILIATION DATE TIME
 [Signature] Pace 10/18 9:20 Y Y

Temp in °C
 Received on: []
 Sealed Cooler (Y/N): []
 Custody (Y/N): []
 Samples Intact (Y/N): []

SAMPLER NAME AND SIGNATURE
 PRINT Name of SAMPLER: Rob Wayne
 SIGNATURE of SAMPLER: [Signature]
 DATE Signed (MM/DD/YYYY): 10/18/18

2

*Important Note: By signing this form you are accepting Pace's NET 30 day payment terms and agreeing to late charges of 1.5% per month for any invoices not paid within 30 days.

Pace Container Order #405675

Addresses

Order By :	Ship To :	Return To:
Company <u>Ayres & Associates</u>	Company <u>Ayres & Associates</u>	Company <u>Pace Analytical Minnesota</u>
Contact <u>Wayne, Rob</u>	Contact <u>Wayne, Rob</u>	Contact <u>Michels, Bob</u>
Email <u>wayner@ayresassociates.com</u>	Email <u>wayner@ayresassociates.com</u>	Email <u>bob.michels@pacelabs.com</u>
Address <u>3433 Oakwood Hills Parkway</u>	Address <u>3433 Oakwood Hills Parkway</u>	Address <u>1700 Elm Street</u>
Address 2 _____	Address 2 _____	Address 2 <u>Suite 200</u>
City <u>Eau Claire</u>	City <u>Eau Claire</u>	City <u>Minneapolis</u>
State <u>WI</u> Zip <u>54701</u>	State <u>WI</u> Zip <u>54701</u>	State <u>MN</u> Zip <u>55414</u>
Phone <u>(715) 831-7506</u>	Phone <u>(715) 831-7506</u>	Phone <u>(612)709-5046</u>

Info

Project Name <u>Saratoga Dam</u>	Due Date <u>10/02/2018</u>	Profile <u>38173</u>	Quote _____
Project Manager <u>Michels, Bob</u>	Return _____	Carrier <u>Most Economical</u>	Location _____

Trip Blanks

Include Trip Blanks

Bottle Labels

- Blank
- Pre-Printed No Sample IDs
- Pre-Printed With Sample IDs

Bottles

- Boxed Cases
- Individually Wrapped
- Grouped By Sample

Return Shipping Labels

- No Shipper Number
- With Shipper Number

Misc

- Sampling Instructions
- Custody Seal
- Temp. Blanks
- Coolers _____
- Syringes _____
- Extra Bubble Wrap
- Short Hold/Rush Stickers
- DI Water
- USDA Regulated Soils

COC Options

- Number of Blanks
- Pre-Printed

# of Samples	Matrix	Test	Container	Total	# of QC	Lot #	Notes
6	SL	Moisture	Dry Weight Container	6	0	050718-5	
6	SL	Metals	4oz. jar unpres	6	0	081318-1KM	As, Cd, Cr, Cu, Pb, Hg, Ni, Zn
6	SL	TOC	4oz. Jar unpres	6	0	081318-1KM	
6	SL	Phos, N+N, Ammonia, TKN	8oz. jar unpres	6	0	072318-1LH	
6	SL	PCBs, PAHs	8oz. jar unpres	6	0	072318-1LH	
6	SL	Particle Size Analysis/Sieve/Hydrometer	2-1 gallon ZipLocks, one inside the other	12	0		

RETURN W/ SAMPLES

Hazard Shipping Placard In Place : NO

*Sample receiving hours are Mon-Fri 7:30am-7:00pm and Sat 9:00am-1:00pm unless special arrangements are made with your project manager.

*Pace Analytical reserves the right to return hazardous, toxic, or radioactive samples to you.

*Pace Analytical reserves the right to charge for unused bottles, as well as cost associated with sample storage and disposal.

*Payment term are net 30 days.

*Please include the proposal number on the chain of custody to insure proper billing.

Sample Notes

Ship Date :	<u>09/28/2018</u>
Prepared By:	<u>HWF</u>
Verified By:	_____

Sample Condition Upon Receipt

Client Name: Ayres Associates Project #: **WO# : 10450829**

Courier: Fed Ex UPS USPS Client
 Commercial Pace Speedee Other: _____

Tracking Number: 1Z 583 44 03 7460 5739

PM: BM2 Due Date: 10/16/18
 CLIENT: AYRES ASSOC.

Custody Seal on Cooler/Box Present? Yes No Seals Intact? Yes No

Packing Material: Bubble Wrap Bubble Bags None Other: _____ Temp Blank? Yes No

Thermometer Used: G87A9170600254 G87A9155100842 Type of Ice: Wet Blue None Dry Melted

Cooler Temp Read (°C): 4.4 Cooler Temp Corrected (°C): 4.6 Biological Tissue Frozen? Yes No N/A
 Temp should be above freezing to 6°C Correction Factor: +0.2 Date and Initials of Person Examining Contents: FE 10/9/18

USDA Regulated Soil (N/A, water sample)
 Did samples originate in a quarantine zone within the United States: AL, AR, CA, FL, GA, ID, LA, MS, NC, NM, NY, OK, OR, SC, TN, TX or VA (check maps)? Yes No
 Did samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? Yes No
 if Yes to either question, fill out a Regulated Soil Checklist (F-MN-Q-338) and include with SCUR/COC paperwork.

	COMMENTS:
Chain of Custody Present? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	1.
Chain of Custody Filled Out? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	2. <u>No Analysis Performed</u>
Chain of Custody Relinquished? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	3.
Sampler Name and/or Signature on COC? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	4.
Samples Arrived within Hold Time? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	5.
Short Hold Time Analysis (<72 hr)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	6.
Rush Turn Around Time Requested? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7.
Sufficient Volume? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	8.
Correct Containers Used? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No -Pace Containers Used? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	9.
Containers Intact? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	10.
Filtered Volume Received for Dissolved Tests? <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11. Note if sediment is visible in the dissolved container
Is sufficient information available to reconcile the samples to the COC? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Matrix: <u>SL</u>	12.
All containers needing acid/base preservation have been checked? <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13. <input type="checkbox"/> HNO ₃ <input type="checkbox"/> H ₂ SO ₄ <input type="checkbox"/> NaOH Positive for Res. Chlorine? Y N
All containers needing preservation are found to be in compliance with EPA recommendation? (HNO ₃ , H ₂ SO ₄ , <2pH, NaOH >9 Sulfide, NaOH >12 Cyanide) Exceptions: VOA, Coliform, TOC/DOC Oil and Grease, DRO/8015 (water) and Dioxin/PFAS <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	Sample #
Headspace in VOA Vials (>6mm)? <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	Initial when completed: Lot # of added preservative:
Trip Blank Present? <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	14.
Trip Blank Custody Seals Present? <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	15.
Pace Trip Blank Lot # (if purchased): <u>N/A</u>	

CLIENT NOTIFICATION/RESOLUTION Field Data Required? Yes No

Person Contacted: _____ Date/Time: _____

Comments/Resolution: _____

Project Manager Review: BA VC Date: 10/19/18

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DEHNR Certification Office (i.e. out of hold, incorrect preservative, out of temp, incorrect containers).

Sample Condition Upon Receipt

Client Name: Pace MN Project #: _____

WO#: 12117109
 PM: CLJ Due Date: 10/23/18
 CLIENT: PACE MPLS

Courier: Fed Ex UPS USPS Client
 Commercial Pace Other: _____

Tracking Number: _____

Custody Seal on Cooler/Box Present? Yes No Seals Intact? Yes No

Packing Material: Bubble Wrap Bubble Bags None Other: _____ Temp Blank? Yes No

Thermometer Used: 140792808 Type of Ice: Wet Blue None Samples on ice, cooling process has begun

Cooler Temp Read °C: 0.1 Cooler Temp Corrected °C: 0.4 Biological Tissue Frozen? Yes No N/A
 Temp should be above freezing to 6°C Correction Factor: 0.3 Date and Initials of Person Examining Contents: 10/9/18 DC

Comments: Bm 10/10/18

Chain of Custody Present?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.
Chain of Custody Filled Out?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	2.
Chain of Custody Relinquished?	<input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	3.
Sampler Name and Signature on COC?	<input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	4.
Samples Arrived within Hold Time?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	5. If Fecal: <input type="checkbox"/> <8 hours <input type="checkbox"/> >8, <24 hours <input type="checkbox"/> >24 hours
Short Hold Time Analysis (<72 hr)?	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	6.
Rush Turn Around Time Requested?	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	7.
Sufficient Volume?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	8.
Correct Containers Used?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	9.
-Pace Containers Used?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	
Containers Intact?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	10.
Filtered Volume Received for Dissolved Tests?	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11. Note if sediment is visible in the dissolved containers.
Sample Labels Match COC?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	12.
-Includes Date/Time/ID/Analysis Matrix: <u>SL</u>		
All containers needing acid/base preservation will be checked and documented in the pH logbook.	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	See pH log for results and additional preservation documentation
Headspace in Methyl Mercury Container	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13.
Headspace in VOA Vials (>6mm)?	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	14.
Trip Blank Present?	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	15.
Trip Blank Custody Seals Present?	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Pace Trip Blank Lot # (if purchased): _____		

CLIENT NOTIFICATION/RESOLUTION Field Data Required? Yes No
 Person Contacted: _____ Date/Time: _____
 Comments/Resolution: _____

FECAL WAIVER ON FILE Y N TEMPERATURE WAIVER ON FILE Y N

Project Manager Review: Caitlin Jones Date: 10/10/18

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DEHNR Certification Office (i.e. out of hold, incorrect preservative, out of temp, incorrect containers)

Sample Condition Upon Receipt Form (SCUR)

Project #:

WO#: 40177349



40177349

Client Name: PACE-MN

Courier: CS Logistics Fed Ex Speedee UPS Walco
 Client Pace Other: _____

Tracking #: 1859297-1

Custody Seal on Cooler/Box Present: Yes No Seals intact: Yes No

Custody Seal on Samples Present: Yes No Seals intact: Yes No

Packing Material: Bubble Wrap Bubble Bags None Other

Thermometer Used SR-77 Type of Ice: Wet Blue Dry None Samples on ice, cooling process has begun

Cooler Temperature Uncorr: 2.0 Corr: 2.0

Temp Blank Present: Yes No Biological Tissue is Frozen: Yes No

Person examining contents:
Date: 10/10/18
Initials: JA

Temp should be above freezing to 6°C.
Biota Samples may be received at ≤ 0°C.

Chain of Custody Present:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.
Chain of Custody Filled Out:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	2.
Chain of Custody Relinquished:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	3.
Sampler Name & Signature on COC:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	4. <u>IRWD</u> <u>JA 10/10/18</u>
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	5.
- VOA Samples frozen upon receipt	<input type="checkbox"/> Yes <input type="checkbox"/> No	Date/Time:
Short Hold Time Analysis (<72hr):	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	6.
Rush Turn Around Time Requested:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7.
Sufficient Volume:		8.
For Analysis: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No MS/MSD: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A		
Correct Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	9.
-Pace Containers Used:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
-Pace IR Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	
Containers Intact:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	10.
Filtered volume received for Dissolved tests	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11.
Sample Labels match COC:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	12.
-Includes date/time/ID/Analysis Matrix: <u>S</u>		
Trip Blank Present:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13.
Trip Blank Custody Seals Present	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Pace Trip Blank Lot # (if purchased):		

Client Notification/ Resolution: _____ if checked, see attached form for additional comments
Person Contacted: _____ Date/Time: _____
Comments/ Resolution: _____

Project Manager Review: Cro Date: 10/10/18

Intra-Regional Chain of Custody



Workorder: 10450829 Workorder Name: Saratoga Dam Owner Received Date: 10/9/2018 Due Date: 10/23/2018

Received at: **Send To Lab:**
 Pace Analytical Minnesota
 1700 Elm Street
 Suite 200
 Minneapolis, MN 55414
 Phone (612)709-5046

Pace Analytical Billings MT
 150 N Ninth Street
 Billings, MT 59101
 Phone (406)254-7226

Report To:
 Bob Michels

Item	Sample ID	Sample Type	Collect Date/Time	Lab ID	Matrix	Preserved Containers						LAB USE ONLY	
						ZPK							
1		PS	10/3/2018 12:30	10450829001	Solid	1							
2		PS	10/3/2018 12:35	10450829002	Solid	1							
3		PS	10/3/2018 12:40	10450829003	Solid	1							
4		PS	10/3/2018 12:45	10450829004	Solid	1							
5		PS	10/3/2018 12:50	10450829005	Solid	1							
6		PS	10/3/2018 12:55	10450829006	Solid	1							

Requested Analysis		Comments	
Transfers	Released By	Date/Time	Received By
1	<i>[Signature]</i>	10/18/18 15:00	
2	<i>[Signature]</i>		<i>Matthew Rose</i>
3			<i>10/18/18 09:20</i>
4			

Cooler Temperature on Receipt 2.2 °C Custody Seal Y or N Received on Ice Y or N Samples Intact Y or N

***In order to maintain client confidentiality, location/name of the sampling site, sampler's name and signature may not be provided on this COC document.
 This chain of custody is considered complete as is since this information is available in the owner laboratory.

Sample Condition Upon Receipt

Client Name: Pace-MN Project #: _____

10450829

Courier: Fed Ex UPS USPS Client
 Commercial Pace Other: _____

Tracking Number: 4638 01931166

Custody Seal on Cooler/Box Present? Yes No Seals Intact? Yes No Optional: Proj. Due Date: Proj. Name:

Packing Material: Bubble Wrap Bubble Bags None Other: _____ Temp Blank? Yes No

Thermometer Used: G86A9181101159 140279186 Type of Ice: Wet Blue None Samples on ice, cooling process has begun

Cooler Temp Read: 2.2

Date and Initials of Person Examining Contents: MW 10/10/18

Cooler Temp Corrected: 2.2

Biological Tissue Frozen? Yes No

USDA Regulated Soil Yes No

Did samples originate in a quarantine zone within the United States: AL, AR, CA, FL, GA, ID, LA, MS, NC, NM, NY, OK, OR, SC, TN, TX or VA? Check maps & Circle State

Did samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? Yes No

If Yes to either question, fill out a Regulated Soil Checklist (F-MN-Q-338) and include with SCUR/COC paperwork.

	Comments:
Chain of Custody Present? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.
Chain of Custody Filled Out? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	2.
Chain of Custody Relinquished? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	3.
Sampler Name and Signature on COC? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	4.
Samples Arrived within Hold Time? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	5.
Short Hold Time Analysis (<72 hr)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	6.
Rush Turn Around Time Requested? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	7.
Sufficient Volume? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	8.
Correct Containers Used? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	9.
-Pace Containers Used? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	
Containers Intact? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	10.
Filtered Volume Received for Dissolved Tests? Note if sediment is visible in the dissolved container. <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11.
Sample Labels Match COC? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	12.
-Includes Date/Time/ID/Analysis Matrix: <u>Soil</u>	
All containers needing acid/base preservation have been checked? <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13. <input type="checkbox"/> HNO ₃ <input type="checkbox"/> H ₂ SO ₄ <input type="checkbox"/> NaOH <input type="checkbox"/> HCl
All containers needing preservation are found to be in compliance with EPA recommendation? (HNO ₃ , H ₂ SO ₄ , HCl<2; NaOH>9 Sulfide, NaOH>12 Cyanide) <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	Sample #
Exceptions: VOA, Coliform, TOC, Oil and Grease, WI-DRO (water) <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Initial when completed: _____ Lot # of added preservative: _____
Headspace in VOA Vials (>6mm)? <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	14.
Trip Blank Present? <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	15.
Trip Blank Custody Seals Present? <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Pace Trip Blank Lot # (if purchased): <u>N/A</u>	

CLIENT NOTIFICATION/RESOLUTION

Field Data Required? Yes No


Person Contacted: _____ Date/Time: _____

Comments/Resolution: _____

Project Manager Review: _____ Date: _____

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DEHNR Certification Office (i.e. out of hold, incorrect preservative, out of temp, incorrect containers)

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0	0	0	0	3	9	66	22

TEST RESULTS (ASTM D422)			
Opening Size	Percent Finer	Spec.* (Percent)	Pass? (X=Fail)
3	100		
2	100		
1.5	100		
1	100		
.75	100		
.375	100		
#4	100		
#10	100		
#20	98		
#40	97		
#60	95		
#140	89		
#200	88		
0.0301 mm.	56		
0.0204 mm.	41		
0.0121 mm.	36		
0.0087 mm.	31		
0.0063 mm.	26		
0.0032 mm.	17		
0.0013 mm.	14		

* (no specification provided)

Material Description

silt

Atterberg Limits (ASTM D 4318)

PL= NP LL= NV PI=

Classification

USCS (D 2487)= ML AASHTO (M 145)= A-4(0)

Coefficients

D₉₀= 0.1243 D₈₅= 0.0647 D₆₀= 0.0326
D₅₀= 0.0262 D₃₀= 0.0084 D₁₅= 0.0023
D₁₀= C_u= C_c=

Remarks

Date Received: 10/9/18 Date Tested: 10/16/18
Tested By: Will Thomas
Checked By: Rhonda Johnson
Title: Lab Manager

Location: 1
Sample Number: 10450826-1

Date Sampled: 10/3/18

Pace Analytical Services, Inc.

Client: Ayers Associates
Project: Saratoga Dam

Billings, MT

Project No:

Figure

GRAIN SIZE DISTRIBUTION TEST DATA

10/18/2018

Client: Ayers Associates

Project: Saratoga Dam

Location: 1

Sample Number: 10450826-1

Material Description: silt

Sample Date: 10/3/18

Date Received: 10/9/18 **PL:** NP

LL: NV

USCS Classification: ML

AASHTO Classification: A-4(0)

Grain Size Test Method: ASTM D422

Tested By: Will Thomas

Test Date: 10/16/18

Checked By: Rhonda Johnson

Title: Lab Manager

Sieve Test Data

Dry Sample and Tare (grams)	Tare (grams)	Sieve Opening Size	Weight Retained (grams)	Sieve Weight (grams)	Percent Finer		
761.78	572.38	3	0.00	0.00	100		
		2	0.00	0.00	100		
		1.5	0.00	0.00	100		
		1	0.00	0.00	100		
		.75	0.00	0.00	100		
		.375	0.35	0.00	100		
		#4	0.09	0.00	100		
		#10	0.24	0.00	100		
		51.23	0.00	#20	0.63	0.00	98
				#40	0.76	0.00	97
#60	1.18			0.00	95		
#140	2.72			0.00	89		
#200	0.93			0.00	88		

Hydrometer Test Data

Hydrometer test uses material passing #200

Percent passing #200 based upon complete sample = 88

Weight of hydrometer sample = 51.23

Automatic temperature correction

Composite correction (fluid density and meniscus height) at 20 deg. C = -7

Meniscus correction only = 0.0

Specific gravity of solids = 2.65

Hydrometer type = 152H

Hydrometer effective depth equation: $L = 16.294964 - 0.164 \times R_m$

Elapsed Time (min.)	Temp. (deg. C.)	Actual Reading	Corrected Reading	K	Rm	Eff. Depth	Diameter (mm.)	Percent Finer
2.00	20.0	40.0	33.0	0.0136	40.0	9.7	0.0301	56.3
5.00	20.0	31.0	24.0	0.0136	31.0	11.2	0.0204	40.9
15.00	20.0	28.0	21.0	0.0136	28.0	11.7	0.0121	35.8
30.00	20.0	25.0	18.0	0.0136	25.0	12.2	0.0087	30.7
60.00	20.0	22.0	15.0	0.0136	22.0	12.7	0.0063	25.6
250.00	20.0	17.0	10.0	0.0136	17.0	13.5	0.0032	17.0
1440.00	20.0	15.0	8.0	0.0136	15.0	13.8	0.0013	13.6

Pace Analytical Services, Inc.

Hydrometer Test Data (continued)

Elapsed Time (min.)	Temp. (deg. C.)	Actual Reading	Corrected Reading	K	Rm	Eff. Depth	Diameter (mm.)	Percent Finer
----------------------------	------------------------	-----------------------	--------------------------	----------	-----------	-------------------	-----------------------	----------------------


Fractional Components

Cobbles	Gravel			Sand				Fines		
	Coarse	Fine	Total	Coarse	Medium	Fine	Total	Silt	Clay	Total
0	0	0	0	0	3	9	12	66	22	88

D ₅	D ₁₀	D ₁₅	D ₂₀	D ₃₀	D ₄₀	D ₅₀	D ₆₀	D ₈₀	D ₈₅	D ₉₀	D ₉₅
		0.0023	0.0042	0.0084	0.0196	0.0262	0.0326	0.0537	0.0647	0.1243	0.2659

Fineness Modulus
0.17

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0	0	0	0	3	14	64	19

TEST RESULTS (ASTM D422)			
Opening Size	Percent Finer	Spec.* (Percent)	Pass? (X=Fail)
3	100		
2	100		
1.5	100		
1	100		
.75	100		
.375	100		
#4	100		
#10	100		
#20	99		
#40	97		
#60	95		
#140	87		
#200	83		
0.0299 mm.	57		
0.0198 mm.	47		
0.0122 mm.	32		
0.0088 mm.	27		
0.0064 mm.	22		
0.0032 mm.	15		
0.0013 mm.	12		

* (no specification provided)

Material Description

silt with sand

Atterberg Limits (ASTM D 4318)

PL= NP LL= NV PI=

Classification

USCS (D 2487)= ML AASHTO (M 145)= A-4(0)

Coefficients

D₉₀= 0.1453 D₈₅= 0.0840 D₆₀= 0.0336
D₅₀= 0.0226 D₃₀= 0.0113 D₁₅= 0.0032
D₁₀= C_u= C_c=

Remarks

Date Received: 10/9/18 Date Tested: 10/16/18
Tested By: Will Thomas
Checked By: Rhonda Johnson
Title: Lab Manager

Location: 2
Sample Number: 10450826-2

Date Sampled: 10/3/18

Pace Analytical Services, Inc.

Client: Ayers Associates
Project: Saratoga Dam

Billings, MT

Project No:

Figure

GRAIN SIZE DISTRIBUTION TEST DATA

10/18/2018

Client: Ayers Associates

Project: Saratoga Dam

Location: 2

Sample Number: 10450826-2

Material Description: silt with sand

Sample Date: 10/3/18

Date Received: 10/9/18 **PL:** NP

LL: NV

USCS Classification: ML

AASHTO Classification: A-4(0)

Grain Size Test Method: ASTM D422

Tested By: Will Thomas

Test Date: 10/16/18

Checked By: Rhonda Johnson

Title: Lab Manager

Sieve Test Data

Dry Sample and Tare (grams)	Tare (grams)	Sieve Opening Size	Weight Retained (grams)	Sieve Weight (grams)	Percent Finer		
869.47	646.17	3	0.00	0.00	100		
		2	0.00	0.00	100		
		1.5	0.00	0.00	100		
		1	0.00	0.00	100		
		.75	0.00	0.00	100		
		.375	0.00	0.00	100		
		#4	0.08	0.00	100		
		#10	0.18	0.00	100		
		50.05	0.00	#20	0.56	0.00	99
				#40	0.95	0.00	97
#60	1.02			0.00	95		
#140	3.90			0.00	87		
#200	1.81			0.00	83		

Hydrometer Test Data

Hydrometer test uses material passing #200

Percent passing #200 based upon complete sample = 83

Weight of hydrometer sample = 50.05

Automatic temperature correction

Composite correction (fluid density and meniscus height) at 20 deg. C = -7

Meniscus correction only = 0.0

Specific gravity of solids = 2.65

Hydrometer type = 152H

Hydrometer effective depth equation: $L = 16.294964 - 0.164 \times R_m$

Elapsed Time (min.)	Temp. (deg. C.)	Actual Reading	Corrected Reading	K	Rm	Eff. Depth	Diameter (mm.)	Percent Finer
2.00	20.0	41.0	34.0	0.0136	41.0	9.6	0.0299	56.6
5.00	20.0	35.0	28.0	0.0136	35.0	10.6	0.0198	46.6
15.00	20.0	26.0	19.0	0.0136	26.0	12.0	0.0122	31.6
30.00	20.0	23.0	16.0	0.0136	23.0	12.5	0.0088	26.6
60.00	20.0	20.0	13.0	0.0136	20.0	13.0	0.0064	21.6
250.00	20.0	16.0	9.0	0.0136	16.0	13.7	0.0032	14.9
1440.00	20.0	14.0	7.0	0.0136	14.0	14.0	0.0013	11.6

Pace Analytical Services, Inc.


Fractional Components

Cobbles	Gravel			Sand				Fines		
	Coarse	Fine	Total	Coarse	Medium	Fine	Total	Silt	Clay	Total
0	0	0	0	0	3	14	17	64	19	83

D ₅	D ₁₀	D ₁₅	D ₂₀	D ₃₀	D ₄₀	D ₅₀	D ₆₀	D ₈₀	D ₈₅	D ₉₀	D ₉₅
		0.0032	0.0056	0.0113	0.0162	0.0226	0.0336	0.0637	0.0840	0.1453	0.2568

Fineness Modulus
0.17

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0	0	0	0	5	11	66	18

TEST RESULTS (ASTM D422)			
Opening Size	Percent Finer	Spec.* (Percent)	Pass? (X=Fail)
3	100		
2	100		
1.5	100		
1	100		
.75	100		
.375	100		
#4	100		
#10	100		
#20	98		
#40	95		
#60	91		
#140	86		
#200	84		
0.0299 mm.	54		
0.0198 mm.	44		
0.0121 mm.	33		
0.0086 mm.	30		
0.0063 mm.	22		
0.0032 mm.	16		
0.0013 mm.	11		

* (no specification provided)

Material Description

silt with sand

Atterberg Limits (ASTM D 4318)

PL= NP LL= NV PI=

Classification

USCS (D 2487)= ML AASHTO (M 145)= A-4(0)

Coefficients

D₉₀= 0.2349 D₈₅= 0.0839 D₆₀= 0.0359
D₅₀= 0.0256 D₃₀= 0.0086 D₁₅= 0.0026
D₁₀= C_u= C_c=

Remarks

Date Received: 10/9/18 Date Tested: 10/16/18
Tested By: Will Thomas
Checked By: Rhonda Johnson
Title: Lab Manager

Location: 3
Sample Number: 10450826-3

Date Sampled: 10/3/18

Pace Analytical Services, Inc.

Client: Ayers Associates
Project: Saratoga Dam

Billings, MT

Project No:

Figure

GRAIN SIZE DISTRIBUTION TEST DATA

10/18/2018

Client: Ayers Associates

Project: Saratoga Dam

Location: 3

Sample Number: 10450826-3

Material Description: silt with sand

Sample Date: 10/3/18

Date Received: 10/9/18 **PL:** NP

LL: NV

USCS Classification: ML

AASHTO Classification: A-4(0)

Grain Size Test Method: ASTM D422

Tested By: Will Thomas

Test Date: 10/16/18

Checked By: Rhonda Johnson

Title: Lab Manager

Sieve Test Data

Dry Sample and Tare (grams)	Tare (grams)	Sieve Opening Size	Weight Retained (grams)	Sieve Weight (grams)	Percent Finer		
810.54	591.06	3	0.00	0.00	100		
		2	0.00	0.00	100		
		1.5	0.00	0.00	100		
		1	0.00	0.00	100		
		.75	0.00	0.00	100		
		.375	0.00	0.00	100		
		#4	0.00	0.00	100		
		#10	0.42	0.00	100		
		52.87	0.00	#20	1.11	0.00	98
				#40	1.58	0.00	95
#60	2.23			0.00	91		
#140	2.64			0.00	86		
#200	0.86			0.00	84		

Hydrometer Test Data

Hydrometer test uses material passing #200

Percent passing #200 based upon complete sample = 84

Weight of hydrometer sample = 52.87

Automatic temperature correction

Composite correction (fluid density and meniscus height) at 20 deg. C = -7

Meniscus correction only = 0.0

Specific gravity of solids = 2.65

Hydrometer type = 152H

Hydrometer effective depth equation: $L = 16.294964 - 0.164 \times R_m$

Elapsed Time (min.)	Temp. (deg. C.)	Actual Reading	Corrected Reading	K	Rm	Eff. Depth	Diameter (mm.)	Percent Finer
2.00	20.0	41.0	34.0	0.0136	41.0	9.6	0.0299	53.9
5.00	20.0	35.0	28.0	0.0136	35.0	10.6	0.0198	44.4
15.00	20.0	28.0	21.0	0.0136	28.0	11.7	0.0121	33.3
30.00	20.0	26.0	19.0	0.0136	26.0	12.0	0.0086	30.1
60.00	20.0	21.0	14.0	0.0136	21.0	12.9	0.0063	22.2
250.00	20.0	17.0	10.0	0.0136	17.0	13.5	0.0032	15.8
1440.00	20.0	14.0	7.0	0.0136	14.0	14.0	0.0013	11.0

Pace Analytical Services, Inc.


Fractional Components

Cobbles	Gravel			Sand				Fines		
	Coarse	Fine	Total	Coarse	Medium	Fine	Total	Silt	Clay	Total
0	0	0	0	0	5	11	16	66	18	84

D ₅	D ₁₀	D ₁₅	D ₂₀	D ₃₀	D ₄₀	D ₅₀	D ₆₀	D ₈₀	D ₈₅	D ₉₀	D ₉₅
		0.0026	0.0057	0.0086	0.0167	0.0256	0.0359	0.0624	0.0839	0.2349	0.4437

Fineness Modulus
0.26

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0	0	3	1	2	9	65	20

TEST RESULTS (ASTM D422)			
Opening Size	Percent Finer	Spec.* (Percent)	Pass? (X=Fail)
3	100		
2	100		
1.5	100		
1	100		
.75	100		
.375	97		
#4	97		
#10	96		
#20	95		
#40	94		
#60	92		
#140	87		
#200	85		
0.0299 mm.	49		
0.0200 mm.	39		
0.0119 mm.	33		
0.0088 mm.	25		
0.0063 mm.	22		
0.0032 mm.	16		
0.0013 mm.	12		

* (no specification provided)

Material Description

silt with sand

Atterberg Limits (ASTM D 4318)

PL= NP LL= NV PI=

Classification

USCS (D 2487)= ML AASHTO (M 145)= A-4(0)

Coefficients

D₉₀= 0.1784 D₈₅= 0.0746 D₆₀= 0.0385
D₅₀= 0.0304 D₃₀= 0.0106 D₁₅= 0.0028
D₁₀= C_u= C_c=

Remarks

Date Received: 10/9/18 Date Tested: 10/16/18
Tested By: Will Thomas
Checked By: Rhonda Johnson
Title: Lab Manager

Location: 4
Sample Number: 10450826-4

Date Sampled: 10/3/18

Pace Analytical Services, Inc.

Client: Ayers Associates
Project: Saratoga Dam

Billings, MT

Project No:

Figure

GRAIN SIZE DISTRIBUTION TEST DATA

10/18/2018

Client: Ayers Associates

Project: Saratoga Dam

Location: 4

Sample Number: 10450826-4

Material Description: silt with sand

Sample Date: 10/3/18

Date Received: 10/9/18 **PL:** NP

LL: NV

USCS Classification: ML

AASHTO Classification: A-4(0)

Grain Size Test Method: ASTM D422

Tested By: Will Thomas

Test Date: 10/16/18

Checked By: Rhonda Johnson

Title: Lab Manager

Sieve Test Data

Dry Sample and Tare (grams)	Tare (grams)	Sieve Opening Size	Weight Retained (grams)	Sieve Weight (grams)	Percent Finer		
799.90	622.22	3	0.00	0.00	100		
		2	0.00	0.00	100		
		1.5	0.00	0.00	100		
		1	0.00	0.00	100		
		.75	0.00	0.00	100		
		.375	4.51	0.00	97		
		#4	0.52	0.00	97		
		#10	1.29	0.00	96		
		58.60	0.00	#20	0.82	0.00	95
				#40	0.88	0.00	94
#60	1.06			0.00	92		
#140	2.70			0.00	87		
#200	1.43			0.00	85		

Hydrometer Test Data

Hydrometer test uses material passing #200

Percent passing #200 based upon complete sample = 85

Weight of hydrometer sample = 58.6

Automatic temperature correction

Composite correction (fluid density and meniscus height) at 20 deg. C = -7

Meniscus correction only = 0.0

Specific gravity of solids = 2.65

Hydrometer type = 152H

Hydrometer effective depth equation: $L = 16.294964 - 0.164 \times R_m$

Elapsed Time (min.)	Temp. (deg. C.)	Actual Reading	Corrected Reading	K	Rm	Eff. Depth	Diameter (mm.)	Percent Finer
2.00	20.0	41.0	34.0	0.0136	41.0	9.6	0.0299	49.3
5.00	20.0	34.0	27.0	0.0136	34.0	10.7	0.0200	39.2
15.00	20.0	30.0	23.0	0.0136	30.0	11.4	0.0119	33.3
30.00	20.0	24.0	17.0	0.0136	24.0	12.4	0.0088	24.6
60.00	20.0	22.0	15.0	0.0136	22.0	12.7	0.0063	21.7
250.00	20.0	18.0	11.0	0.0136	18.0	13.3	0.0032	15.9
1440.00	20.0	15.0	8.0	0.0136	15.0	13.8	0.0013	11.6

Pace Analytical Services, Inc.


Fractional Components

Cobbles	Gravel			Sand				Fines		
	Coarse	Fine	Total	Coarse	Medium	Fine	Total	Silt	Clay	Total
0	0	3	3	1	2	9	12	65	20	85

D ₅	D ₁₀	D ₁₅	D ₂₀	D ₃₀	D ₄₀	D ₅₀	D ₆₀	D ₈₀	D ₈₅	D ₉₀	D ₉₅
		0.0028	0.0049	0.0106	0.0212	0.0304	0.0385	0.0616	0.0746	0.1784	0.8076

Fineness Modulus
0.37

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0	0	0	0	1	4	60	35

TEST RESULTS (ASTM D422)			
Opening Size	Percent Finer	Spec.* (Percent)	Pass? (X=Fail)
3	100		
2	100		
1.5	100		
1	100		
.75	100		
.375	100		
#4	100		
#10	100		
#20	99		
#40	99		
#60	98		
#140	96		
#200	95		
0.0291 mm.	67		
0.0189 mm.	61		
0.0113 mm.	54		
0.0083 mm.	43		
0.0060 mm.	38		
0.0031 mm.	25		
0.0013 mm.	18		

* (no specification provided)

Material Description

silt

Atterberg Limits (ASTM D 4318)

PL= NP LL= NV PI=

Classification

USCS (D 2487)= ML AASHTO (M 145)= A-4(0)

Coefficients

D₉₀= 0.0599 D₈₅= 0.0510 D₆₀= 0.0155
D₅₀= 0.0100 D₃₀= 0.0040 D₁₅=
D₁₀= C_u= C_c=

Remarks

Date Received: 10/9/18 Date Tested: 10/16/18
Tested By: Will Thomas
Checked By: Rhonda Johnson
Title: Lab Manager

Location: 5
Sample Number: 10450826-5

Date Sampled: 10/3/18

Pace Analytical Services, Inc.

Client: Ayers Associates
Project: Saratoga Dam

Billings, MT

Project No:

Figure

GRAIN SIZE DISTRIBUTION TEST DATA

10/18/2018

Client: Ayers Associates

Project: Saratoga Dam

Location: 5

Sample Number: 10450826-5

Material Description: silt

Sample Date: 10/3/18

Date Received: 10/9/18 **PL:** NP

LL: NV

USCS Classification: ML

AASHTO Classification: A-4(0)

Grain Size Test Method: ASTM D422

Tested By: Will Thomas

Test Date: 10/16/18

Checked By: Rhonda Johnson

Title: Lab Manager

Sieve Test Data

Dry Sample and Tare (grams)	Tare (grams)	Sieve Opening Size	Weight Retained (grams)	Sieve Weight (grams)	Percent Finer		
725.65	577.23	3	0.00	0.00	100		
		2	0.00	0.00	100		
		1.5	0.00	0.00	100		
		1	0.00	0.00	100		
		.75	0.00	0.00	100		
		.375	0.00	0.00	100		
		#4	0.00	0.00	100		
		#10	0.00	0.00	100		
		52.33	0.00	#20	0.51	0.00	99
				#40	0.20	0.00	99
#60	0.25			0.00	98		
#140	1.33			0.00	96		
#200	0.54			0.00	95		

Hydrometer Test Data

Hydrometer test uses material passing #200

Percent passing #200 based upon complete sample = 95

Weight of hydrometer sample = 52.33

Automatic temperature correction

Composite correction (fluid density and meniscus height) at 20 deg. C = -7

Meniscus correction only = 0.0

Specific gravity of solids = 2.65

Hydrometer type = 152H

Hydrometer effective depth equation: $L = 16.294964 - 0.164 \times R_m$

Elapsed Time (min.)	Temp. (deg. C.)	Actual Reading	Corrected Reading	K	Rm	Eff. Depth	Diameter (mm.)	Percent Finer
2.00	20.0	44.0	37.0	0.0136	44.0	9.1	0.0291	66.8
5.00	20.0	41.0	34.0	0.0136	41.0	9.6	0.0189	61.4
15.00	20.0	37.0	30.0	0.0136	37.0	10.2	0.0113	54.2
30.00	20.0	31.0	24.0	0.0136	31.0	11.2	0.0083	43.3
60.00	20.0	28.0	21.0	0.0136	28.0	11.7	0.0060	37.9
250.00	20.0	21.0	14.0	0.0136	21.0	12.9	0.0031	25.2
1440.00	20.0	17.0	10.0	0.0136	17.0	13.5	0.0013	18.0

Pace Analytical Services, Inc.

Fractional Components

Cobbles	Gravel			Sand				Fines		
	Coarse	Fine	Total	Coarse	Medium	Fine	Total	Silt	Clay	Total
0	0	0	0	0	1	4	5	60	35	95

D5	D10	D15	D20	D30	D40	D50	D60	D80	D85	D90	D95
			0.0019	0.0040	0.0071	0.0100	0.0155	0.0442	0.0510	0.0599	0.0860

Fineness Modulus
0.07

GRAIN SIZE DISTRIBUTION TEST DATA

10/18/2018

Client: Ayers Associates

Project: Saratoga Dam

Location: 6

Sample Number: 10450826-6

Material Description: silt

Sample Date: 10/3/18

Date Received: 10/9/18 **PL:** NP

LL: NV

PI: NP

USCS Classification: ML

AASHTO Classification: A-4(0)

Grain Size Test Method: ASTM D422

Tested By: Will Thomas

Test Date: 10/16/18

Checked By: Rhonda Johnson

Title: Lab Manager

Sieve Test Data

Dry Sample and Tare (grams)	Tare (grams)	Sieve Opening Size	Weight Retained (grams)	Sieve Weight (grams)	Percent Finer		
784.05	639.70	3	0.00	0.00	100		
		2	0.00	0.00	100		
		1.5	0.00	0.00	100		
		1	0.00	0.00	100		
		.75	0.00	0.00	100		
		.375	0.00	0.00	100		
		#4	0.06	0.00	100		
		#10	0.28	0.00	100		
		59.90	0.00	#20	0.61	0.00	99
				#40	0.75	0.00	97
#60	1.12			0.00	96		
#140	2.92			0.00	91		
#200	1.02			0.00	89		

Hydrometer Test Data

Hydrometer test uses material passing #200

Percent passing #200 based upon complete sample = 89

Weight of hydrometer sample = 59.9

Automatic temperature correction

Composite correction (fluid density and meniscus height) at 20 deg. C = -7

Meniscus correction only = 0.0

Specific gravity of solids = 2.65

Hydrometer type = 152H

Hydrometer effective depth equation: $L = 16.294964 - 0.164 \times R_m$

Elapsed Time (min.)	Temp. (deg. C.)	Actual Reading	Corrected Reading	K	Rm	Eff. Depth	Diameter (mm.)	Percent Finer
2.00	20.0	51.0	44.0	0.0136	51.0	7.9	0.0272	65.4
5.00	20.0	40.0	33.0	0.0136	40.0	9.7	0.0190	49.0
15.00	20.0	35.0	28.0	0.0136	35.0	10.6	0.0114	41.6
30.00	20.0	25.0	18.0	0.0136	25.0	12.2	0.0087	26.7
60.00	20.0	25.0	18.0	0.0136	25.0	12.2	0.0062	26.7
250.00	20.0	20.0	13.0	0.0136	20.0	13.0	0.0031	19.3
1440.00	20.0	16.0	9.0	0.0136	16.0	13.7	0.0013	13.3

Pace Analytical Services, Inc.

Fractional Components

Cobbles	Gravel			Sand				Fines		
	Coarse	Fine	Total	Coarse	Medium	Fine	Total	Silt	Clay	Total
0	0	0	0	0	3	8	11	65	24	89

D ₅	D ₁₀	D ₁₅	D ₂₀	D ₃₀	D ₄₀	D ₅₀	D ₆₀	D ₈₀	D ₈₅	D ₉₀	D ₉₅
		0.0021	0.0034	0.0094	0.0111	0.0197	0.0245	0.0402	0.0510	0.0894	0.2211

Fineness Modulus
0.14



Attachment C

SITE EXHIBIT FRAME PARK

LOCATED ALONG THE FOX RIVER, IN THE CITY OF WAUKESHA, WAUKESHA COUNTY, WISCONSIN.


STORM AND SANITARY SEWERS ARE SHOWN PER PLANS FROM THE CITY OF WAUKESHA.

PREPARED FOR: POWRTEK ENGINEERING, INC.
DATE: APRIL 15, 2022
DRAWING NO: 168724-KAC



LEGEND

- BOLLARD
- + SOIL BORING/MONITORING WELL
- ⌵ FLAGPOLE
- ✉ MAILBOX
- ⌵ SIGN
- ⊠ AIR CONDITIONER
- ⊠ CONTROL BOX
- ⊠ TRAFFIC SIGNAL
- ⊠ CABLE PEDESTAL
- ⊠ POWER POLE
- ⌵ GUY WIRE
- ⌵ GUY WIRE
- ⌵ LIGHT POLE
- ⊠ SPOT/YARD/PEDESTAL LIGHT
- ⊠ HANDICAPPED PARKING
- ELECTRIC MANHOLE
- ⊠ ELECTRIC PEDESTAL
- ⊠ ELECTRIC METER
- ⊠ ELECTRIC TRANSFORMER
- ⊠ TELEPHONE MANHOLE
- ⊠ TELEPHONE PEDESTAL
- ⊠ UTILITY VAULT
- ⊠ GAS VALVE
- ⊠ GAS METER
- ⊠ GAS WARNING SIGN
- ⊠ STORM MANHOLE
- ROUND INLET
- ⊠ SQUARE INLET
- ⌵ STORM SEWER END SECTION
- SANITARY MANHOLE
- ⌵ SANITARY CLEANOUT OR SEPTIC VENT
- ⊠ SANITARY INTERCEPTOR MANHOLE
- ⊠ MISCELLANEOUS MANHOLE
- ⌵ ELECTRIC OUTLET
- ⊠ WATER VALVE
- ⊠ HYDRANT
- ⊠ WATER SERVICE CURB STOP
- ⊠ WATER MANHOLE
- ⌵ WELL
- ⌵ WATER SURFACE
- ⊠ WETLANDS FLAG
- ⊠ MARSH
- ★ CONIFEROUS TREE
- DECIDUOUS TREE
- SHRUB
- EDGE OF TREES
- S—SANITARY SEWER
- STO—STORM SEWER
- W—WATERMAIN
- G—MARKED GAS MAIN
- E—MARKED ELECTRIC
- OHW—OVERHEAD WIRES
- B—BUREAU ELEC. SERV.
- T—MARKED TELEPHONE
- TV—MARKED CABLE TV LINE
- FO—MARKED FIBER OPTIC
- INDICATES EXISTING CONTOUR ELEVATION
- 780— INDICATES EXISTING SPOT ELEVATION
- × 780.55—



DIGGERS HOTLINE TICKET NOS: 20221205518 & 5522

THE UNDERGROUND UTILITY INFORMATION AS SHOWN HEREON IS BASED, IN PART, UPON INFORMATION FURNISHED BY UTILITY COMPANIES AND THE LOCAL MUNICIPALITY. WHILE THIS INFORMATION IS BELIEVED TO BE RELIABLE, ITS ACCURACY AND COMPLETENESS CANNOT BE GUARANTEED NOR CERTIFIED TO.

(P) INDICATES PIPE SIZES PER RECORD PLANS. OTHER PIPE SIZES ARE ESTIMATED. NO PIPE SIZES SHOULD BE RELIED UPON WITHOUT FURTHER VERIFICATION.


raSmith
CREATIVITY BEYOND ENGINEERING

16745 W. Bluemound Road
Brookfield, WI 53005-5938
(262) 781-1000
rasmith.com

SITE EXHIBIT



FRAME PARK

LOCATED ALONG THE FOX RIVER, IN THE CITY OF WAUKESHA, WAUKESHA COUNTY, WISCONSIN.
 STORM AND SANITARY SEWERS ARE SHOWN PER PLANS FROM THE CITY OF WAUKESHA.
 PREPARED FOR: POWRTEK ENGINEERING, INC.
 DATE: APRIL 15, 2022
 DRAWING NO: 168724-KAC



FOX RIVER

FRAME PARK DR.



DIGGERS HOTLINE TICKET NOS: 20221205518 & 5522

THE UNDERGROUND UTILITY INFORMATION AS SHOWN HEREON IS BASED, IN PART, UPON INFORMATION FURNISHED BY UTILITY COMPANIES AND THE LOCAL MUNICIPALITY. WHILE THIS INFORMATION IS BELIEVED TO BE RELIABLE, ITS ACCURACY AND COMPLETENESS CANNOT BE GUARANTEED NOR CERTIFIED TO.

(P) INDICATES PIPE SIZES PER RECORD PLANS. OTHER PIPE SIZES ARE ESTIMATED. NO PIPE SIZES SHOULD BE RELIED UPON WITHOUT FURTHER VERIFICATION.




raSmith
 CREATIVITY BEYOND ENGINEERING

16745 W. Bluemound Road
 Brookfield, WI 53005-5938
 (262) 781-1000
 rasmith.com

SITE EXHIBIT

FRAME PARK

LOCATED ALONG THE FOX RIVER, IN THE CITY OF WAUKESHA, WAUKESHA COUNTY, WISCONSIN.
 STORM AND SANITARY SEWERS ARE SHOWN PER PLANS FROM THE CITY OF WAUKESHA.
 PREPARED FOR: POWRTEK ENGINEERING, INC.
 DATE: APRIL 15, 2022
 DRAWING NO: 168724-KAC



DIGGERS HOTLINE TICKET NOS: 20221205518 & 5522

THE UNDERGROUND UTILITY INFORMATION AS SHOWN HEREON IS BASED, IN PART, UPON INFORMATION FURNISHED BY UTILITY COMPANIES AND THE LOCAL MUNICIPALITY. WHILE THIS INFORMATION IS BELIEVED TO BE RELIABLE, ITS ACCURACY AND COMPLETENESS CANNOT BE GUARANTEED NOR CERTIFIED TO.
 (P) INDICATES PIPE SIZES PER RECORD PLANS. OTHER PIPE SIZES ARE ESTIMATED. NO PIPE SIZES SHOULD BE RELIED UPON WITHOUT FURTHER VERIFICATION.

raSmith
 CREATIVITY BEYOND ENGINEERING
 16745 W. Bluemound Road
 Brookfield, WI 53005-5938
 (262) 781-1000
 rasmith.com

S:\168724\dwg\SX101D.dwg, SHEET 3, 9/27/2022 1:41:33 PM, NWD